

NFPA[®]

13R

Standard for the
Installation of Sprinkler Systems
in Low-Rise Residential Occupancies

2022



NFPA[®] 13R

Standard for the Installation of Sprinkler Systems in Low-Rise Residential Occupancies

2022 Edition



NFPA, 1 Batterymarch Park, Quincy, MA 02169-7471
An International Codes and Standards Organization

IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA® STANDARDS




NFPA® codes, standards, recommended practices, and guides (“NFPA Standards”), of which the document contained herein is one, are developed through a consensus standards development process approved by the American National Standards Institute. This process brings together volunteers representing varied viewpoints and interests to achieve consensus on fire and other safety issues. While the NFPA administers the process and establishes rules to promote fairness in the development of consensus, it does not independently test, evaluate, or verify the accuracy of any information or the soundness of any judgments contained in NFPA Standards.

The NFPA disclaims liability for any personal injury, property, or other damages of any nature whatsoever, whether special, indirect, consequential or compensatory, directly or indirectly resulting from the publication, use of, or reliance on NFPA Standards. The NFPA also makes no guaranty or warranty as to the accuracy or completeness of any information published herein.

In issuing and making NFPA Standards available, the NFPA is not undertaking to render professional or other services for or on behalf of any person or entity. Nor is the NFPA undertaking to perform any duty owed by any person or entity to someone else. Anyone using this document should rely on his or her own independent judgment or, as appropriate, seek the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

The NFPA has no power, nor does it undertake, to police or enforce compliance with the contents of NFPA Standards. Nor does the NFPA list, certify, test, or inspect products, designs, or installations for compliance with this document. Any certification or other statement of compliance with the requirements of this document shall not be attributable to the NFPA and is solely the responsibility of the certifier or maker of the statement.

REVISION SYMBOLS IDENTIFYING CHANGES FROM THE PREVIOUS EDITION

Text revisions are shaded. A  before a section number indicates that words within that section were deleted and a  to the left of a table or figure number indicates a revision to an existing table or figure. When a chapter was heavily revised, the entire chapter is marked throughout with the  symbol. Where one or more sections were deleted, a • is placed between the remaining sections. Chapters, annexes, sections, figures, and tables that are new are indicated with an **N**.

Note that these indicators are a guide. Rearrangement of sections may not be captured in the markup, but users can view complete revision details in the First and Second Draft Reports located in the archived revision information section of each code at www.nfpa.org/docinfo. Any subsequent changes from the NFPA Technical Meeting, Tentative Interim Amendments, and Errata are also located there.

REMINDER: UPDATING OF NFPA STANDARDS

Users of NFPA codes, standards, recommended practices, and guides (“NFPA Standards”) should be aware that these documents may be superseded at any time by the issuance of a new edition, may be amended with the issuance of Tentative Interim Amendments (TIAs), or be corrected by Errata. It is intended that through regular revisions and amendments, participants in the NFPA standards development process consider the then-current and available information on incidents, materials, technologies, innovations, and methods as these develop over time and that NFPA Standards reflect this consideration. Therefore, any previous edition of this document no longer represents the current NFPA Standard on the subject matter addressed. NFPA encourages the use of the most current edition of any NFPA Standard [as it may be amended by TIA(s) or Errata] to take advantage of current experience and understanding. An official NFPA Standard at any point in time consists of the current edition of the document, including any issued TIAs and Errata then in effect.

To determine whether an NFPA Standard has been amended through the issuance of TIAs or corrected by Errata, visit the “Codes & Standards” section at www.nfpa.org.

ADDITIONAL IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA® STANDARDS

Updating of NFPA Standards

Users of NFPA codes, standards, recommended practices, and guides (“NFPA Standards”) should be aware that these documents may be superseded at any time by the issuance of a new edition, may be amended with the issuance of Tentative Interim Amendments (TIAs), or be corrected by Errata. It is intended that through regular revisions and amendments, participants in the NFPA standards development process consider the then-current and available information on incidents, materials, technologies, innovations, and methods as these develop over time and that NFPA Standards reflect this consideration. Therefore, any previous edition of this document no longer represents the current NFPA Standard on the subject matter addressed. NFPA encourages the use of the most current edition of any NFPA Standard [as it may be amended by TIA(s) or Errata] to take advantage of current experience and understanding. An official NFPA Standard at any point in time consists of the current edition of the document, including any issued TIAs and Errata then in effect.

To determine whether an NFPA Standard has been amended through the issuance of TIAs or corrected by Errata, visit the “Codes & Standards” section at www.nfpa.org.

Interpretations of NFPA Standards

A statement, written or oral, that is not processed in accordance with Section 6 of the Regulations Governing the Development of NFPA Standards shall not be considered the official position of NFPA or any of its Committees and shall not be considered to be, nor be relied upon as, a Formal Interpretation.

Patents

The NFPA does not take any position with respect to the validity of any patent rights referenced in, related to, or asserted in connection with an NFPA Standard. The users of NFPA Standards bear the sole responsibility for determining the validity of any such patent rights, as well as the risk of infringement of such rights, and the NFPA disclaims liability for the infringement of any patent resulting from the use of or reliance on NFPA Standards.

NFPA adheres to the policy of the American National Standards Institute (ANSI) regarding the inclusion of patents in American National Standards (“the ANSI Patent Policy”), and hereby gives the following notice pursuant to that policy:

NOTICE: The user’s attention is called to the possibility that compliance with an NFPA Standard may require use of an invention covered by patent rights. NFPA takes no position as to the validity of any such patent rights or as to whether such patent rights constitute or include essential patent claims under the ANSI Patent Policy. If, in connection with the ANSI Patent Policy, a patent holder has filed a statement of willingness to grant licenses under these rights on reasonable and nondiscriminatory terms and conditions to applicants desiring to obtain such a license, copies of such filed statements can be obtained, on request, from NFPA. For further information, contact the NFPA at the address listed below.

Law and Regulations

Users of NFPA Standards should consult applicable federal, state, and local laws and regulations. NFPA does not, by the publication of its codes, standards, recommended practices, and guides, intend to urge action that is not in compliance with applicable laws, and these documents may not be construed as doing so.

Copyrights

NFPA Standards are copyrighted. They are made available for a wide variety of both public and private uses. These include both use, by reference, in laws and regulations, and use in private self-regulation, standardization, and the promotion of safe practices and methods. By making these documents available for use and adoption by public authorities and private users, the NFPA does not waive any rights in copyright to these documents.

Use of NFPA Standards for regulatory purposes should be accomplished through adoption by reference. The term “adoption by reference” means the citing of title, edition, and publishing information only. Any deletions, additions, and changes desired by the adopting authority should be noted separately in the adopting instrument. In order to assist NFPA in following the uses made of its documents, adopting authorities are requested to notify the NFPA (Attention: Secretary, Standards Council) in writing of such use. For technical assistance and questions concerning adoption of NFPA Standards, contact NFPA at the address below.

For Further Information

All questions or other communications relating to NFPA Standards and all requests for information on NFPA procedures governing its codes and standards development process, including information on the procedures for requesting Formal Interpretations, for proposing Tentative Interim Amendments, and for proposing revisions to NFPA standards during regular revision cycles, should be sent to NFPA headquarters, addressed to the attention of the Secretary, Standards Council, NFPA, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02269-9101; email: stds_admin@nfpa.org.

For more information about NFPA, visit the NFPA website at www.nfpa.org. All NFPA codes and standards can be viewed at no cost at www.nfpa.org/docinfo.

Copyright © 2021 National Fire Protection Association®. All Rights Reserved.

NFPA® 13R

Standard for the

Installation of Sprinkler Systems in Low-Rise Residential Occupancies

2022 Edition

This edition of NFPA 13R, *Standard for the Installation of Sprinkler Systems in Low-Rise Residential Occupancies*, was prepared by the Technical Committee on Residential Sprinkler Systems and released by the Correlating Committee on Automatic Sprinkler Systems. It was issued by the Standards Council on March 18, 2021, with an effective date of April 8, 2021, and supersedes all previous editions.

This edition of NFPA 13R was approved as an American National Standard on April 8, 2021.

Origin and Development of NFPA 13R

The first edition of NFPA 13R, published in 1989, represented a milestone in the development of sprinkler installation design standards. The first edition resulted in a standard for the protection of low-rise residential facilities.

This standard is intended to provide a high degree of life safety and property protection to the inhabitants of low-rise multifamily dwellings. Promulgated as a document that provides for increased levels of protection to building occupants, the document also considers the economic aspects of a sprinklered facility as compared to an unsprinklered facility.

As the number of states and cities that implements sprinkler ordinances continues to grow, and as the threshold levels for sprinkler requirements in residential occupancies in the building codes extend to certain low-rise structures, it is believed that systems for certain residential occupancies can be installed efficiently and effectively in accordance with this standard.

The 1994 edition provided expanded information on nonmetallic pipe materials, made minor changes to clarify the established design criteria, and added a new recommendation on underground pipe materials.

The 1996 edition included several changes that paralleled amendments in the 1996 edition of NFPA 13, *Standard for the Installation of Sprinkler Systems*. Other changes included a number of clarifications concerning the selection of sprinklers as well as the proper use of sprinklers.

The 1999 edition clarified criteria for nonmetallic pipe and fittings and established a minimum operating pressure for sprinklers. Guidance on providing freeze protection using insulation in attics and antifreeze systems was provided, as was information on the application of solvent cement for nonmetallic piping. Exceptions were added for omitting sprinkler coverage in closets, on balconies, and underneath garage doors.

The 2002 edition incorporated revisions to update the standard to comply with the 2000 edition of the *Manual of Style for NFPA Technical Committee Documents*. These revisions included rewording exceptions as requirements. The 2002 edition also included changes that further clarified the scope of the standard, established a minimum design discharge density, and added protection requirements specifically for garages. The section addressing spaces where sprinklers are permitted to be omitted was changed so that the area of full-height tub/shower enclosures would be included in the area determination for bathrooms, sprinklers would be provided in concealed spaces with fuel-fired equipment, and the omission of sprinklers in elevator machine rooms would not be dependent on the room's location.

The 2007 edition included spacing and obstruction rules addressing sloped ceilings, ceiling pockets, ceiling fans, and kitchen cabinets. Also, the requirements for using quick-response sprinklers within NFPA 13R regulations were clarified, and new requirements addressing architectural features in dwelling units were added. Additionally, the requirements covering closets, including obstructions within closets and protection of mechanical closets, were clarified. Finally,

new NFPA 13 requirements were added that apply to NFPA 13R to ensure proper administration of those requirements where relevant.

The 2010 edition was reorganized, dividing material on installation, discharge, plans and calculation, water supplies, acceptance testing, and care and maintenance into separate chapters. Clarification was provided in the Annex A material of Chapter 1 for assistance in determining when NFPA 13R applies and establishing that the building code defines the structure. NFPA 13R is used after such determination has been made. Further clarification was added stating that sprinklers are not required on balconies or balcony closets.

The 2013 edition revised the title to address low-rise residential occupancies instead of addressing the number of stories outlined in the document scope. Several sections were added to address the concept of shadow areas in different configurations within NFPA 13R protected structures. The requirements for locations of sprinklers were updated to provide specific direction on protection of porte cocheres, closets, and areas outside the dwelling unit. New language addressing the number of heads to be calculated for certain sloped and beamed ceiling configurations was added based on a Fire Protection Research Foundation report.

Several significant revisions were made during the development of the 2016 edition. The definition of sprinkler system was revised to correlate with NFPA 13 and NFPA 25. The Annex A text for the scope statement of the document was significantly revised to address mixed-use buildings and the applicability of NFPA 13R systems. Clarification was added that once a sprinkler is removed from a fitting or welded outlet it should not be reinstalled if torque was applied to the sprinkler itself. Nonmetallic piping compatibility language was updated for consistency with NFPA 13. The section addressing sprinkler protection outside dwelling units was reorganized and restructured to make it easier for the user to follow. Language was added to address sprinkler protection where the device is intended to protect a glazing assembly. One of the largest changes to the 2016 edition of NFPA 13R was the review of all metric conversions. Historically the document had used an “exact” conversion process, but in the 2016 edition an approximate conversion process was used. The intent of this change was to make the document more usable outside the United States.

The 2019 edition added a new definition for carport, as well as several new requirements that address where pipe and tube, listed for light hazard, can be used in an ordinary hazard application; beam rules for sprinklers installed under and adjacent to beams (along with new figures); waste and linen systems; installation of fuel-fired equipment; and obstructions in hallways.

Chapter 9, Water Supplies, was reorganized, and the domestic demand tables were moved from the annex to the body of the standard, and values were updated. In addition, new images clarifying sprinkler location and clearances needed around fireplaces were added.

The 2022 edition includes a revised method for determining when system components are subject to freezing and needing protection, which will require the use of current temperature data. Criteria for the protection of pipes or tubes from mechanical damage has been added to Chapter 5. Ceiling pocket protection criteria for quick-response sprinklers has been added to Chapter 6, and the obstruction tables have been modified for ease of use. A new section on system operational tests and main drain valves has been added to Chapter 10 for system acceptance. The Contractor’s Material and Test Certificate for Aboveground Piping has been relocated to Annex A. In addition, the fire data tables of A.1.2 have been updated with the most current information.

Correlating Committee on Automatic Sprinkler Systems

William E. Koffel, *Chair*
Koffel Associates, Inc, MD [SE]

Roland A. Asp, National Fire Sprinkler Association, Inc., MD [M]
Rep. National Fire Sprinkler Association

Jose R. Baz, JRB Associates Group Inc., FL [M]
Rep. NFPA Latin American Section

Kerry M. Bell, UL LLC, IL [RT]

Tracey D. Bellamy, Telgian Corporation, GA [U]
Rep. The Home Depot

Chase A. Browning, Medford Fire Department, OR [E]

Steven W. Dellasanta, Jensen Hughes Associates, Inc., RI [SE]

John August Denhardt, American Fire Sprinkler Association (AFSA), TX [IM]
Rep. American Fire Sprinkler Association

Michael J. Friedman, Friedman Consulting, Inc, MD [SE]

Alex Hoffman, Viking Fire Protection Inc., Canada [IM]
Rep. Canadian Automatic Sprinkler Association

Sultan M. Javeri, SC Engineering, France [IM]

Charles W. Ketner, National Automatic Sprinkler Fitters LU 669, MD [L]

Rep. United Assn. of Journeymen & Apprentices of the Plumbing & Pipe Fitting Industry

James D. Lake, Viking Corporation, MI [M]

John A. LeBlanc, FM Global, MA [I]

Kenneth W. Linder, Swiss Re, CT [I]

David O. Lowrey, City of Boulder Fire Rescue, CO [E]

Bryan Edwin Matthews, Liberty Mutual Group, NY [I]

Garner A. Palenske, Wiss Janney Elstner Associates, Inc., CA [SE]

Lawrence Richard Phillips, US Department of the Navy, VA [E]

Adam Seghi, Coda Risk Analysis, TX [I]

Joseph Su, National Research Council of Canada, Canada [RT]

J. Michael Thompson, GHD/The Protection Engineering Group, PC, VA [SE]

Alternates

Ralph E. Bless, Jr., Telgian Corporation, GA [U]
(Alt. to Tracey D. Bellamy)

Bruce H. Clarke, American International Group, Inc. (AIG), SC [I]
(Alt. to Adam Seghi)

Russell P. Fleming, Northeast Fire Suppression Associates, LLC, NH [SE]
(Alt. to Michael J. Friedman)

Scott T. Franson, The Viking Corporation, MI [M]
(Alt. to James D. Lake)

David B. Fuller, FM Approvals, RI [I]
(Alt. to John A. LeBlanc)

Jeffrey E. Harper, JENSEN HUGHES, IL [SE]
(Alt. to Steven W. Dellasanta)

Jeff Hebenstreit, UL LLC, IL [RT]
(Alt. to Kerry M. Bell)

Jeffrey M. Hugo, National Fire Sprinkler Association, Inc., MI [M]
(Alt. to Roland A. Asp)

Jack A. Medovich, Fire & Life Safety America, MD [IM]
(Alt. to John August Denhardt)

Donato A. Pirro, Electro Sistemas De Panama, S.A., Panama [M]
(Alt. to Jose R. Baz)

Jason W. Ryckman, Canadian Automatic Sprinkler Association, Canada [IM]
(Alt. to Alex Hoffman)

Douglas Paul Stultz, US Department of the Navy, VA [E]
(Alt. to Lawrence Richard Phillips)

Jeffrey J. Van Rhyn, Jr., Local 669 JATC, NV [L]
(Alt. to Charles W. Ketner)

Nonvoting

James B. Biggins, TUV SUD America Inc./Global Risk Consultants Corporation, IL [SE]
Rep. TC on Hanging & Bracing of Water-Based Systems

Christopher I. Deneff, FM Global, RI [I]
Rep. TC on Hanging & Bracing of Water-Based Systems

Raymond A. Grill, Arup, DC [SE]
Rep. TC on Sprinkler System Installation Criteria

Kenneth E. Isman, University of Maryland, MD [SE]
Rep. TC on Residential Sprinkler Systems

Chad Duffy, NFPA Staff Liaison

Russell B. Leavitt, Telgian Corporation, AZ [U]
Rep. TC on Sprinkler System Discharge Criteria

John J. Walsh, UA Joint Apprenticeship Committee Local 669, MD [SE]
Rep. United Assn. of Journeymen & Apprentices of the Plumbing & Pipe Fitting Industry
(Member Emeritus)

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have overall responsibility for documents that pertain to the criteria for the design and installation of automatic, open and foam-water sprinkler systems including the character and adequacy of water supplies, and the selection of sprinklers, piping, valves, and all materials and accessories. This Committee does not cover the installation of tanks and towers, nor the installation, maintenance, and use of

central station, proprietary, auxiliary, and local signaling systems for watchmen, fire alarm, supervisory service, nor the design of fire department hose connections.

Technical Committee on Residential Sprinkler Systems

Kenneth E. Isman, *Chair*
University of Maryland, MD [SE]

Roland A. Asp, National Fire Sprinkler Association, Inc., MD [M]
Kerry M. Bell, UL LLC, IL [RT]
Fred Benn, Advanced Automatic Sprinkler, Inc., CA [IM]
Jonathan C. Bittenbender, REHAU Incorporated, VA [M]
Chase A. Browning, Medford Fire Department, OR [E]
Bradford T. Cronin, Newport Fire Department, RI [E]
John August Denhardt, American Fire Sprinkler Association (AFSA), TX [IM]
 Rep. American Fire Sprinkler Association
Jeffrey Feid, State Farm Insurance Company, IL [I]
Cesar Lujan, National Association of Home Builders (NAHB), DC [U]
 Rep. National Association of Home Builders
Michael O'Brian, Brighton Area Fire Authority, MI [E]
 Rep. International Association of Fire Chiefs
Wade Palazini, JENSEN HUGHES, RI [SE]
Darren Palmieri, The Viking Corporation, MI [M]
Maurice M. Pilette, Mechanical Designs Ltd., MA [SE]
Milosh T. Puchovsky, Worcester Polytechnic Institute, MA [SE]
Jason W. Ryckman, Canadian Automatic Sprinkler Association, Canada [IM]
 Rep. Canadian Automatic Sprinkler Association

Peter T. Schwab, Wayne Automatic Fire Sprinklers, Inc., FL [IM]
Eric J. Skare, Uponor, Inc., MN [M]
George W. Stanley, Wiginton Fire Protection Engineering, Inc., FL [IM]
Donald R. Townley, Lubrizol, OH [M]
Martin C. W. Trim, Barrett Engineered Pumps, CA [SE]
 Rep. American Society of Plumbing Engineers
Jeffrey J. Van Rhyn, Jr., Local 669 JATC, NV [L]
 Rep. United Assn. of Journeymen & Apprentices of the Plumbing & Pipe Fitting Industry
Ed Van Walraven, Basalt And Rural Fire Protection District, CO [E]
Terry L. Victor, Johnson Controls, MD [M]
John F. Viola, JFV Engineering, LLC, MA [IM]
 Rep. American Fire Sprinkler Association
Ronald N. Webb, S.A. Comunale Company, Inc., OH [IM]
 Rep. National Fire Sprinkler Association
Steven D. Wolin, Reliable Automatic Sprinkler Company, Inc., SC [M]
 Rep. National Fire Sprinkler Association
Hong-Zeng Yu, FM Global, MA [I]

Alternates

Jon R. Ackley, Dalmatian Fire, IN [IM]
 (Alt. to Ronald N. Webb)
Robert S. Blach, Menlo Park Fire Protection District, CA [E]
 (Alt. to Michael O'Brian)
Katherine M. Clay, Jackson Hole Fire/EMS, WY [E]
 (Alt. to Ed Van Walraven)
Samuel S. Dannaway, Coffman Engineers, HI [SE]
 (Alt. to Martin C. W. Trim)
John Desrosier, Globe Fire Sprinkler Corporation, MI [M]
 (Alt. to Steven D. Wolin)
Robert L. Dufault, Newport Fire Department, RI [E]
 (Alt. to Bradford T. Cronin)
Gary Ehrlich, National Association of Home Builders (NAHB), DC [U]
 (Alt. to Cesar Lujan)
Mark E. Fessenden, Johnson Controls, WI [M]
 (Alt. to Terry L. Victor)
Yogish Gopala, FM Global, MA [I]
 (Alt. to Hong-Zeng Yu)
Forest Hampton, Lubrizol Advanced Materials, Inc., OH [M]
 (Alt. to Donald R. Townley)
Jeff Hebenstreit, UL LLC, IL [RT]
 (Alt. to Kerry M. Bell)
Brent Kotula, Uponor, MN [M]
 (Alt. to Eric J. Skare)

David O. Lowrey, City of Boulder Fire Rescue, CO [E]
 (Alt. to Chase A. Browning)
James R. Lugar, JENSEN HUGHES, MD [SE]
 (Alt. to Wade Palazini)
Daniel J. Mathias, Absolute Fire Protection, Inc., MD [IM]
 (Alt. to John August Denhardt)
Dan Mendoza, Advanced Automatic Sprinkler, CA [IM]
 (Alt. to Fred Benn)
Matthew Osburn, Canadian Automatic Sprinkler Association, Canada [IM]
 (Alt. to Jason W. Ryckman)
Ryan Lee Peterson, Wayne Auto Fire Sprinklers, FL [IM]
 (Alt. to Peter T. Schwab)
William Scott Roberts, Quick Response Fire Protection, NJ [M]
 (Alt. to Roland A. Asp)
Ernesto Rodriguez, Jr., Wiginton Fire Protection Engineering, Inc., FL [IM]
 (Alt. to George W. Stanley)
Ralph D Young, Sprinkler Fitters Local 669, NY [L]
 (Alt. to Jeffrey J. Van Rhyn, Jr.)
Brent Zimiga, Rapid Fire Protection Inc., SD [IM]
 (Alt. to John Viola)

Nonvoting

Rohit "Rik" Khanna, US Consumer Product Safety Commission (CPSC), MD [C]
 Rep. US Consumer Product Safety Commission (CPSC)

Chad Duffy, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the design and installation of automatic sprinkler systems in dwellings and residential occupancies up to and including four stories in height, including the character and adequacy of water supplies, and the selection of sprinklers, piping, valves, and all materials and accessories. In addition, this Committee shall have primary responsibility of inspection, testing, and maintenance requirements for sprinkler systems installed in one- and two-family dwellings and manufactured homes.

Contents

Chapter 1 Administration	13R- 8	6.12 Pressure Gauges.	13R- 26
1.1 Scope.	13R- 8	6.13 Piping Support.	13R- 26
1.2 Purpose.	13R- 8	6.14 Open-Grid Ceilings.	13R- 26
1.3 Retroactivity.	13R- 8	6.15 Drop-Out Ceilings.	13R- 26
1.4 Equivalency.	13R- 8	6.16 Alarms.	13R- 26
1.5 Units.	13R- 8	Chapter 7 Design Criteria	13R- 26
1.6 New Technology.	13R- 9	7.1 Inside Dwelling Unit.	13R- 26
Chapter 2 Referenced Publications	13R- 9	7.2 Outside Dwelling Unit.	13R- 27
2.1 General.	13R- 9	7.3 Garages.	13R- 27
2.2 NFPA Publications.	13R- 9	7.4 Attics.	13R- 28
2.3 Other Publications.	13R- 9	7.5 Combustible Concealed Spaces.	13R- 28
2.4 References for Extracts in Mandatory Sections.	13R- 10	Chapter 8 Plans and Calculations	13R- 28
Chapter 3 Definitions	13R- 10	8.1 Working Plans.	13R- 28
3.1 General.	13R- 10	8.2 Hydraulic Calculations.	13R- 29
3.2 NFPA Official Definitions.	13R- 10	Chapter 9 Water Supplies	13R- 30
3.3 General Definitions.	13R- 10	9.1 Number of Supplies.	13R- 30
Chapter 4 General Requirements	13R- 11	9.2 Capacity.	13R- 30
4.1 Sprinklered Throughout.	13R- 11	9.3 Domestic Demand.	13R- 30
4.2 Basic Requirements.	13R- 11	9.4 Connection from Waterworks System.	13R- 30
4.3 Tube.	13R- 11	9.5 Types.	13R- 30
4.4 Listed or Labeled.	13R- 11	9.6 Connections to Waterworks Systems.	13R- 31
4.5 System Arrangement.	13R- 11	9.7 Fire Pump.	13R- 31
Chapter 5 System Components	13R- 11	9.8 Penstocks, Flumes, Rivers, Lakes, or Reservoirs.	13R- 31
5.1 General.	13R- 11	9.9 Non-Fire Protection Connections.	13R- 31
5.2 Aboveground Piping and Equipment.	13R- 13	Chapter 10 System Acceptance	13R- 31
5.3 Underground Pipe.	13R- 15	10.1 Approval of Sprinkler Systems.	13R- 31
5.4 System Types.	13R- 15	10.2 Acceptance Tests.	13R- 31
Chapter 6 Installation	13R- 16	Chapter 11 Care and Maintenance	13R- 31
6.1 System Protection Area Limitations.	13R- 16	11.1 Stock of Spare Sprinklers.	13R- 31
6.2 Use of Sprinklers.	13R- 16	11.2 Owner's Responsibility.	13R- 32
6.3 Quick-Response Sprinklers.	13R- 17	11.3 Inspection, Testing, and Maintenance.	13R- 32
6.4 Residential Sprinklers.	13R- 18	11.4 Instructions.	13R- 32
6.5 Special Situations.	13R- 21	Annex A Explanatory Material	13R- 32
6.6 Location of Sprinklers.	13R- 24	Annex B Informational References	13R- 50
6.7 Piping.	13R- 25	Index	13R- 51
6.8 Valves.	13R- 25		
6.9 Drains.	13R- 26		
6.10 Test Connection.	13R- 26		
6.11 Fire Department Connection.	13R- 26		

NFPA 13R

Standard for the

Installation of Sprinkler Systems in Low-Rise Residential Occupancies

2022 Edition

IMPORTANT NOTE: This NFPA document is made available for use subject to important notices and legal disclaimers. These notices and disclaimers appear in all publications containing this document and may be found under the heading “Important Notices and Disclaimers Concerning NFPA Standards.” They can also be viewed at www.nfpa.org/disclaimers or obtained on request from NFPA.

UPDATES, ALERTS, AND FUTURE EDITIONS: New editions of NFPA codes, standards, recommended practices, and guides (i.e., NFPA Standards) are released on scheduled revision cycles. This edition may be superseded by a later one, or it may be amended outside of its scheduled revision cycle through the issuance of Tentative Interim Amendments (TIAs). An official NFPA Standard at any point in time consists of the current edition of the document, together with all TIAs and Errata in effect. To verify that this document is the current edition or to determine if it has been amended by TIAs or Errata, please consult the National Fire Codes® Subscription Service or the “List of NFPA Codes & Standards” at www.nfpa.org/docinfo. In addition to TIAs and Errata, the document information pages also include the option to sign up for alerts for individual documents and to be involved in the development of the next edition.

NOTICE: An asterisk (*) following the number or letter designating a paragraph indicates that explanatory material on the paragraph can be found in Annex A.

A reference in brackets [] following a section or paragraph indicates material that has been extracted from another NFPA document. Extracted text may be edited for consistency and style and may include the revision of internal paragraph references and other references as appropriate. Requests for interpretations or revisions of extracted text shall be sent to the technical committee responsible for the source document.

Information on referenced and extracted publications can be found in Chapter 2 and Annex B.

Chapter 1 Administration

1.1* Scope. This standard shall cover the design and installation of automatic sprinkler systems for protection against fire hazards in residential occupancies up to and including four stories in height that are located in buildings not exceeding 60 ft (18 m) in height above grade plane.

1.1.1 This standard shall be based on the concept that the sprinkler system is designed to protect against a fire originating from a single ignition location.

1.1.2 This standard shall not provide requirements for the design or installation of water mist fire protection systems, which are not considered fire sprinkler systems and are addressed by NFPA 750.

1.2* Purpose.

1.2.1 The purpose of this standard shall be to provide a sprinkler system that aids in the detection and control of residential

fires and thus provides improved protection against injury, life loss, and property damage.

1.2.2 A sprinkler system shall be designed and installed in accordance with this standard to prevent flashover (total involvement) in the room of fire origin, where sprinklered, and to improve the chance for occupants to escape or be evacuated.

1.2.3 The layout, calculation, and installation of sprinkler systems installed in accordance with this standard shall only be performed by people knowledgeable and trained in such systems.

1.3 Retroactivity. The provisions of this standard reflect a consensus of what is necessary to provide an acceptable degree of protection from the hazards addressed in this standard at the time the standard was issued.

1.3.1 Unless otherwise specified, the provisions of this standard shall not apply to facilities, equipment, structures, or installations that existed or were approved for construction or installation prior to the effective date of the standard. Where specified, the provisions of this standard shall be retroactive.

1.3.2 In those cases where the authority having jurisdiction determines that the existing situation presents an unacceptable degree of risk, the authority having jurisdiction shall be permitted to apply retroactively any portions of this standard deemed appropriate.

1.3.3 The retroactive requirements of this standard shall be permitted to be modified if their application clearly would be impractical in the judgment of the authority having jurisdiction, and only where it is clearly evident that a reasonable degree of safety is provided.

1.4 Equivalency. Nothing in this standard is intended to prevent the use of systems, methods, or devices of equivalent or superior quality, strength, fire resistance, effectiveness, durability, and safety over those prescribed by this standard.

1.4.1 Technical documentation shall be submitted to the authority having jurisdiction to demonstrate equivalency.

1.4.2 The system, method, or device shall be approved for the intended purpose by the authority having jurisdiction.

1.5 Units.

1.5.1* Metric units of measurement in this standard shall be in accordance with the modernized metric system known as the International System of Units (SI).

1.5.2 The liter and bar units shall be permitted to be used in this standard.

1.5.3 The conversion factors for liter, pascal, and bar shall be in accordance with Table 1.5.3.

Table 1.5.3 Metric Conversions

Name of Unit	Unit Symbol	Conversion Factor
liter	L	1 gal = 3.785 L
pascal	Pa	1 psi = 6894.757 Pa
bar	bar	1 psi = 0.0689 bar
bar	bar	1 bar = 10 ⁵ Pa

1.5.4* Where a value for measurement as specified in this standard is followed by an equivalent value in other units, the first stated value shall be regarded as the requirement.

1.5.5 The equivalent value for a measurement in SI shall be converted by multiplying the value by the conversion factor and then rounding the result to the appropriate number of significant digits.

1.6 New Technology.

1.6.1 Nothing in this standard shall be intended to restrict new technologies or alternate arrangements, provided the level of safety prescribed by this standard is not lowered.

1.6.2 Materials or devices not specifically designated by this standard shall be utilized in complete accord with all conditions, requirements, and limitations of their listings.

Chapter 2 Referenced Publications

2.1 General. The documents or portions thereof listed in this chapter are referenced within this standard and shall be considered part of the requirements of this document.

2.2 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02169-7471.

NFPA 13, *Standard for the Installation of Sprinkler Systems*, 2022 edition.

NFPA 20, *Standard for the Installation of Stationary Pumps for Fire Protection*, 2022 edition.

NFPA 22, *Standard for Water Tanks for Private Fire Protection*, 2018 edition.

NFPA 24, *Standard for the Installation of Private Fire Service Mains and Their Appurtenances*, 2022 edition.

NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*, 2020 edition.

NFPA 82, *Standard on Incinerators and Waste and Linen Handling Systems and Equipment*, 2019 edition.

NFPA 101®, *Life Safety Code*®, 2021 edition.

NFPA 220, *Standard on Types of Building Construction*, 2021 edition.

NFPA 750, *Standard on Water Mist Fire Protection Systems*, 2019 edition.

NFPA 5000®, *Building Construction and Safety Code*®, 2021 edition.

2.3 Other Publications.

▲ **2.3.1 ASME Publications.** American Society of Mechanical Engineers, Two Park Avenue, New York, NY 10016-5990.

ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, 2019.

ASME B16.1, *Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250*, 2015.

ASME B16.3, *Malleable Iron Threaded Fittings: Classes 150 and 300*, 2016.

ASME B16.4, *Gray Iron Threaded Fittings: Classes 125 and 250*, 2016.

ASME B16.5, *Pipe Flanges and Flanged Fittings: NPS 1/2 through NPS 24 Metric/Inch Standard*, 2017.

ASME B16.9, *Factory-Made Wrought Butt Welding Fittings*, 2018.

ASME B16.11, *Forged Fittings, Socket-Welding and Threaded*, 2016.

ASME B16.15, *Cast Copper Alloy Threaded Fittings: Classes 125 and 250*, 2018.

ASME B16.18, *Cast Copper Alloy Solder Joint Pressure Fittings*, 2018.

ASME B16.22, *Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings*, 2018.

ASME B16.25, *Butt Welding Ends*, 2017.

ASME B36.10M, *Welded and Seamless Wrought Steel Pipe*, 2018.

▲ **2.3.2 ASTM Publications.** ASTM International, 100 Barr Harbor Drive, P.O. Box C700, West Conshohocken, PA 19428-2959.

ASTM A53/A53M, *Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless*, 2018.

ASTM A135/A135M, *Standard Specification for Electric-Resistance-Welded Steel Pipe*, 2019.

ASTM A234/A234M, *Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperatures*, 2019.

ASTM A795/A795M, *Standard Specification for Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless Steel Pipe for Fire Protection Use*, 2013 (2020).

ASTM B32, *Standard Specification for Solder Metal*, 2008, reapproved 2014.

ASTM B43, *Standard Specification for Seamless Red Brass Pipe, Standard Sizes*, 2020.

ASTM B88, *Standard Specification for Seamless Copper Water Tube*, 2020.

ASTM B251/B251M, *Standard Specification for General Requirements for Wrought Seamless Copper and Copper-Alloy Tube*, 2017.

ASTM B813, *Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper-Alloy Tube*, 2016.

ASTM F437, *Standard Specification for Threaded Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80*, 2015.

ASTM F438, *Standard Specification for Socket-Type Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40*, 2017.

ASTM F439, *Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80*, 2019.

ASTM F442/F442M, *Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe (SDR-PR)*, 2019.

▲ **2.3.3 AWS Publications.** American Welding Society, 8669 NW 36 Street, #130, Miami, FL 33166-6672.

AWS A5.8/A5.8M, *Specification for Filler Metals for Brazing and Braze Welding*, 2011, Amendment 1, 2012.

2.3.4 Other Publications.

Merriam-Webster's Collegiate Dictionary, 11th edition, Merriam-Webster, Inc., Springfield, MA, 2003.

2.4 References for Extracts in Mandatory Sections.

NFPA 13, *Standard for the Installation of Sprinkler Systems*, 2022 edition.

NFPA 5000®, *Building Construction and Safety Code*®, 2021 edition.

Chapter 3 Definitions

3.1 General. The definitions contained in this chapter shall apply to the terms used in this standard. Where terms are not defined in this chapter or within another chapter, they shall be defined using their ordinarily accepted meanings within the context in which they are used. *Merriam-Webster's Collegiate Dictionary*, 11th edition, shall be the source for the ordinarily accepted meaning.

3.2 NFPA Official Definitions.

3.2.1* Approved. Acceptable to the authority having jurisdiction.

3.2.2* Authority Having Jurisdiction (AHJ). An organization, office, or individual responsible for enforcing the requirements of a code or standard, or for approving equipment, materials, an installation, or a procedure.

3.2.3 Labeled. Equipment or materials to which has been attached a label, symbol, or other identifying mark of an organization that is acceptable to the authority having jurisdiction and concerned with product evaluation, that maintains periodic inspection of production of labeled equipment or materials, and by whose labeling the manufacturer indicates compliance with appropriate standards or performance in a specified manner.

3.2.4* Listed. Equipment, materials, or services included in a list published by an organization that is acceptable to the authority having jurisdiction and concerned with evaluation of products or services, that maintains periodic inspection of production of listed equipment or materials or periodic evaluation of services, and whose listing states that either the equipment, material, or service meets appropriate designated standards or has been tested and found suitable for a specified purpose.

3.2.5 Shall. Indicates a mandatory requirement.

3.2.6 Standard. An NFPA Standard, the main text of which contains only mandatory provisions using the word “shall” to indicate requirements and that is in a form generally suitable for mandatory reference by another standard or code or for adoption into law. Nonmandatory provisions are not to be considered a part of the requirements of a standard and shall be located in an appendix, annex, footnote, informational note, or other means as permitted in the NFPA Manuals of Style. When used in a generic sense, such as in the phrase “standards development process” or “standards development activities,” the term “standards” includes all NFPA Standards, including Codes, Standards, Recommended Practices, and Guides.

3.3 General Definitions.

3.3.1* Bathroom. Within a dwelling unit, any room or compartment containing a lavatory dedicated to personal hygiene, or a water closet, or bathing capability such as a shower or tub, or any combination of facilities thereof.

3.3.2 Carport. A freestanding or attached covered structure open on at least two sides that provides shelter for motor vehicles.

3.3.3 Compartment. A space completely enclosed by walls and a ceiling. Each wall in the compartment is permitted to have openings to an adjoining space if the openings have a minimum lintel depth of 8 in. (200 mm) from the ceiling and the total width of the openings in a single wall does not exceed 8 ft (2.4 m) in width. A single opening of 36 in. (900 mm) or less in width without a lintel is permitted when there are no other openings to adjoining spaces.

3.3.4 Design Discharge. The rate of water discharged by an automatic sprinkler, expressed in gpm (mm/min).

3.3.5 Dwelling Unit. One or more rooms, arranged for the use of one or more individuals living together, as in a single housekeeping unit, that normally have cooking, living, sanitary, and sleeping facilities.

3.3.6 Fuel-Fired Heating Unit. An appliance that produces heat by burning fuel.

3.3.7 Grade Plane. A reference plane upon which vertical measurements of a building are based representing the average of the finished ground level adjoining the building at all exterior walls. [See also 3.3.222, *Finished Ground Level (Grade)*, of NFPA 5000.] [5000, 2021]

3.3.8 Hazard Classifications.

3.3.8.1* Light-Hazard Occupancy. Occupancies or portions of other occupancies where the quantity and/or combustibility of contents is low and fires with relatively low rates of heat release are expected.

3.3.8.2* Ordinary Hazard (Group 1). Occupancies or portions of other occupancies where combustibility is low, quantity of combustibles is moderate, stockpiles of combustibles do not exceed 8 ft (2.4 m), and fires with moderate rates of heat release are expected.

3.3.8.3* Ordinary Hazard (Group 2). Occupancies or portions of other occupancies where the quantity and combustibility of contents are moderate to high, stockpiles of contents with moderate rates of heat release do not exceed 12 ft (3.7 m), and stockpiles of contents with high rates of heat release do not exceed 8 ft (2.4 m).

3.3.9* Raw Water Source. A water supply taken from the environment that has not been treated and could contain foreign material that could accumulate freely and enter the sprinkler system.

3.3.10* Residential Occupancies. Occupancies that include the following, as defined in NFPA 101: (1) apartment buildings, (2) lodging and rooming houses, (3) board and care facilities, and (4) hotels, motels, and dormitories.

3.3.11* Shadow Area. The dry floor area within the protection area of a sprinkler created by the portion of sprinkler discharge that is blocked by a wall or partition.

3.3.12 Sprinkler.

3.3.12.1 Automatic Sprinkler. A fire suppression or control device that operates automatically when its heat-actuated element is heated to its thermal rating or above, allowing water to discharge over a specific area.

3.3.12.2 Quick-Response (QR) Sprinkler. A type of spray sprinkler having a thermal element with an RTI of 50 (meters-second)^{1/2} or less and is listed as a quick-response sprinkler for its intended use.

3.3.12.3 Residential Sprinkler. A type of fast-response sprinkler having a thermal element with an RTI of 50 (meters-second)^{1/2} or less, that has been specifically investigated for its ability to enhance survivability in the room of fire origin, and that is listed for use in the protection of dwelling units.

Δ 3.3.13 Sprinkler System. A system, commonly activated by heat from a fire and discharges water over the fire area, that consists of an integrated network of piping designed in accordance with fire protection engineering standards that includes a water supply source, a water control valve, a waterflow alarm, and a drain. The portion of the sprinkler system above ground is a network of specifically sized or hydraulically designed piping installed in a building, structure, or area, generally overhead, and to which sprinklers are attached in a systematic pattern. [13, 2022]

3.3.13.1 Dry Pipe Sprinkler System. A sprinkler system employing automatic sprinklers that are attached to a piping system that contains air or nitrogen under pressure, the release of which (as from the opening of a sprinkler) permits the water pressure to open a valve known as a dry pipe valve, and the water then flows into the piping system and out the opened sprinkler.

3.3.13.2 Preaction Sprinkler System. A sprinkler system employing automatic sprinklers that are attached to a piping system containing air that might or might not be under pressure, with a supplemental detection system installed in the same areas as the sprinklers.

3.3.13.3 Wet Pipe Sprinkler System. A sprinkler system employing automatic sprinklers attached to a piping system containing water and connected to a water supply so that water discharges immediately from sprinklers opened by heat from a fire.

3.3.14 System Working Pressure. The maximum anticipated static (i.e., nonflowing) or residual flowing pressure applied to sprinkler system components exclusive of surge pressures and of pressure from the fire department connection.

3.3.15 Valve.

3.3.15.1 Check Valve. A valve that allows flow in one direction only.

3.3.15.2 Control Valve. An indicating valve employed to control (shut) a supply of water to a sprinkler system.

3.3.16 Waterflow Alarm Device. An attachment to the sprinkler system that detects a predetermined water flow and is connected to a fire alarm system to initiate an alarm condition or is used to mechanically or electrically initiate a fire pump or local audible or visual alarm. [13, 2022]

3.3.17 Waterflow Detector. An electric signaling indicator or alarm check valve actuated by water flow in one direction only.

Chapter 4 General Requirements

4.1 Sprinklered Throughout. A building provided with a fire sprinkler system designed and installed in accordance with the

requirements of this standard, including its allowable omissions, shall be considered fully sprinklered throughout.

4.2 Basic Requirements. The requirements for spacing, location, and position of sprinklers shall be based on the following principles:

- (1) Sprinklers shall be installed throughout the premises.
- (2) Sprinklers shall be located so as not to exceed maximum protection area per sprinkler.
- (3) Sprinklers shall be positioned and located so as to provide satisfactory performance with respect to activation time and distribution.
- (4) Sprinklers shall be permitted to be omitted from areas specifically allowed by this standard (*see Section 6.6*).
- (5) When sprinklers are specifically tested and test results demonstrate that deviations from clearance requirements to structural members do not impair the ability of the sprinkler to control or suppress a fire, their positioning and locating in accordance with the test results shall be permitted.
- (6) Clearance between sprinklers and ceilings exceeding the maximums specified in this standard shall be permitted, provided that tests or calculations demonstrate comparable sensitivity and performance of the sprinklers to those installed in conformance with these sections.

4.3 Tube. Wherever the word *pipe* is used in this standard, it shall also mean *tube*.

4.4 Listed or Labeled. Listed or labeled devices and materials shall be installed and used in accordance with the listing limitations and the manufacturers' instructions unless permitted by other sections of this document.

4.5 System Arrangement. In townhouse-style buildings protected in accordance with this standard, each dwelling unit shall have its own dedicated sprinkler system or the control valve for the sprinkler system in the building shall be located outside the dwelling units or in a common area.

Chapter 5 System Components

5.1 General.

5.1.1 Sprinklers.

5.1.1.1* Sprinkler Removal. Only new listed sprinklers shall be installed in sprinkler systems.

5.1.1.1.1* Where a sprinkler is removed from a fitting or welded outlet, it shall not be reinstalled except as permitted by 5.1.1.1.1.1.

5.1.1.1.1.1 Dry sprinklers shall be permitted to be reinstalled when removed in accordance with the manufacturer's installation and maintenance instructions.

5.1.1.1.2* Sprinkler Replacement. Where replacing residential sprinklers manufactured prior to 2003 and that are no longer available from the manufacturer and are installed using a design density less than 0.05 gpm/ft² (2.04 mm/min), a residential sprinkler with an equivalent K-factor (± 5%) shall be permitted to be used provided the currently listed coverage area for the replacement sprinkler is not exceeded.

5.1.1.1.3* Sprinkler Identification. All sprinklers shall be permanently marked with a one- or two-character manufacturer symbol, followed by three or four numbers, so as to identify

tify a unique sprinkler identification for every change in orifice size or shape, deflector characteristic, pressure rating, and thermal sensitivity.

5.1.1.4 Sprinkler Discharge Characteristics.

5.1.1.4.1 General. Unless the requirements of 5.1.1.4.2 or 5.1.1.4.3 are met, the K-factor, relative discharge, and marking identification for sprinklers having different orifice sizes shall be in accordance with Table 5.1.1.4.1.

5.1.1.4.2 Pipe Threads. Listed sprinklers having pipe threads different from those shown in Table 5.1.1.4.1 shall be permitted.

5.1.1.4.3 Residential Sprinklers. Residential sprinklers with K-factors other than those specified in Table 5.1.1.4.1 shall be permitted.

5.1.1.5 Occupancy Limitations. Unless the requirements of 5.1.1.5.1 or 5.1.1.5.2 are met, sprinklers shall not be listed for protection of a portion of an occupancy classification.

5.1.1.5.1 Residential Sprinklers. Residential sprinklers shall be permitted to be listed for portions of residential occupancies.

5.1.1.5.2 Special Sprinklers. Special sprinklers shall be permitted to be listed for protection of a specific construction feature in a portion of an occupancy classification where such sprinklers meet 5.1.1.5.3 and have been evaluated and listed for performance under the following conditions:

- (1) Fire tests related to the intended hazard
- (2) Distribution of the spray pattern with respect to wetting of floors and walls
- (3) Distribution of the spray pattern with respect to obstructions
- (4) Evaluation of the thermal sensitivity of the sprinkler
- (5) Performance under horizontal or sloped ceilings
- (6) Area of design

5.1.1.5.3 Special sprinklers shall maintain the following characteristics:

- (1) Orifice size shall be in accordance with 5.1.1.4.
- (2) Temperature ratings shall be in accordance with Table 5.1.1.6.1.

- (3) The protection area of coverage shall not exceed 400 ft² (37 m²) for light-hazard and ordinary-hazard occupancies.

5.1.1.6* Temperature Characteristics.

5.1.1.6.1 Automatic sprinklers shall have their frame arms, deflector, coating material, or liquid bulb colored in accordance with the requirements of Table 5.1.1.6.1 or the requirements of 5.1.1.6.2, 5.1.1.6.3, 5.1.1.6.4, or 5.1.1.6.5.

5.1.1.6.2 A dot on the top of the deflector, the color of the coating material, or colored frame arms shall be permitted for color identification of corrosion-resistant sprinklers.

5.1.1.6.3 Color identification shall not be required for ornamental sprinklers such as factory-plated or factory-painted sprinklers or for recessed, flush, or concealed sprinklers.

5.1.1.6.4 The frame arms of bulb-type sprinklers shall not be required to be color coded.

5.1.1.6.5 The liquid in bulb-type sprinklers shall be color coded in accordance with Table 5.1.1.6.1.

5.1.1.7 Escutcheons and Cover Plates.

5.1.1.7.1 Nonmetallic escutcheons shall be listed.

5.1.1.7.2* Escutcheons used with recessed, flush-type, or concealed sprinklers shall be part of a listed sprinkler assembly.

5.1.1.7.3 Cover plates used with concealed sprinklers shall be part of the listed sprinkler assembly.

5.1.1.8 Painting and Finish. Sprinkler painting and finish material shall only be permitted in accordance with NFPA 13.

5.1.1.9 Protective Caps and Straps.

5.1.1.9.1* Protective caps and straps shall be removed using means that are in accordance with the manufacturer's instructions.

5.1.1.9.2* Protective caps and straps shall be removed from all sprinklers prior to the time when the sprinkler system is placed in service.

▲ Table 5.1.1.4.1 Sprinkler Discharge Characteristics Identification

Nominal K-factor [gpm/(psi) ^{1/2}]	K-factor Range [gpm/(psi) ^{1/2}]	K-factor Range [dm ³ /min/(kPa) ^{1/2}]	Percent of Nominal K-5.6 Discharge	Thread Type (in. NPT)
1.4	1.3–1.5	1.9–2.2	25	½
1.9	1.8–2.0	2.6–2.9	33.3	½
2.8	2.6–2.9	3.8–4.2	50	½
4.2	4.0–4.4	5.9–6.4	75	½
5.6	5.3–5.8	7.6–8.4	100	½
8.0	7.4–8.2	10.7–11.8	140	¾ or ½
11.2	11.0–11.5	15.9–16.6	200	½ or ¾
14.0	13.5–14.5	19.5–20.9	250	¾
16.8	16.0–17.6	23.1–25.4	300	¾
19.6	18.6–20.6	27.2–30.1	350	1
22.4	21.3–23.5	31.1–34.3	400	1
25.2	23.9–26.5	34.9–38.7	450	1
28.0	26.6–29.4	38.9–43.0	500	1

Table 5.1.1.6.1 Sprinkler Temperature Ratings, Classifications, and Color Codings

Maximum Ceiling Temperature		Temperature Rating		Temperature Classification	Color Code	Glass Bulb Colors
°F	°C	°F	°C			
100	38	135–170	57–77	Ordinary	Uncolored or black	Orange or red
150	66	175–225	79–107	Intermediate	White	Yellow or green
225	107	250–300	121–149	High	Blue	Blue
300	149	325–375	163–191	Extra high	Red	Purple
375	191	400–475	204–246	Very extra high	Green	Black
475	246	500–575	260–302	Ultra high	Orange	Black
625	329	650	343	Ultra high	Orange	Black

5.1.1.9.3 Protective caps and straps on all upright sprinklers or on any sprinklers installed more than 10 ft (3 m) above the floor shall be permitted to be removed from sprinklers immediately following their installation.

5.1.2 Listing. Only listed or approved devices and materials as specified in this standard shall be used in sprinkler systems.

5.1.2.1 Water meters and pressure-reducing valves that are installed in a combined domestic water and fire protection supply to the building shall not be required to be listed for fire protection.

5.1.2.2 Materials and components shall be installed in accordance with material compatibility information that is available as a part of a listing or manufacturer's published information.

5.1.3 Rated Pressure. System components shall be rated for the maximum system working pressure to which they are exposed but shall not be rated at less than 175 psi (12.1 bar) for components installed above ground and 150 psi (10 bar) for components installed underground between the water supply and the system riser.

5.1.4 Reconditioned Equipment.

5.1.4.1 The use of reconditioned valves and devices as replacement equipment in existing systems shall be permitted.

5.1.4.2 Reconditioned sprinklers shall not be permitted to be utilized on any new or existing system.

5.2 Aboveground Piping and Equipment.

5.2.1 Pipe or tube used in sprinkler systems shall be of the materials specified in Table 5.2.1 or in accordance with 5.2.2.

5.2.1.1 The chemical properties, physical properties, and dimensions of pipe materials shall be at least equivalent to the standards cited in Table 5.2.1.

5.2.1.2 Pipe shall be designed to withstand a working pressure of not less than 175 psi (12 bar).

5.2.1.3 When nonmetallic pipe is used, the pipe shall be designed to withstand a working pressure of not less than 175 psi (12.1 bar) at 120°F (49°C).

5.2.1.4 Nonmetallic pipe and fittings included in Table 5.2.1 and Table 5.2.9 shall be listed.

Table 5.2.1 Pipe or Tube Materials and Dimensions

Materials and Dimensions	Standard
Black and hot-dipped zinc-coated (galvanized) welded and seamless steel pipe for fire protection use	ASTM A795/A795M
Pipe, steel, black and hot-dipped, zinc-coated, welded and seamless	ASTM A53/A53M
Welded and seamless wrought steel pipe	ASME B36.10M
Electric-resistance-welded steel pipe	ASTM A135/A135M
Seamless copper water tube [copper tube (drawn, seamless)]	ASTM B88
Wrought seamless copper and copper-alloy tube	ASTM B251/B251M
Liquid and paste fluxes for soldering applications of copper and copper-alloy tube	ASTM B813
Filler metals for brazing and braze welding (Classification BCuP-3 or BCuP-4)	AWS A5.8/A5.8M
Solder alloys containing less than 0.2 percent lead (Pb) as identified in Table 5 of Section 1 ASTM B32 and having a solidus temperature that exceeds 400°F (204°C)	ASTM B32
Cast copper alloy threaded fittings, Classes 125 and 250	ASME B16.15
Seamless red brass pipe, standard sizes	ASTM B43
Chlorinated poly(vinyl chloride) (CPVC) plastic pipe (SDR-PR)	ASTM F442/F442M

5.2.2 Types of pipe other than those specified in Table 5.2.1 shall be permitted to be used where listed for sprinkler system use.

5.2.2.1 Pipe differing from those specified in Table 5.2.1 shall be installed in accordance with their listings and the manufacturer's installation instructions.

• **5.2.2.2** Pipe or tube listed for light-hazard occupancies shall be permitted to be installed in ordinary-hazard rooms of otherwise light-hazard occupancies under the following conditions:

- (1) In rooms 800 ft² (74 m²) or less, piping shall be permitted to be installed either exposed in accordance with its listing or concealed behind a minimum of one layer of ⅝ in. (10 mm) thick gypsum wallboard or ½ in. (13 mm) thick plywood.
- (2) In rooms over 800 ft² (74 m²), piping shall be permitted to be installed concealed behind a minimum of one layer

of ⅜ in. (10 mm) thick gypsum wallboard or ½ in. (13 mm) thick plywood.

5.2.2.2.1 Pipe or tube installed in accordance with 5.2.2.2 shall be permitted to be installed exposed, in accordance with their listing.

5.2.3* Chlorinated polyvinyl chloride (CPVC) pipe shall comply with the portions of the American Society for Testing and Materials (ASTM) standards specified in Table 5.2.1 that apply to fire protection service.

5.2.3.1 Nonmetallic pipe in accordance with Table 5.2.1 shall be investigated for suitability in automatic sprinkler installations and listed for this service.

5.2.3.1.1 Listed nonmetallic pipe shall be installed in accordance with its listing limitations, including installation instructions.

5.2.3.1.2 Manufacturer's installation instructions shall include its listing limitations.

5.2.3.2 When nonmetallic pipe is used in systems utilizing steel pipe internally coated with corrosion inhibitors, the steel pipe coating shall be listed for compatibility with the nonmetallic pipe materials.

5.2.3.3 When nonmetallic pipe is used in systems utilizing steel pipe that is not internally coated with corrosion inhibitors, no additional evaluations shall be required.

5.2.3.4* When nonmetallic pipe is used in systems utilizing steel pipe, cutting oils and lubricants used for fabrication of the steel piping shall be compatible with the nonmetallic pipe materials in accordance with 5.1.2.2.

5.2.3.5 Fire-stopping materials intended for use on nonmetallic piping penetrations shall be compatible with the nonmetallic pipe materials in accordance with 5.1.2.2.

5.2.3.6 Nonmetallic pipe shall not be listed for portions of an occupancy classification.

N 5.2.3.7 Where pipe other than steel is run horizontally or vertically through wood or metal studs, the following provisions shall apply:

- (1) Steel shield plates shall be provided where the face of the piping is less than 1.25 in. (32 mm) from the nearest edge of the member.
- (2) Steel shield plates shall have a minimum thickness of 0.0575 in. (1.463 mm) (No. 16 gauge).
- (3) Steel shield plates shall cover the area of the pipe where the member is notched or bored.

5.2.4 Brass pipe specified in Table 5.2.1 shall be permitted in the standard weight in sizes up to 6 in. (150 mm) for pressures up to 175 psi (12 bar) and in the extra strong weight in sizes up to 8 in. (200 mm) for pressures up to 300 psi (21 bar).

5.2.5 Pipe with a wall thickness less than that of Schedule 30 pipe shall not be joined by fittings utilizing cut grooves where the pipe is 8 in. (200 mm) nominal or larger in size.

5.2.6 Pipe having a wall thickness less than that of Schedule 40 pipe shall not be joined by fittings utilizing cut grooves where the pipe is less than 8 in. (200 mm) nominal in size.

5.2.7 Pipe joined with mechanical fittings using cut or rolled grooves shall be joined by a listed combination of fittings, gaskets, and grooves.

5.2.8 Grooves cut or rolled on pipe shall be dimensionally compatible with the fittings.

5.2.9 Fittings used in sprinkler systems shall meet or exceed the standards in Table 5.2.9 or be in accordance with 5.2.12.

5.2.9.1 The chemical properties, physical properties, and dimensions of fitting materials shall be at least equivalent to the standards cited in Table 5.2.9.

5.2.9.2 Fittings used in sprinkler systems shall be designed to withstand a working pressure of not less than 175 psi (12 bar).

5.2.9.3 When nonmetallic fittings are used, the fittings shall be designed to withstand a working pressure of not less than 175 psi (12 bar) at 120°F (49°C).

5.2.10 Joints for the connection of copper pipe shall be brazed on dry pipe and preaction systems.

5.2.11 Joints for the connection of copper pipe for wet systems shall be solder joints or be brazed.

5.2.12 Types of fittings other than those specified in Table 5.2.9 shall be permitted to be used where listed for sprinkler system use.

5.2.12.1 Fittings differing from those specified in Table 5.2.9 shall be installed in accordance with their listings and the manufacturer's installation instructions.

5.2.12.2* Nonmetallic fittings shall comply with the portions of the ASTM standards specified in Table 5.2.9 that apply to fire protection service.

Table 5.2.9 Fittings Materials and Dimensions

Materials and Dimensions	Standard
<i>Cast Iron:</i>	
Gray iron threaded fittings, Classes 125 and 250	ASME B16.4
Gray iron pipe flanges and flanged fittings, Classes 25, 125, and 250	ASME B16.1
<i>Malleable Iron:</i>	
Malleable iron threaded fittings, Classes 150 and 300	ASME B16.3
<i>Steel:</i>	
Factory-made wrought butt welding fittings	ASME B16.9
Butt welding ends	ASME B16.25
Piping fittings of wrought carbon steel and alloy steel for moderate and high temperatures	ASTM A234/A234M
Pipe flanges and flanged fittings, NPS 1/2 through NPS 24 metric/inch standard	ASME B16.5
Forged fittings, socket-welding and threaded	ASME B16.11
<i>Copper:</i>	
Wrought copper and copper alloy solder joint pressure fittings	ASME B16.22
Cast copper alloy solder joint pressure fittings	ASME B16.18
<i>CPVC:</i>	
Threaded chlorinated poly(vinyl chloride) (CPVC) plastic pipe fittings, Schedule 80	ASTM F437
Socket-type chlorinated poly(vinyl chloride) (CPVC) plastic pipe fittings, Schedule 40	ASTM F438
Socket-type chlorinated poly(vinyl chloride) (CPVC) plastic pipe fittings, Schedule 80	ASTM F439

5.2.12.2.1 Nonmetallic fittings in accordance with Table 5.2.9 shall be investigated for suitability in automatic sprinkler installations and listed for this service. Listed nonmetallic fittings shall be installed in accordance with their listing limitations, including installation instructions.

5.2.12.2.1.1 When nonmetallic fittings are used in systems utilizing internally coated steel piping, the steel pipe coating shall be listed for compatibility with the nonmetallic fittings.

5.2.12.2.1.2 When nonmetallic fittings are used in systems utilizing steel pipe that is not internally coated with corrosion inhibitors, no additional evaluations shall be required.

5.2.12.2.1.3* When nonmetallic fittings are used in systems utilizing steel pipe, cutting oils and lubricants used for fabrication of the steel piping shall be compatible with the nonmetallic fittings in accordance with 5.1.2.2.

5.2.12.2.1.4 Fire-stopping materials intended for use on nonmetallic fitting penetrations shall be investigated for compatibility with the nonmetallic fitting materials in accordance with 5.1.2.2.

5.2.12.2.1.5* Other types of fittings investigated for suitability in automatic sprinkler installations and listed for this service, including but not limited to CPVC and steel, and differing from that provided in Table 5.2.9 shall be permitted when installed in accordance with their listing limitations, including installation instructions.

5.2.13 Welded pipe and fittings shall be permitted to be used in accordance with the rules of NFPA 13.

5.2.14 Valves.

5.2.14.1 General.

5.2.14.1.1 Valve Pressure Requirements. When water pressures exceed 175 psi (12 bar), valves shall be used in accordance with their pressure ratings.

5.2.14.1.2 Valve Closure Time. Listed indicating valves shall not close in less than 5 seconds when operated at maximum possible speed from the fully open position.

5.2.14.1.3 Listed Indicating Valves. Unless the requirements of 5.2.14.1.3.1, 5.2.14.1.3.2, or 5.2.14.1.3.3 are met, all valves controlling connections to water supplies and to supply pipes to sprinklers shall be listed indicating valves.

5.2.14.1.3.1 A listed underground gate valve equipped with a listed indicator post shall be permitted.

5.2.14.1.3.2 A listed water control valve assembly with a reliable position indication connected to a remote supervisory station shall be permitted.

5.2.14.1.3.3 A nonindicating valve, such as an underground gate valve with approved roadway box, complete with T-wrench, and where accepted by the authority having jurisdiction, shall be permitted.

5.2.14.2 Wafer-Type Valves. Wafer-type valves with components that extend beyond the valve body shall be installed in a manner that does not interfere with the operation of any system components.

5.2.14.3 Drain Valves and Test Valves. Drain valves and test valves shall be approved.

5.2.14.4* Identification of Valves.

5.2.14.4.1 All control, drain, and test connection valves shall be provided with permanently marked weatherproof metal or rigid plastic identification signs.

5.2.14.4.2 The identification sign shall be secured with corrosion-resistant wire, chain, or other approved means.

5.2.14.4.3 The control valve sign shall identify the portion of the building served.

5.2.14.4.4* Systems that have more than one control valve that must be closed to work on a system or space shall have a sign referring to the existence and location of other valves.

5.2.14.5 Backflow Preventers.

5.2.14.5.1* Backflow preventers shall be listed for fire protection service.

5.2.15 Gauges.

5.2.15.1 A pressure gauge with a connection not smaller than ¼ in. (6 mm) shall be installed at the system main drain, at each main drain associated with a floor control valve, and on the inlet and outlet side of each pressure-reducing valve.

5.2.15.2 Each gauge connection shall be equipped with a shut-off valve and provisions for draining.

5.2.15.3 The required pressure gauges shall be approved and shall have a maximum limit not less than twice the normal system working pressure at the point where installed.

5.2.15.4 Gauges shall be installed to permit removal and shall be located where they will not be subject to freezing.

▲ 5.3 Underground Pipe.

N 5.3.1 Any type of pipe or tube acceptable under the adopted plumbing code for underground supply pipe smaller than 4 in. (100 mm) nominal dimension shall be acceptable as underground supply for the system when installed between the point of connection and the system riser.

N 5.3.2 Underground pipe and tube for underground supply pipe 4 in. (100 mm) and larger nominal dimension shall be in accordance with NFPA 24 when installed between the point of connection and the system riser.

5.4 System Types.

5.4.1 A wet pipe system shall be used where piping is installed in areas that can be maintained reliably above 40°F (4°C).

5.4.2* Systems in Areas Subject to Freezing. Where any portion of a system is subject to freezing and the temperature cannot be maintained reliably at or above 40°F (4°C), the pipe shall be protected by use of one of the following methods:

- (1)* Antifreeze system using a listed antifreeze solution in accordance with NFPA 13
- (2) Dry pipe system
- (3) Preaction system
- (4) Listed dry pendent, dry upright, or dry sidewall sprinklers extended from pipe in heated areas
- (5) Heat tracing in accordance with 6.7.2.2

5.4.3 Where antifreeze systems, dry pipe systems, and preaction systems are installed, they shall be installed in accordance with NFPA 13.

5.4.4* Water-filled piping shall be permitted to be installed in areas subject to freezing when heat loss calculations performed by a professional engineer verify that the system will not freeze.

Chapter 6 Installation

6.1 System Protection Area Limitations.

6.1.1 The maximum floor area on any one floor to be protected by sprinklers supplied by any one sprinkler system riser or combined system riser shall not exceed 52,000 ft² (4830 m²).

6.1.2 The floor area occupied by mezzanines shall not be included in the area limits of 6.1.1.

6.2 Use of Sprinklers.

6.2.1 Inside Dwelling Units.

6.2.1.1 Listed residential sprinklers shall be used unless another type is permitted by 6.2.1.3 or 6.2.1.4.

6.2.1.2 Residential sprinklers shall not be used on systems other than wet pipe systems unless specifically listed for use on that particular type of system.

6.2.1.3 Listed quick-response sprinklers shall be permitted to be installed in dwelling units meeting the definition of a compartment, as defined in Section 3.3, where no more than four sprinklers are located in the dwelling unit.

6.2.1.3.1 Where quick-response sprinklers, including extended coverage quick-response sprinklers, are used, the density/area requirement shall be a minimum of 0.1 gpm/ft² (4.1 mm/min) over the entire dwelling unit.

6.2.1.3.2 Where extended coverage quick-response sprinklers are used, the flow shall be sufficient to meet the listing of the sprinklers at the spacing for which they are being used.

6.2.1.4 Quick-response sprinklers discharging a minimum of 0.1 gpm/ft² (4.1 mm/min) shall be permitted to be used in mechanical closets.

6.2.2 Outside Dwelling Units.

6.2.2.1 Sprinklers outside of the dwelling units shall be quick response, except as permitted by 6.2.2.2.

6.2.2.1.1 The sprinkler design criteria shall be in accordance with Chapter 7.

6.2.2.2 The following types of spaces shall be permitted to be protected by residential sprinklers in accordance with Section 7.1:

- (1) Lobbies not in hotels and motels
- (2) Foyers
- (3) Corridors
- (4) Halls
- (5) Lounges
- (6) Ordinary-hazard areas in accordance with 7.2.4.1
- (7) Garages in accordance in accordance with 7.3.4 and 7.3.4.1(1)
- (8) Porches, balconies, lanais, and similar areas
- (9) Other areas with fire loads similar to residential fire loads

6.2.2.3 Standard response sprinklers shall be permitted in garages in accordance with 7.3.2.

6.2.3 Temperature Ratings.

6.2.3.1* Sprinklers installed where maximum ambient ceiling temperatures do not exceed 100°F (38°C) shall be ordinary temperature-rated sprinklers or intermediate temperature-rated unless modified by 6.2.3.3.

6.2.3.2* Sprinklers installed where maximum ambient ceiling temperatures are between 101°F and 150°F (39°C and 66°C) shall be intermediate temperature-rated sprinklers unless modified by 6.2.3.3.

6.2.3.3* The practices of 6.2.3.3.1 through 6.2.3.3.5 shall be observed when installing residential sprinklers unless higher expected ambient temperatures require a higher temperature rating.

6.2.3.3.1 Sprinklers under glass or plastic skylights exposed to direct rays of the sun shall be of intermediate temperature classification.

6.2.3.3.2 Sprinklers in an unventilated concealed space under uninsulated roof or in an unventilated attic shall be of intermediate temperature classification.

6.2.3.3.3* Sprinklers installed near specific heat sources that are identified in Table 6.2.3.3.3 shall be of the temperature rating indicated in Table 6.2.3.3.3 unless sprinklers are listed for positioning closer to the heat source.

6.2.3.3.3.1 Sprinklers adjacent to diffusers shall not be required to meet 6.2.3.3.3 where the temperature from the diffuser does not exceed 100°F (38°C).

6.2.3.3.4 Sprinklers in closets containing ventless clothes dryers shall be of the intermediate-temperature classification or higher.

6.2.3.3.5 All sprinklers within a compartment shall have the same temperature classification except where required by 6.2.3.3 for a specific location.

Δ 6.2.3.4 Sprinkler Positioning.

6.2.3.4.1 Sprinklers shall be positioned in accordance with this standard and the manufacturer's installation guidelines.

6.2.3.4.2 Ceiling Pockets Where Protected with Residential Sprinklers.

6.2.3.4.2.1 Sprinklers shall be required in all ceiling pockets.

6.2.3.4.2.2 The requirement of 6.2.3.4.2.1 shall not apply where all of the following requirements are met:

- (1) The total volume of the unprotected ceiling pocket does not exceed 100 ft³ (2.8 m³).
- (2) The depth of the unprotected ceiling pocket does not exceed 12 in. (300 mm).
- (3) The entire floor under the unprotected ceiling pocket is protected by sidewall or pendent sprinklers at the lower ceiling elevation.
- (4) The interior finish of the unprotected ceiling pocket is noncombustible or limited-combustible construction.

N 6.2.3.4.3 Ceiling Pockets Where Protected with Quick-Response Pendent or Upright Sprinklers.

N 6.2.3.4.3.1 Sprinklers shall be required in all ceiling pockets.

Table 6.2.3.3.3 Minimum Distances for Ordinary and Intermediate Temperature Residential Sprinklers

Heat Source	From Edge of Source to Ordinary Temperature Sprinkler		From Edge of Source to Intermediate Temperature Sprinkler	
	in.	mm	in.	mm
Side of open or recessed fireplace	36	900	12	300
Front of recessed fireplace	60	1500	36	900
Coal- or wood- burning stove	42	1050	12	300
Kitchen range	18	450	9	225
Wall oven	18	450	9	225
Hot air flues	18	450	9	225
Uninsulated heat ducts	18	450	9	225
Uninsulated hot water pipes	12	300	6	150
Side of ceiling- or wall-mounted hot air diffusers	24	600	12	300
Front of wall-mounted hot air diffusers	36	900	18	450
Hot water heater or furnace	6	150	3	75
Light fixture:				
0 W–250 W	6	150	3	75
250 W–499 W	12	300	6	150

N 6.2.3.4.3.2 The requirement of 6.2.3.4.3.1 shall not apply where all of the following requirements are met:

- (1) The total volume of the unprotected ceiling pocket does not exceed 1000 ft³ (28 m³).
- (2) The depth of the unprotected ceiling pocket does not exceed 36 in. (900 mm).
- (3) The entire floor under the unprotected ceiling pocket is protected by the sprinklers at the lower ceiling elevation.
- (4) The total size of all unprotected ceiling pockets in the same compartment within 10 ft (3 m) of each other does not exceed 1000 ft³ (28 m³).
- (5) The unprotected ceiling pocket has noncombustible or limited-combustible finishes.
- (6) Quick-response sprinklers are utilized throughout the compartment.
- (7) The design area is in accordance with NFPA 13.

6.2.4 Exposed Barrel Lengths.

Δ 6.2.4.1* Where dry sprinklers are connected to wet pipe sprinkler systems protecting areas subject to freezing temperatures, the minimum exposed length of the barrel of the dry sprinkler shall be in accordance with Table 6.2.4.1.

6.2.4.2 The minimum barrel length shall be measured from the face of the fitting to which the dry sprinkler is installed to the inside surface of the insulation, wall, or ceiling leading to the cold space, whichever is closer to the fitting.

6.3 Quick-Response Sprinklers. Where quick-response sprinklers are installed in accordance with 6.2.1.3, 6.2.1.4, or 6.2.2.1, the maximum allowable spacing, minimum allowable spacing, obstruction criteria, and distance from the ceiling shall be in accordance with NFPA 13.

Δ Table 6.2.4.1 Minimum Exposed Barrel Lengths for Dry Sprinklers

Average Annual Extreme Minimum Temperature Exposed to Discharge End of Sprinkler		Minimum Exposed Barrel Length					
		When Exposed to 40°F (4°C)		When Exposed to 50°F (10°C)		When Exposed to 60°F (16°C)	
°F	°C	in.	mm	in.	mm	in.	mm
40	4	0	0	0	0	0	0
30	-1	0	0	0	0	0	0
20	-7	4	100	0	0	0	0
10	-12	8	200	1	25	0	0
0	-18	12	300	3	75	0	0
-10	-23	14	360	4	100	1	25
-20	-29	14	360	6	150	3	75
-30	-34	16	400	8	200	4	100
-40	-40	18	460	8	200	4	100
-50	-46	20	510	10	250	6	150
-60	-51	20	510	10	250	6	150

6.4 Residential Sprinklers.

6.4.1 Residential Sprinklers That Have Been Listed with Specific Coverage Criteria. Sprinklers shall be installed in accordance with the coverage criteria specified by the listing.

6.4.2 Sloped Ceilings.

6.4.2.1 Where the ceiling is sloped, the maximum S dimension shall be measured along the slope of the ceiling to the next sprinkler or wall as shown in Figure 6.4.2.1.

6.4.2.2 The sprinklers shall maintain the minimum listed spacing, but not less than 8 ft (2.4 m), measured in the plan view from one sprinkler to another as shown in Figure 6.4.2.1.

6.4.2.3 Sprinklers under or near the peak of a roof or ceiling shall have deflectors located not more than 36 in. (900 mm) vertically down from the peak as indicated in Figure 6.4.2.1.

6.4.3 Sprinklers shall be installed in accordance with their listing where the type of ceiling configuration is referenced in the listing.

6.4.4* Where construction features or other special conditions exist that are outside the scope of sprinkler listings, listed sprinklers shall be permitted to be installed beyond their listing limitations.

6.4.5 Operating Pressure. The minimum operating pressure of any sprinkler shall be the higher of the minimum operating pressure specified by the listing or 7 psi (0.5 bar).

6.4.6 Position of Residential Sprinklers.

6.4.6.1 Pendent and Upright Sprinklers.

6.4.6.1.1 Pendent and upright sprinklers that have not been listed with specific positioning criteria or deflector-to-ceiling distances shall be positioned so that the deflectors are within

1 in. to 4 in. (25 mm to 100 mm) of the ceiling unless otherwise permitted by 6.4.6.1.1.1.

6.4.6.1.1.1* Pendent-type residential sprinklers located under or adjacent to beams in accordance with 7.1.1.3.1 shall be installed in accordance with one of the following:

- (1) Pendent, recessed pendent, **concealed**, and flush-type pendent sprinklers shall be permitted to be installed directly under a beam having a maximum depth of 14 in. (350 mm) with the sprinkler deflector 1 in. to 2 in. (25 mm to 50 mm) below the beam, or in accordance with the manufacturer's instructions for recessed or flush sprinklers if the deflector is less than 1 in. (25 mm) below the beam, as shown in Figure 6.4.6.1.1(a).
- (2) Pendent sprinklers shall be permitted to be installed adjacent to beams where the vertical centerline of the sprinkler is no greater than 2 in. (50 mm) from the edge of the beam and with the sprinkler deflector 1 in. to 2 in. (25 mm to 50 mm) below the beam, or in accordance with the manufacturer's instructions for flush sprinklers if the deflector is less than 1 in. (25 mm) below the beam, as shown in Figure 6.4.6.1.1(b).

6.4.6.1.2 Pendent and upright sprinklers that have been listed with specific positioning criteria shall be positioned in accordance with the listing.

6.4.6.1.3 Except as permitted by 6.4.6.3.2, pendent and upright sprinklers shall be located a minimum of 4 in. (100 mm) from a wall.

6.4.6.2 Sidewall Sprinklers.

6.4.6.2.1 Sidewall sprinklers that have not been listed with specific positioning criteria shall be positioned so that the deflectors are within 4 in. to 6 in. (100 mm to 150 mm) of the ceiling.




FIGURE 6.4.2.1 Measuring S Dimension.




FIGURE 6.4.6.1.1(a) Position of Sprinkler Under a Beam.

6.4.6.2.2 Sidewall sprinklers that have been listed with specific positioning criteria shall be positioned in accordance with the listing.

6.4.6.2.3 Residential horizontal sidewall sprinkler deflectors shall be located no more than 6 in. (150 mm) from the wall on which they are mounted.

6.4.6.3* Obstructions to Residential Sprinklers.

6.4.6.3.1* Except as otherwise permitted in 6.4.6.3, residential sprinklers shall provide complete coverage of the floor area within the compartments requiring sprinkler protection.

6.4.6.3.2* Within Closets and Compartments. In all closets and compartments that are not larger than 400 ft³ (11 m³), including those housing mechanical equipment, pendent, upright, and sidewall residential sprinklers shall be permitted to be installed in either of the following situations:

- (1) Within 18 in. (450 mm) of the ceiling to avoid obstructions near the ceiling where the compartment is enclosed by walls and a door
- (2) At the highest ceiling level without regard to obstructions or minimum distances to walls

6.4.6.3.3 Shadow Areas.

6.4.6.3.3.1* Shadow areas shall be permitted in the protection area of a sprinkler if the cumulative dry areas do not exceed 15 ft² (1.4 m²) per sprinkler.

(A) Shadow areas shall be permitted to exceed 15 ft² (1.4 m²) in closets and compartments 400 ft³ (11 m³) or less in accordance with 6.4.6.3.2.

6.4.6.3.3.2 Shadow areas in corridors up to 2 ft (0.61 m) in depth and up to 9 ft (2.7 m) in length behind sidewall sprinklers shall be permitted as shown in Figure 6.4.6.3.3.2.

6.4.6.3.3.3 Small areas created by architectural features such as planter box windows, bay windows, and similar features shall be evaluated as follows:

- (1) Where no additional floor area is created by the architectural feature, no additional sprinkler protection is required.




FIGURE 6.4.6.1.1(b) Position of Sprinkler Adjacent to a Beam.

- (2) Where additional floor area is created by an architectural feature, no additional sprinkler protection is required, provided all of the following conditions are met:

- (a) The floor area shall not exceed 18 ft² (1.7 m²).
- (b) The floor area shall not be greater than 2 ft (0.61 m) in depth at the deepest point of the architectural feature to the plane of the primary wall where measured along the finished floor.
- (c) The floor shall not be greater than 9 ft (2.7 m) in length where measured along the plane of the primary wall.
- (d) Measurement from the deepest point of the architectural feature to the sprinkler shall not exceed the maximum listed spacing of the sprinkler.

- (3) The hydraulic design is not required to consider the area created by the architectural feature.




FIGURE 6.4.6.3.3.2 Shadow Areas Behind Sidewall Sprinklers in Corridors.

6.4.6.3.4 Pendent Sprinklers.

6.4.6.3.4.1 Pendent sprinklers shall be located at least 3 ft (914 mm) from obstructions such as ceiling fans and light fixtures unless the requirements of 6.4.6.3.4.5 or 6.4.6.3.6 are met.

6.4.6.3.4.2 The distance shall be measured from the center of the sprinkler to the center of the obstruction.

6.4.6.3.4.3 Where the sprinkler cannot be located 3 ft (914 mm) from the obstruction (as measured from the center of the obstruction), an additional sprinkler shall be located on the other side of the obstruction.

6.4.6.3.4.4 Where the area of the fan blades encompasses more than 50 percent of the area of the plan view, the sprinkler shall be installed in accordance with 6.4.6.3.6.

6.4.6.3.4.5* In hallways up to 6 ft (1.8 m) in width, sprinklers shall be permitted to be located adjacent to obstructions where the sprinkler is installed in the allowable obstruction zone as shown in Figure 6.4.6.3.4.5 and the closest edge of the obstruction is a minimum of 12 in. (300 mm) away from the centerline of the sprinkler.

6.4.6.3.5 Sidewall Sprinklers.

6.4.6.3.5.1 Sidewall sprinklers shall be located at least 5 ft (1.5 m) from obstructions such as ceiling fans and light fixtures unless the requirements of 6.4.6.3.5.5 or 6.4.6.3.7 are met.

6.4.6.3.5.2 The distance shall be measured from the center of the sprinkler to the center of the obstruction.

6.4.6.3.5.3 Where the sprinkler cannot be located 5 ft (1.5 m) from the obstruction (as measured to the center of the obstruction), an additional sprinkler shall be installed on the other side of the obstruction.

6.4.6.3.5.4 Where the area of the fan blades encompasses more than 50 percent of the area of the plan view, the sprinkler shall be installed in accordance with 6.4.6.3.6.

6.4.6.3.5.5* Obstruction in Hallway — Sidewall Sprinkler. In hallways up to 6 ft (1.8 m) in width, sprinklers shall be permitted to be located adjacent to obstructions where the sprinkler is installed in the allowable obstruction zone as shown in Figure 6.4.6.3.5.5 and closest edge of the obstruction is a minimum of 12 in. (300 mm) away from the deflector.

6.4.6.3.6 Continuous Obstructions to Pendent Sprinklers.

6.4.6.3.6.1 Sprinklers shall be positioned with respect to continuous obstructions in accordance with 6.4.6.3.6.2, 6.4.6.3.6.3, or 6.4.6.3.6.4.

6.4.6.3.6.2 Sprinklers shall be positioned with respect to continuous obstructions in accordance with Table 6.4.6.3.6.2 and Figure 6.4.6.3.6.2.

6.4.6.3.6.3 Sprinklers shall be positioned with respect to an obstruction against a wall in accordance with Figure 6.4.6.3.6.3(a), Figure 6.4.6.3.6.3(b), or Figure 6.4.6.3.6.3(c).

6.4.6.3.6.4 A sprinkler shall be installed on the other side of the obstruction.





FIGURE 6.4.6.3.4.5 Obstruction in Hallway — Pendent Sprinkler.



▲ FIGURE 6.4.6.3.5.5 Obstruction in Hallway — Sidewall Sprinkler.

6.4.6.3.7 Continuous Obstructions to Sidewall Sprinklers.

6.4.6.3.7.1 Sprinklers shall be positioned with respect to continuous obstructions in accordance with 6.4.6.3.7.2 or 6.4.6.3.7.3.

▲ 6.4.6.3.7.2 Sprinklers shall be positioned with respect to continuous obstructions in accordance with Table 6.4.6.3.7.2(a), Figure 6.4.6.3.7.2(a), Table 6.4.6.3.7.2(b), Figure 6.4.6.3.7.2(b), Figure 6.4.6.3.7.2(c), and Figure 6.4.6.3.7.2(d).

6.4.6.3.7.3 A sprinkler shall be installed on the other side of the obstruction.

6.4.6.3.8 Soffits and Cabinets. Where soffits are used for the installation of sidewall sprinklers, the sprinklers and soffits shall be installed in accordance with 6.4.6.3.8.1, 6.4.6.3.8.2, or 6.4.6.3.8.3.

6.4.6.3.8.1 Where soffits exceed more than 8 in. (203 mm) in width or projection from the wall, pendent sprinklers shall be installed under the soffit.

6.4.6.3.8.2 Sidewall sprinklers shall be permitted to be installed in the face of a soffit located directly over cabinets, without requiring additional sprinklers below the soffit or cabinets, where the soffit does not project horizontally more than 12 in. (300 mm) from the wall.

6.4.6.3.8.3 Where sidewall sprinklers are more than 3 ft (914 mm) above the top of cabinets, the sprinkler shall be permitted to be installed on the wall above the cabinets where the cabinets are no greater than 12 in. (305 mm) from the wall.

6.5 Special Situations.

6.5.1 Return Bends.

▲ 6.5.1.1 Unless the requirements of 6.5.1.3 are met, return bends shall be used where pendent sprinklers are supplied from a raw water source, a millpond, or open-top reservoirs.

6.5.1.2 Return bends shall be connected to the top of branch lines in order to avoid accumulation of sediment in the drop nipples in accordance with Figure 6.5.1.2.

6.5.1.3 Return bends shall not be required where dry pendent sprinklers are used.

6.5.2 Dry Pipe Underground.

6.5.2.1 Where necessary to place pipe that is under air pressure underground, the pipe shall be protected against corrosion.

▲ Table 6.4.6.3.6.2 Positioning of Sprinklers to Avoid Obstructions to Discharge (Residential Upright and Pendent)

Distance from Sprinkler to Side of Obstruction (A)		Allowable Distance of Deflector Above Bottom of Obstruction (B)	
ft	mm	in.	mm
Less than 1.5 ft	Less than 450	0	0
1.5 or more	450 or more	1	25
3 or more	900 or more	3	75
4 or more	1200 or more	5	125
4.5 or more	1400 or more	7	175
6 or more	1800 or more	9	225
6.5 or more	2000 or more	11	275
7 or more	2100 or more	14	350
8 or more	2400 or more	15	375
8.5 or more	2600 or more	17	425
9 or more	2700 or more	19	475

Note: For A and B, refer to Figure 6.4.6.3.6.2.






FIGURE 6.4.6.3.6.2 Positioning of Sprinkler to Avoid Obstruction to Discharge (Residential Upright and Pendent Spray Sprinklers).


6.5.2.2 Unprotected cast-iron or ductile-iron pipe shall be permitted where joined with a gasketed joint listed for air service underground.



Δ FIGURE 6.4.6.3.6.3(a) Positioning of Sprinkler to Avoid Obstructions Against Walls — Scenario 1 (Residential Upright and Pendent Spray Sprinklers).



N FIGURE 6.4.6.3.6.3(c) Positioning of Sprinklers to Avoid Obstructions Against Walls — Scenario 3 (Residential Upright and Pendent Spray Sprinklers).



Δ FIGURE 6.4.6.3.6.3(b) Positioning of Sprinkler to Avoid Obstructions Against Walls — Scenario 2 (Residential Upright and Pendent Spray Sprinklers).

Table 6.4.6.3.7.2(a) Positioning of Sprinklers to Avoid Obstructions (Residential Sidewall Sprinklers)

Distance from Sidewall Sprinkler to Side of Obstruction (A)		Allowable Distance of Deflector Above Bottom of Obstruction (B)	
ft	mm	ft	mm
Less than 8	Less than 2400	0	0
8 or more	2400 or more	1	25
10 or more	3000 or more	2	50
11 or more	3400 or more	3	75
12 or more	3700 or more	4	100
13 or more	4000 or more	6	150
14 or more	4300 or more	7	175
15 or more	4600 or more	9	225
16 or more	4900 or more	11	275
17 or more	5200 or more	14	350

For SI units, 1 in. = 25 mm; 1 ft = 0.30 m.

Note: For A and B, refer to Figure 6.4.6.3.7.2(a).

Table 6.4.6.3.7.2(b) Positioning of Sprinklers to Avoid Obstructions Along Wall (Residential Sidewall Sprinklers)

Distance from Sidewall Sprinkler to Side of Obstruction (A)		Allowable Distance of Deflector Above Bottom of Obstruction (B)	
ft	mm	in.	mm
Less than 1 ft 6 in.	Less than 450	0	0
1 ft 6 in. or more	450 or more	1	25
3 ft or more	900 or more	3	75
4 ft or more	1200 or more	5	125
4 ft 6 in. or more	1400 or more	7	175
6 ft or more	1800 or more	9	225
6 ft 6 in. or more	2000 or more	11	275
7 ft to less than 7 ft 6 in.	2200 to less than 2300	14	350

For SI units, 1 in. = 25 mm; 1 ft = 0.30 m.

Note: For A and B, refer to Figure 6.4.6.3.7.2(b).




FIGURE 6.4.6.3.7.2(a) Positioning of Sprinkler to Avoid Obstruction (Residential Sidewall Sprinklers).




FIGURE 6.4.6.3.7.2(b) Positioning of Sprinkler to Avoid Obstruction Along Wall (Residential Sidewall Sprinklers).





FIGURE 6.4.6.3.7.2(c) Positioning of Sprinkler to Avoid Obstructions Against Walls — Scenario 1 (Residential Sidewall Sprinklers).

6.5.3* Sprinkler-Protected Glazing. Where sprinklers are used in combination with glazing as an alternative to a required fire-rated wall or window assembly, the sprinkler-protected assembly shall comply with the following:

- (1) Sprinklers shall be listed as specific application window sprinklers unless the standard spray sprinklers are specifically permitted by the building code.
- (2) Sprinklers shall be supplied by a wet-pipe system.
- (3) Glazing shall be heat-strengthened, tempered, or glass ceramic and shall be fixed.
- (4) Where the assembly is required to be protected from both sides, sprinklers shall be installed on both sides of the glazing.
- (5) The use of sprinkler-protected glazing shall be limited to non-load-bearing walls.
- (6) The glazed assembly shall not have any horizontal members that would interfere with uniform distribution of water over the surface of the glazing, and there shall be no obstructions between sprinklers and glazing that would obstruct water distribution.



N FIGURE 6.4.6.3.7.2(d) Positioning of Sprinkler to Avoid Obstructions Against Walls — Scenario 2 (Residential Sidewall Spray Sprinklers).




FIGURE 6.5.1.2 Return Bend Arrangement.

- (7) The water supply duration for the design area that includes the window sprinklers shall not be less than the required rating of the assembly.

6.5.4 Waste and Linen Handling Systems.

6.5.4.1 A sprinkler shall be installed within the chute at alternate floor levels in buildings over two stories in height, with a mandatory sprinkler located at the lowest service level.

6.5.4.2 Gravity chutes shall be protected internally by automatic sprinklers unless they are lined in accordance with 6.2.2.6.1 of NFPA 82.

6.6 Location of Sprinklers.

6.6.1 Sprinklers shall be installed in all areas except where omission is permitted by 6.6.2 through 6.6.7.

6.6.2* Sprinklers shall not be required in bathrooms in dwelling units where the bathroom area does not exceed 55 ft² (5.1 m²).

6.6.3 Except where specified in 6.6.4, sprinklers shall not be required in clothes closets, linen closets, and pantries within dwelling units that meet all of the following conditions:

- (1) The area of the space does not exceed 24 ft² (2.2 m²).
- (2) The walls and ceilings are surfaced with noncombustible or limited-combustible materials as defined by NFPA 220.

6.6.4* Sprinklers shall be installed in any closet used for heating or air-conditioning equipment, washers, dryers, or water heaters except as permitted by 6.6.7.

Δ 6.6.5* Except as provided for in 6.6.5.1 and 6.6.5.2, sprinklers shall not be required in any of the following features that are open and attached:

- (1) Porches, balconies, lanais, verandas, awnings, or similar areas
- (2) Trellis overhangs
- (3) Carports
- (4) Porte cocheres
- (5) Stairs
- (6) Corridors that are not part of a means of egress
- (7) Other similar features

Δ 6.6.5.1* Where a roof, deck, or balcony greater than 4 ft (1.2 m) wide is provided above, sprinklers shall be installed to protect attached exterior balconies, attached exterior decks, and ground floor patios directly serving dwelling units in buildings of Type V construction.

Δ 6.6.5.1.1 Where sprinklers are installed beneath roofs, overhangs, decks, or balconies, sprinklers shall be permitted to be installed with deflectors positioned in accordance with 6.6.5.1.1.1, 6.6.5.1.1.2, or 6.6.5.1.1.3.

N 6.6.5.1.1.1 Sidewall sprinklers shall not be less than 4 in. (100 mm) or more than 6 in. (150 mm) below a smooth ceiling and not less than 1 in. (25 mm) or more than 6 in. (150 mm) below exposed structural members, provided that the deflector is not more than 14 in. (350 mm) below the underside surface of the deck above the exposed structural members.

N 6.6.5.1.1.2 Upright and pendent residential sprinklers shall be installed in accordance with 6.4.6.1.

N 6.6.5.1.1.3 Upright and pendent quick-response sprinklers shall be installed in accordance with the spacing and location requirements of NFPA 13.

N 6.6.5.2 Sprinkler protection shall be provided for corridors and balconies that are part of a means of egress.

6.6.6* Sprinklers shall not be required in attics, penthouse equipment rooms, elevator machine rooms, concealed spaces dedicated exclusively to and containing only dwelling unit ventilation equipment, crawl spaces, floor/ceiling spaces, vertical chases, elevator shafts where the elevator installation complies with ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, and other concealed spaces that are not intended for living purposes or storage and do not contain fuel-fired equipment.

6.6.6.1 When fuel-fired equipment is present, at least one quick-response intermediate temperature sprinkler shall be installed above the equipment.

6.6.6.2 Spaces that contain fuel-fired equipment shall also comply with 6.6.6.3 or 6.6.6.4.

6.6.6.3 Where the fuel-fired equipment is above all occupied areas, sprinkler protection shall not be required in the concealed space.

6.6.6.4 Where fuel-fired equipment is below or on the same level as occupied areas, at least one quick-response intermediate-temperature sprinkler shall be installed above the equipment or at the wall separating the space with the fuel-fired equipment from the occupied space.

6.6.7 Sprinklers shall not be required in closets (regardless of size) on exterior balconies if all of the following conditions are met:

- (1) The closet does not have doors leading directly into the dwelling unit.
- (2) The closet does not have unprotected penetrations directly into the dwelling unit.
- (3) The balcony is not used as a means of egress.

6.6.8 All situations regarding sprinkler location and position that are not directly discussed in NFPA 13R shall be in accordance with NFPA 13.

6.6.9 Interior Stairwells.

6.6.9.1 Except as allowed by 6.6.9.2, 6.6.9.3, and 6.6.9.4, sprinklers shall be installed throughout all interior, enclosed stairwells.

6.6.9.2* Sprinklers shall not be required underneath stair risers in dwelling units where the walls and ceilings are surfaced with noncombustible or limited-combustible finishes.

6.6.9.3 Closets located underneath stairs shall be protected in accordance with 6.4.6.3.2, 6.6.3, 6.6.4, and 6.6.7.

6.6.9.4 Interior stairwells located outside the dwelling unit shall be protected in accordance with NFPA 13.

6.7 Piping.

6.7.1 Installation of Piping.

6.7.1.1 Where solvent cement is used as the pipe and fittings bonding agent, sprinklers shall not be installed in the fittings prior to the fittings being cemented in place.

6.7.1.2 In existing buildings, CPVC cut-ins to active fire sprinkler systems shall follow the manufacturer's recommended cut-in procedure.

6.7.2 Protection of Piping.

6.7.2.1* Freezing. Where aboveground water-filled supply pipes, risers, system risers, feed mains, or branch lines pass through open areas, cold rooms, passageways, or other areas exposed to freezing temperatures, the pipe shall be protected against freezing by insulating coverings, frostproof casings, listed heat tracing systems, or other reliable means capable of maintaining a minimum temperature between 40°F and 120°F (4°C and 48.9°C). (See also 5.4.2.)

6.7.2.1.1 Piping shall be permitted to be exposed to temperatures less than 40°F (4°C) when in accordance with 5.4.4.

N 6.7.2.1.2* The weather temperature used to determine if an unconditioned portion of a system is subject to freezing and required to be protected in accordance with 6.7.2.1 shall be the

average annual extreme minimum temperature, obtained from an approved source.

6.7.2.2 Heat Tracing.

6.7.2.2.1 Where listed heat tracing systems are used, they shall be supervised.

6.7.2.2.1.1 Electric supervision of the heat tracing system shall provide positive confirmation that the circuit is energized.

6.7.2.2.2 Where listed heat tracing is utilized for branch lines, it shall be specifically listed for use on branch lines.

6.7.2.2.3 Heat tracing systems shall be supervised by one of the following methods:

- (1) Central station, proprietary, or remote station signaling service
- (2) Local signaling service that will cause a signal at a constantly attended location

6.7.2.3 Corrosion.

6.7.2.3.1 Where corrosive conditions are known to exist due to moisture or fumes from corrosive chemicals, or both, special types of fittings, pipes, and hangers that resist corrosion shall be used, or a protective coating shall be applied to all unprotected exposed surfaces of the sprinkler system.

6.7.2.3.2 Where water supplies are known to have unusual corrosive properties and threaded or cut-groove steel pipe is to be used, wall thickness shall be in accordance with Schedule 30 [in sizes 8 in. (200 mm) or larger] or Schedule 40 [in sizes less than 8 in. (200 mm)].

6.7.2.3.3 Where corrosive conditions exist or piping is exposed to the weather, corrosion-resistant types of pipe, fittings, and hangers or protective corrosion-resistant coatings shall be used.

6.7.2.3.4 Where steel pipe is used underground, the pipe shall be protected against corrosion.

6.7.2.4 Hazardous Areas.

6.7.2.4.1 Private service main aboveground piping shall not pass through hazardous areas, except as permitted in 6.7.2.4.2, and shall be located so that it is protected from mechanical and fire damage.

6.7.2.4.2 Private service main aboveground piping shall be permitted to be located in hazardous areas protected by an automatic sprinkler system.

6.7.2.5 Risers Subject to Mechanical Damage. Sprinkler risers subject to mechanical damage shall be protected by steel posts, concrete barriers, or other approved means.

6.8 Valves.

6.8.1 A single control valve arranged to shut off both the domestic system and the sprinkler system shall be installed for systems with common sprinkler/domestic mains unless a separate shutoff valve for the sprinkler system is installed in accordance with 6.8.2.

6.8.2 The sprinkler system piping shall not have a separate control valve installed unless supervised by one of the following methods:

- (1) Central station, proprietary, or remote station alarm service

- (2) Local alarm service that causes the sounding of an audible signal at a constantly attended location
- (3) Valves that are locked open

6.8.3 A separate shutoff valve shall be installed for the domestic water supply in installations having a common sprinkler/domestic main.

6.8.4 System control or shutoff valves shall be of the slow-closing type.

6.8.5 A listed backflow prevention assembly shall be considered a check valve, and an additional check valve shall not be required.

6.8.6 A listed backflow prevention assembly shall be considered a control valve, and an additional control valve shall not be required.

6.8.7 The control valve for a system or portion of a system protecting a dwelling unit shall not be located in a different dwelling unit than the unit it serves.

6.8.8 In multistory buildings, a control valve per floor shall not be required.

6.8.9* Backflow Prevention Valves. Means shall be provided downstream of all backflow prevention valves for forward flow tests at a minimum flow rate of the system demand.

6.8.10* Each connection from a standpipe that is part of a combined system to a sprinkler system or floor shall have an individual control valve and check valve.

6.9* Drains.

6.9.1 Each sprinkler system shall have a drain on the system side of the control valve.

6.9.2 The drain pipe shall be at least 1 in. (25 mm) nominal diameter.

6.9.3 A valve shall be installed in the drain piping.

6.9.4 A ½ in. (13 mm) drain shall be installed for each trapped portion of a dry system that is subject to freezing temperatures.

6.10* Test Connection.

6.10.1 Each sprinkler system shall have a test connection.

6.10.2 The test connection pipe shall be at least 1 in. (25 mm) nominal diameter and terminate in an orifice equal to or smaller than the same size as the smallest sprinkler installed in the system.

6.10.3 A valve shall be installed in the test connection piping.

6.10.4 The test connection shall be permitted to be located at any point on the system side of the alarm flow device.

6.10.5 When the drain required in 6.9.1 is arranged as a test connection, a separate test connection shall not be required.

6.11* Fire Department Connection.

6.11.1 At least one fire department connection shall be provided for buildings, accessible by a fire department, that exceed 2000 ft² (185 m²) or are more than a single story.

6.11.2 Fire department connection inlets shall be at least 1½ in. (40 mm).

6.11.3 Each fire department connection to sprinkler systems shall be designated by a sign having raised or engraved letters at least 1 in. (25 mm) in height on plate or fitting reading service design — for example, AUTOSPKR., OPEN SPKR., AND STANDPIPE.

6.11.4 The piping between the check valve and the outside hose coupling shall be equipped with an approved automatic drip in areas subject to freezing.

6.11.5* Fire department connections shall be permitted to connect to the underground piping dedicated to the sprinkler system where the pipe is rated for a pressure of at least 175 psi (12 bar).

6.11.5.1 Where the underground pipe is nonmetallic, the pressure rating shall be based on a temperature of at least 120°F (50°C).

6.11.6 In buildings with mixed occupancies where the nonresidential occupancy/occupancies is protected with an NFPA 13 system, a single fire department connection in accordance with NFPA 13 shall be permitted.

6.12 Pressure Gauges.

6.12.1 A pressure gauge with shutoff valve shall be provided to indicate pressure of the supply.

6.12.2 A pressure gauge with shutoff valve shall be provided to indicate pressure of the system.

6.13* Piping Support. Piping hanging and bracing methods shall comply with NFPA 13.

6.14 Open-Grid Ceilings. Open-grid ceilings shall be installed only as permitted by NFPA 13.

6.15 Drop-Out Ceilings. Drop-out ceilings shall be permitted to be installed beneath sprinklers where ceilings are listed for that service and are installed in accordance with their listings.

6.16* Alarms.

6.16.1 A local waterflow alarm shall be provided on all sprinkler systems.

6.16.2 Where a building fire alarm system is provided, the local waterflow alarms shall be connected to the building fire alarm system.

6.16.3 Waterflow alarms shall be installed in accordance with NFPA 13.

6.16.4 Where a building fire alarm system is provided, the building fire sprinkler system shall not be required to be zoned by floor.

Chapter 7 Design Criteria

7.1 Inside Dwelling Unit.

Δ 7.1.1 Residential Sprinklers.

7.1.1.1* The system shall provide at least the flow required to produce a minimum discharge density of 0.05 gpm/ft² (2.04 mm/min) or the sprinkler listing, whichever is greater, to the design sprinklers.

7.1.1.2 Listed flows associated with testing under a smooth, flat, horizontal 8 ft (2.4 m) high ceiling shall be permitted to be used for the ceiling configurations referenced in 7.1.1.3.1.

7.1.1.3* Number of Design Sprinklers.

7.1.1.3.1 For each of the following situations, the number of sprinklers in the design area shall be all of the sprinklers within a compartment, up to a maximum of four sprinklers, that require the greatest hydraulic demand:

- (1) A flat, smooth, horizontal ceiling with no beams up to a maximum of 24 ft (7.3 m) above the floor.
- (2) A flat, horizontal, beamed ceiling, with a maximum ceiling height of 24 ft (7.3 m), with beams up to 14 in. (350 mm) deep with pendent sprinklers under the beams. The compartment containing the beamed ceiling shall be a maximum of 600 ft² (56 m²) in area. The highest sprinkler in the compartment shall be above all openings from the compartment into any communicating spaces.
- (3) A smooth, flat, sloped ceiling with no beams up to a maximum slope of 8 in 12. The highest portion of the ceiling shall not be more than 24 ft (7.3 m) above the floor. The highest sprinkler in the sloped portion of the ceiling shall be above all openings from the compartment containing the sloped ceiling into any communicating spaces.
- (4) A sloped ceiling with beams up to 14 in. (355 mm) deep with pendent sprinklers under the beams. The compartment containing the sloped, beamed ceiling shall be a maximum of 600 ft² (55 m²) in area. The slope of the ceiling shall be between 2 in 12 and 8 in 12. The highest portion of the ceiling shall not be more than 24 ft (7.3 m) above the floor. The highest sprinkler in the sloped portion of the ceiling shall be above all openings from the compartment containing the sloped ceiling into any communicating spaces.
- (5) A sloped ceiling with beams of any depth with sidewall or pendent sprinklers in each pocket formed by the beams. The compartment containing the sloped, beamed ceiling shall be a maximum of 600 ft² (56 m²) in area. The slope of the ceiling shall be between 2 in 12 and 8 in 12. The highest portion of the ceiling shall not be more than 24 ft (7.3 m) above the floor.

7.1.1.3.2 For situations not meeting one of the conditions in 7.1.1.3.1, residential sprinklers listed for use in specific ceiling configurations shall be permitted to be used in accordance with their listing.

7.1.1.3.3* For situations not meeting one of the conditions in 7.1.1.3.1 and 7.1.1.3.2, the number of sprinklers in the design area shall be determined in consultation with the authority having jurisdiction as appropriate for the conditions.

7.1.2 Quick-Response Sprinklers. Where quick-response sprinklers are used in accordance with 6.2.1.3, the discharge and design area requirements of NFPA 13 shall apply.

7.2* Outside Dwelling Unit.

7.2.1 Areas outside the dwelling unit shall comply with Section 7.2.

Δ 7.2.2 The number of design sprinklers for a corridor outside the dwelling unit shall include up to the four most hydraulically demanding adjacent sprinklers.

7.2.3 The design discharge and design area criteria for areas protected by quick-response sprinklers shall comply with NFPA 13 except as allowed by 7.2.3.1.

7.2.3.1 For compartments 500 ft² (46 m²) or less that meet all of the following conditions and are protected with quick-response sprinklers, the design area shall be permitted to be limited to the number of sprinklers in the compartment but shall not exceed four sprinklers:

- (1) The area is protected with 30 minute-rated construction.
- (2) The sprinklers are spaced at 225 ft² (20 m²) maximum for light hazard, 130 ft² (12 m²) maximum for ordinary hazard, or in accordance with their listing.
- (3) Openings have a lintel depth at least 8 in. (200 mm) in depth.
- (4) The total area of openings, excluding any overhead doors that open to the exterior, does not exceed 50 ft² (4.6 m²) for each compartment.
- (5) Discharge densities are in accordance with NFPA 13.

7.2.4 Where residential sprinklers are used outside the dwelling unit as allowed by 6.2.2.2, the discharge criteria shall be in accordance with Section 7.1, except as modified by 7.2.4.1.

7.2.4.1 Residential sprinklers shall be permitted to be used in ordinary-hazard areas that meet the following conditions:

- (1) The area is compartmented into 500 ft² (46 m²) or less by 30-minute fire-rated construction.
- (2) The sprinklers are spaced at 130 ft² (12 m²) per sprinkler.
- (3) Openings have a lintel at least 8 in. (200 mm) in depth.
- (4) The total area of openings, excluding any overhead garage doors that open to the exterior, does not exceed 50 ft² (4.6 m²) for each compartment.
- (5) Discharge densities are in accordance with NFPA 13 for ordinary hazard.

7.3 Garages.

7.3.1 Garages that are completely separated from the residential portion of the building by fire-resistive construction sufficient to have them considered separate buildings under the local code shall be protected in accordance with NFPA 13.

7.3.2 Garages that are accessible by people from more than one dwelling unit, and are not covered by 7.3.1, shall be considered part of the building and shall be protected in accordance with Section 7.2.

7.3.2.1 Garage doors shall not be considered obstructions and shall be permitted to be ignored for placement and calculation of sprinklers.

7.3.3 Garages that serve only a single dwelling unit shall be considered as part of that dwelling unit.

7.3.4* Garages that are accessible only from a single dwelling unit shall be considered as part of that dwelling unit.

7.3.4.1 Garages that meet the criteria of 7.3.3 or 7.3.4 shall be protected in accordance with one of the following:

- (1) Use of a residential sprinkler in accordance with Section 7.1
- (2) Use of an extended coverage sprinkler discharging water not less than its listed flow rate for light hazard
- (3) Quick-response spray sprinkler at light-hazard spacing in accordance with NFPA 13 designed to discharge at 0.05 gpm/ft² (2.04 mm/min) density

7.3.4.2 The system demand shall be permitted to be limited to the number of sprinklers in the compartment but shall not exceed four sprinklers.

7.3.4.3 Garage doors shall not be considered obstructions and shall be permitted to be ignored for placement and calculation of sprinklers.

7.4 Attics.

7.4.1 Occupied Attics and Attics Used for Storage. Attics that are intended for occupancy or storage shall comply with Section 7.1, where the attic is part of the dwelling unit, or Section 7.2, where the attic is outside of the dwelling unit.

7.4.1.1 Sprinkler temperature ratings shall comply with 6.2.3.

7.4.2 Fuel-Fired Equipment. Where fuel-fired equipment is installed in an attic that is not otherwise required to have sprinklers, the space containing the fuel-fired equipment shall comply with 6.6.6.1 through 6.6.6.4.

7.4.3* Other Attics. Attics that are not required by 7.4.1 to have sprinklers shall be permitted to have protection in accordance with one of the following.

- (1) Protection complying with NFPA 13
- (2) Protection using sprinklers specifically listed to provide attic protection in residential occupancies using a discharge density of not less than 0.05 gpm/ft² (2.04 mm/min) and a design area of not less than four sprinklers

7.4.3.1 Sprinkler temperature ratings shall comply with 6.2.3.

7.5* Combustible Concealed Spaces. Where unsprinklered combustible concealed spaces are present in a residential occupancy, the design area shall not be required to be increased to 3000 ft² (280 m²) or any other value due to the existence of the unsprinklered concealed spaces, regardless of the type of sprinklers used and whether the area is inside or outside of a dwelling unit.

Chapter 8 Plans and Calculations

8.1 Working Plans.

8.1.1 Working plans shall be submitted for approval to the authority having jurisdiction before any equipment is installed or remodeled.

8.1.2 Deviations from approved plans shall require approval of the authority having jurisdiction.

8.1.3 Working plans shall be drawn to a specified scale.

8.1.4 Sprinkler plans shall be drawn on sheets of uniform size.

8.1.5 Sprinkler plans shall provide a plan of each floor.

8.1.5.1 It shall be acceptable to provide typical floor plans when applicable.

8.1.6 Sprinkler plans shall be capable of being easily duplicated.

Δ 8.1.7 Working plans shall be drawn to an indicated scale, on sheets of uniform size, with a plan of each floor, and shall show those items from the following list that pertain to the design of the system:

- (1) Edition year of this standard to which the sprinkler system is designed
- (2) Project name
- (3) Location, including street address
- (4) Name and address of the contractor
- (5) Point of compass
- (6) A graphic representation of the scale used on all plans
- (7) Full-height cross-section or schematic diagram, including structural member information, if required for clarity, and including ceiling construction and method of protection for nonmetallic piping
- (8) Ceiling/roof height and slopes not shown in the full-height cross section
- (9) Location of partitions, fire barriers, fire walls, draft curtains, and similar features as they relate to the sprinkler system
- (10) Any small enclosures in which no sprinklers are to be installed
- (11) Location and size of concealed spaces, attics, closets, and bathrooms
- (12) Location of fuel-fired equipment and heating and air-conditioning equipment
- (13) Location of closets on exterior balconies, and any doors or penetration between the closet and the dwelling unit
- (14) Area per floor
- (15) Size of the city main in the street and the city main test results, including elevation of the test hydrant
- (16) Underground pipe size, length, location, weight, material, and point of connection to the city main; type of valves, meters, and valve pits; and depth at which the top of the pipe is laid below grade
- (17) Size and location of hydrants, showing size and number of outlets, including any static and residual hydrants that were used in flow tests
- (18) Size, location, and piping arrangement of fire department connections
- (19) Information about backflow preventers (e.g., manufacturer, size, type)
- (20) Make, manufacturer, type, temperature rating, sprinkler identification number, and nominal k-factor of the sprinkler
- (21) Type and location of high-temperature sprinklers
- (22) Number of sprinklers on each riser, per floor
- (23) Type of pipe and fittings
- (24) Pipe type and schedule of wall thickness
- (25) Nominal pipe size and lengths (lengths as they relate to hydraulic reference points)
- (26) Location and size of riser nipples
- (27) Types of fittings and joints and the locations of all welds and bends
- (28) All control valves, check valves, drain pipes, and test connections
- (29) Information about antifreeze solution used (e.g., type and amount)
- (30) Type and location of alarm bells
- (31) Types and locations of hangers, sleeves, and braces, and methods of securing sprinklers, where applicable
- (32) Where the equipment is to be installed as an addition to an existing system, enough of the existing system indicated on the plans to make all conditions clear
- (33) Hydraulic reference points shown on the plan that correspond with comparable reference points on the hydraulic calculation sheets
- (34) The minimum rate of water application and the design area of water application

- (35) The total quantity of water and the pressure required noted at a common reference point for each system
- (36) Relative elevations of sprinklers, junction points, and supply or reference points

8.2 Hydraulic Calculations.

8.2.1 Pipe Sizing. Piping shall be sized using hydraulic calculation procedures in accordance with NFPA 13.

8.2.2 A hydraulic calculation summary sheet shall be provided as shown in Figure 8.2.2.

PROJECT GENERAL INFORMATION	
Project name _____	Date ____/____/____
Location/address _____	
Owner/occupant _____	
Installing contractor's name _____	Phone (____) _____
Installing contractor's address _____	
Designer _____	Phone (____) _____
Authority having jurisdiction(s) _____	
SYSTEM DESIGN REQUIREMENTS	
Design area name or number _____	NFPA 13R design edition _____
Design area location _____	Drawing/sheet # _____
Dwelling unit calculation <input type="checkbox"/> or Outside dwelling unit calculation <input type="checkbox"/> Other _____	
System type Wet <input type="checkbox"/> Dry or Preaction <input type="checkbox"/> System volume _____ gal	Antifreeze <input type="checkbox"/> Other <input type="checkbox"/>
Sprinkler type Standard coverage <input type="checkbox"/> Extended coverage <input type="checkbox"/> Residential <input type="checkbox"/> Other <input type="checkbox"/>	
Maximum coverage per sprinkler _____ ft ²	
Minimum rate of water application _____ gpm/ft ²	
Design area of application (outside of dwelling unit) _____ ft ²	
Number of sprinklers calculated (dwelling, corridor, garage) _____	
Limitations for extended coverage or special sprinklers _____	

Elevation of highest calculated sprinkler _____ ft	
Total system demand at source (gpm at psi) _____	
Meter size _____	Make and model _____
WATER SUPPLY INFORMATION	
Date of test ____/____/____	Time of test ____ : ____ am/pm
Location of test hydrant _____	
Elevation of test hydrant relative to project finished floor _____ ft	
Location of flow hydrant(s) _____	
Source of water for flow test _____	
Size of fire pump (gpm at psi) _____	Size of water tank (gal) _____
Notes _____	

FIGURE 8.2.2 Summary Sheet for Hydraulic Calculations.

Chapter 9 Water Supplies

9.1 Number of Supplies. Every automatic sprinkler system shall have at least one automatic water supply.

9.2 Capacity. Water supplies shall be capable of providing the required flow and pressure for all design areas determined using the requirements of Chapter 7 and the hydraulic procedures located in NFPA 13.

9.2.1 The water supply shall be capable of supplying the system demand for at least 30 minutes. (See 7.1.1.3.)

9.3 Domestic Demand.

9.3.1 For systems with common domestic/fire mains serving more than one dwelling unit, domestic demand for the building being calculated shall be included as part of the overall system demand unless provisions are made to prevent the domestic waterflow on sprinkler system activation.

Δ 9.3.2 Domestic demand shall be based on one of the following:

- (1) Table 9.3.2(a) and Table 9.3.2(b)
- (2) The locally adopted plumbing code
- (3) Specifications or values from a registered design professional

9.3.2.1 Interpolation of Table 9.3.2(b) shall be allowed when calculating domestic demand.

9.3.3 Domestic demand shall be added to the hydraulic calculations at the point the piping becomes combined or common.

Table 9.3.2(a) Fixture Load Values

Facility Type	Unit
Private Facilities (those within individual dwelling units)	
Bathroom group with flush tank (including lavatory, water closet, and bathtub with shower)	3.6
Bathroom group with flush valve	8
Bathtub	1.4
Dishwasher	1.4
Kitchen sink	1.4
Laundry trays (1 to 3)	1.4
Lavatory	0.7
Shower head	1.4
Washing machine	1.4
Water closet with flush valve	6
Water closet with flush tank	2.2
Public Facilities	
Bathtub	4
Drinking fountain	0
Kitchen sink	4
Lavatory	2
Service sink	3
Shower head	4
Urinal with 1 in. (25 mm) flush valve	10
Urinal with ¾ in. (20 mm) flush valve	5
Urinal with flush tank	3
Washing machine [8 lb (3.63 kg)]	3
Washing machine [16 lb (7.26 kg)]	4
Water closet with flush valve	10
Water closet with flush tank	5

Δ Table 9.3.2(b) Total Estimated Domestic Demand

Total Fixture Load Units [from Table 9.3.3(a)]	Total Demand			
	For Systems with Predominately Flush Tanks		For Systems with Predominately Load Units	
	gpm	L/min	gpm	L/min
1	3	11.5	—	—
2	5	19	—	—
5	10	38	15	57
10	15	57	25	95
20	20	76	35	130
35	25	95	45	170
50	30	115	50	190
70	35	130	60	225
100	45	170	70	265
150	55	210	80	305
200	65	245	90	340
250	75	285	100	380
350	100	380	125	475
500	125	475	150	570
750	175	660	175	660
1000	200	755	200	755
1500	275	1040	275	1040
2000	325	1230	325	1230
3500	500	1900	500	1900

N 9.3.4 For buildings with multiple occupancies that utilize an NFPA 13 system and a single water supply, the calculations for occupancies in accordance with this standard shall use the hose demand or the domestic demand, whichever is greater.

9.3.5 The flow and pressure of a public water supply shall be determined from waterflow test data or other approved method.

• 9.4 Connection from Waterworks System.

9.4.1 The requirements of the public health authority having jurisdiction shall be determined and followed.

9.4.2* Where equipment is installed to guard against possible contamination of the public water system, such equipment and devices shall be listed for fire protection service.

9.5* Types. Water supplies for sprinkler systems shall be one of the following or any combination thereof:

- (1) A connection to an approved public or private waterworks system in accordance with Section 9.6.
- (2) A connection including a fire pump in accordance with Section 9.7.
- (3) A connection to a water storage tank at grade or below grade in accordance with NFPA 22 and filled from an approved source.
- (4) A connection to a pressure tank in accordance with NFPA 13 and NFPA 22 and filled from an approved source.
- (5) A connection to a gravity tank in accordance with NFPA 22 and filled from an approved source.
- (6) A penstock, flume, river, lake, pond, or reservoir in accordance with Section 9.8.
- (7) A source of recycled or reclaimed water where the building owner (or their agent) has analyzed the source of the water and the treatment process (if any) that the water

undergoes before being made available to the sprinkler system and determined that any materials, chemicals, or contaminants in the water will not be detrimental to the components of the sprinkler system it comes in contact with.

9.6 Connections to Waterworks Systems.

9.6.1 A connection to a reliable waterworks system shall be an acceptable water supply source.

9.6.2 The volume and pressure of a public or private water supply shall be determined from waterflow test data or other approved method.

9.6.2.1 Where a waterflow test is used for the purposes of system design, the test shall be conducted no more than 12 months prior to a working plan submittal unless otherwise approved by the authority having jurisdiction.

9.7 Fire Pump.

9.7.1* A single automatically controlled fire pump unit shall be an acceptable water supply source.

9.7.2 Fire pump units shall be designed and installed in accordance with NFPA 20.

9.8 Penstocks, Flumes, Rivers, Lakes, or Reservoirs. Water supply connections from penstocks, flumes, rivers, lakes, or reservoirs shall be arranged to avoid mud and sediment and shall be provided with approved double removable screens or approved strainers installed in an approved manner.

9.9 Non-Fire Protection Connections. Sprinkler systems with non-fire protection connections shall not be permitted.

Chapter 10 System Acceptance

10.1 Approval of Sprinkler Systems.

10.1.1 The installer shall perform all required acceptance tests (*see Section 10.2*) prior to asking for approval of the installation.

Δ 10.1.2* The installer shall complete the contractor's material and test certificate(s) (*see Figure A.10.1.2*) prior to asking for approval of the installation.

10.1.3 The installer shall forward the certificate(s) to the authority having jurisdiction prior to asking for approval of the installation.

10.1.4 Where the authority having jurisdiction is required to be present when acceptance tests are conducted, the installer shall provide advance notification of the time and date the testing will be performed.

10.2 Acceptance Tests.

10.2.1* Flushing of Underground Connections.

10.2.1.1 Underground mains and lead-in connections to system risers shall be flushed before a connection is made to sprinkler piping.

10.2.1.2 The flushing operation shall be continued until the water issuing from the main is clear.

10.2.1.3 The flushing operation shall be performed at the hydraulically calculated water demand rate of the system.

10.2.1.4 The flushing operation shall be performed such that the disposal of water issuing from the test outlets does not damage the property.

10.2.2* Hydrostatic Pressure Tests.

10.2.2.1 Systems having more than 20 sprinklers or having a fire department connection shall pass a hydrostatic pressure test performed for the aboveground piping system in accordance with NFPA 13.

10.2.2.2 Systems having both fewer than 20 sprinklers and no fire department connection shall pass a hydrostatic pressure test performed for the aboveground piping system at 50 psi (3.4 bar) higher than the maximum system pressure, using the hydrostatic test procedure specified in NFPA 13.

N 10.2.3 System Operational Tests.

N 10.2.3.1 Waterflow detecting devices, including the associated alarm circuits, shall be flow tested through the inspector's test connection.

N 10.2.3.1.1 The flow test shall result in an audible alarm on the premises within 5 minutes of the start of the flow and until the flow stops.

N 10.2.3.1.2 Where a fire alarm system is monitoring water flow, an alarm signal shall activate in accordance with the requirements of the adopted fire alarm code.

N 10.2.3.2 Dry pipe systems and preaction systems shall be tested in accordance with NFPA 13.

N 10.2.4 Main Drain Valves.

N 10.2.4.1 The main drain valve required by Section 6.9 shall be opened and remain open until the system pressure stabilizes.

N 10.2.4.2* The static and residual pressures shall be recorded on the contractor's material and test certificate in accordance with 10.1.2.

Chapter 11 Care and Maintenance

11.1 Stock of Spare Sprinklers.

11.1.1* A supply of spare sprinklers shall be maintained on the premises so that any sprinklers that have operated or been damaged in any way can be promptly replaced. The quantity of spare sprinklers maintained shall be as specified in 11.1.5.

11.1.2 The sprinklers shall correspond to the types and temperature ratings of the sprinklers in the property.

11.1.3 The sprinklers shall be kept in a cabinet located where the temperature to which they are subjected will at no time exceed 100°F (38°C).

11.1.3.1 The sprinklers shall be kept in a cabinet located where the temperature to which they are subjected will at no time exceed the maximum ceiling temperatures specified in Table 5.1.1.6.1 for each of the sprinklers within the cabinet.

11.1.4 Where dry sprinklers of different lengths are installed, spare dry sprinklers shall not be required, provided that a means of returning the system to service is furnished.

11.1.5 The stock of spare sprinklers shall include all types and ratings installed and shall be as follows:

- (1) For systems serving a single-family dwelling — no fewer than two sprinklers
- (2) For protected facilities having under 300 sprinklers — no fewer than six sprinklers
- (3) For protected facilities having 300 to 1000 sprinklers — no fewer than 12 sprinklers
- (4) For protected facilities having over 1000 sprinklers — no fewer than 24 sprinklers

11.1.6* One sprinkler wrench as specified by the sprinkler manufacturer shall be provided in the cabinet for each type of sprinkler installed to be used for the removal and installation of sprinklers in the system.

11.1.7 A list of the sprinklers installed in the property shall be posted in the sprinkler cabinet.

11.1.7.1* The list shall include the following:

- (1) Sprinkler Identification Number (SIN) if equipped; or the manufacturer, model, orifice, deflector type, thermal sensitivity, and pressure rating
- (2) General description
- (3) Quantity of each type to be contained in the cabinet
- (4) Issue or revision date of the list

11.1.8* On a single property with multiple buildings under the same ownership, it shall be acceptable to provide the required spare sprinklers in a single location.

11.2* Owner's Responsibility. The owner shall be responsible for the condition of a sprinkler system and shall keep the system in normal operating condition.

11.3 Inspection, Testing, and Maintenance. Sprinkler systems shall be inspected, tested, and maintained in accordance with NFPA 25.

11.4 Instructions. The installing contractor shall provide the property owner or the property owner's authorized representative with the following:

- (1) All literature and instructions provided by the manufacturer describing proper operation and maintenance of any equipment and devices installed
- (2) A copy of NFPA 25

Annex A Explanatory Material

Annex A is not a part of the requirements of this NFPA document but is included for informational purposes only. This annex contains explanatory material, numbered to correspond with the applicable text paragraphs.

- ▲ **A.1.1** This standard is appropriate for use as an alternative to NFPA 13 only in those residential occupancies, as defined in this standard, up to and including four stories in height above grade plane. This standard references NFPA 13 in many aspects (e.g., hanging and bracing, design densities and spacing outside of dwelling unit, painting and finish of sprinklers, welding). If this standard does not specifically address a situation, NFPA 13 is a suitable resource that can be utilized by the installer and the authority having jurisdiction for a solution. It is not the intent of this standard to require compliance with NFPA 13 when this standard is silent on a subject.

Buildings that contain multiple occupancies (either separated or nonseparated), accessory occupancies, or incidental uses are often subject to special rules that might restrict the use of this standard. In buildings containing a residential occupancy properly separated from other occupancies, the use of this standard in the residential occupancy and NFPA 13 protection levels in the nonresidential occupancy(s) is appropriate. Model building codes also include a variety of incentives when a building is equipped with sprinklers, many of which are applicable to a system in accordance with this standard. Refer to the adopted building code to determine whether the use of this standard is applicable.

It should be noted that some model building codes contain special allowances for pedestal or podium-style buildings, which permit the story height (i.e., number of stories) for structures above the pedestal to be counted from the top surface of the pedestal rather than from grade plane, and it is the intent of this standard to follow this model building code method for determining the number of stories and building height measurement. (Note that model building codes do not allow building height to be measured from the top of a pedestal. That allowance only applies to determining the number of stories. Model building codes determine the height of a structure above grade plane on the average height of the highest roof surface above grade plane.) Accordingly, it is possible for a four-story residential structure to be within the scope of this standard even when that structure is constructed on top of a one-story pedestal. However, where this is allowed, model building codes will require the pedestal portion to be constructed using Type I construction, and the pedestal portion will be required to be protected by an NFPA 13-compliant sprinkler system.


Regardless of whether a building does or does not involve a pedestal, systems in accordance with this standard are always limited to structures that do not exceed 60 ft (18 m) in height above grade plane. For further information on building height story limits, see model building codes.

To be effective, sprinkler systems installed in accordance with this standard need to open the sprinklers closest to the fire before the fire exceeds the ability of the sprinkler discharge to extinguish or control the fire. Conditions that allow the fire to grow beyond that point before sprinkler activation or that interfere with the quality of water distribution can produce conditions beyond the capabilities of the sprinkler system described in this standard. Unusually high ceilings or ceiling configurations that tend to divert the rising hot gases from sprinkler locations or change the sprinkler discharge pattern from its standard pattern can produce fire conditions that cannot be extinguished or controlled by the systems described in this standard.

The criteria in this standard are based on full-scale fire tests of rooms containing typical furnishings found in residential living rooms, kitchens, and bedrooms. The furnishings were arranged as typically found in dwelling units in a manner similar to that shown in Figure A.1.1(a), Figure A.1.1(b), and Figure A.1.1(c). Sixty full-scale fire tests were conducted in a two-story dwelling in Los Angeles, California, and 16 tests were conducted in a 14 ft (4.3 m) wide mobile home in Charlotte, North Carolina. Sprinkler systems designed and installed according to this standard are expected to prevent flashover within the compartment of origin where sprinklers are installed in the compartment. A sprinkler system designed and installed

Table A.1.2(b) indicates the fire problem in the United States based on major property uses and illustrates the severity of loss of life, injuries, and property loss in residential occupancies.

A.3.2.2 Authority Having Jurisdiction (AHJ). The phrase “authority having jurisdiction,” or its acronym AHJ, is used in NFPA documents in a broad manner, since jurisdictions and approval agencies vary, as do their responsibilities. Where public safety is primary, the authority having jurisdiction may be a federal, state, local, or other regional department or individual such as a fire chief; fire marshal; chief of a fire prevention bureau, labor department, or health department; building official; electrical inspector; or others having statutory authority. For insurance purposes, an insurance inspection department, rating bureau, or other insurance company representative may be the authority having jurisdiction. In






FIGURE A.1.1(b) Manufactured Home Bedroom.

many circumstances, the property owner or his or her designated agent assumes the role of the authority having jurisdiction; at government installations, the commanding officer or departmental official may be the authority having jurisdiction.

A.3.2.4 Listed. The means for identifying listed equipment may vary for each organization concerned with product evaluation; some organizations do not recognize equipment as listed unless it is also labeled. The authority having jurisdiction should utilize the system employed by the listing organization to identify a listed product.

A.3.3.1 Bathroom. A room is still considered a bathroom if it contains just a toilet. Additionally, two bathrooms that are adjacent to each other are considered separate rooms.

A.3.3.8.1 Light-Hazard Occupancy. Light-hazard occupancies include occupancies having uses and conditions similar to the following: churches; clubs; educational; hospitals; institutional; libraries, except large stack rooms; museums; nursing or convalescent homes; offices, including data processing; residential; restaurant seating areas; and theaters and auditoriums, excluding stages and prosceniums.

A.3.3.8.2 Ordinary Hazard (Group 1). Ordinary-hazard occupancies (Group 1) include occupancies having uses and conditions similar to the following: automobile parking and showrooms, bakeries, laundries, and restaurant service areas.

A.3.3.8.3 Ordinary Hazard (Group 2). Ordinary-hazard occupancies (Group 2) include occupancies having uses and conditions similar to the following: dry cleaners, horse stables, libraries — large stack room areas, mercantile, post offices, repair garages, and stages.




FIGURE A.1.1(c) Living Room.

Table A.1.2(a) Reported Apartment or Multifamily Housing Structure Fires by Area of Origin; 2013–2017 Annual Averages

Area of Origin	Civilian Deaths	Civilian Percent	Fires	Percent	Injuries	Percent	Property Damage (Millions)	Percent
Bedroom	110	27	4,500	44	740	19	\$195	13
Living room, family room, or den	100	27	2,400	2	410	11	\$146	10
Other known area of origin	90	22	17,700	16	570	15	\$614	42
Kitchen or cooking area	80	20	74,900	68	1,920	49	\$318	22
Lavatory or bathroom	10	2	1,900	2	70	2	\$29	2
Exterior balcony or unenclosed porch	0	1	2,500	2	60	2	\$124	8
Trash or waste chute or container	0	0	2,200	2	10	0	\$2	0
Laundry room or area	0	0	2,100	2	60	1	\$22	1
Unclassified area of origin	0	1	1,800	2	30	1	\$15	1
Total	390	100	110,000	100	3,890	100	\$1,466	100

Source: NFIRS 5.0 and The NFPA fire experience survey (Published report: "Home Structure Fires: Supporting Tables," 2019, Table 10B).

Note: Sums might not equal totals due to rounding errors.

Table A.1.2(b) Reported Fires by Property Use: 2014–2018 Annual Averages

Majority Property Class	Fires	Civilian Deaths	Civilian Injuries	Property Loss
1—Assembly	15,984	14	176	\$333,380,930
2—Educational	4,763	1	50	\$64,628,767
3—Health care, detention, and correction	6,719	5	156	\$56,766,860
4—Residential	382,399	2,746	11,477	\$7,561,851,557
40—Unclassified or unknown-type residential	16,444	91	214	\$236,084,226
41—One- or two-family dwelling	242,973	2,217	7,164	\$5,652,781,171
42—Apartment or multi-family dwelling	110,170	404	3,865	\$1,534,155,746
43—Boarding house, residential hotel	2,935	13	65	\$16,715,711
44—Hotel or motel	3,932	16	108	\$97,712,933
45—Residential boarding and care	1,958	5	30	\$12,399,354
46—Dormitory, fraternity, sorority, or barracks	3,988	1	31	\$12,002,415
5—Mercantile or business	18,972	15	282	\$849,120,202
6—Industrial, utility, defense, agriculture, mining	2,925	2	36	\$230,102,755
7—Manufacturing, processing	5,270	3	167	\$509,513,456
8—Storage	22,401	32	299	\$637,147,702
9—Outside or special property	27,418	19	113	\$135,960,099
Unclassified or unknown property	6,946	7	56	\$80,039,075
Grand Total	493,797	2,844	12,812	\$10,458,511,401

Source: NFIRS 5.0 and the NFPA fire experience survey.

Note: Sums might not equal totals due to rounding errors.

A.3.3.9 Raw Water Source. Examples of raw water sources are millponds, lakes, streams, open top reservoirs, and so forth. Examples of non-raw water sources can include city water supplies, cisterns, pressure tanks, gravity tanks, break tanks, aquifers, and so forth. Water sources that are closed or protected from direct contact with the environment should not be considered raw.

A.3.3.10 Residential Occupancies. Buildings that contain multiple occupancies, either separated or nonseparated; accessory occupancies; or incidental uses are often subject to special rules that could restrict the use of NFPA 13R. Refer to the adopted building code to determine whether such restrictions are applicable. NFPA 13R is appropriate for use in a residential occupancy. In the list of building types included in this definition, there are situations where there will be mixed occupancies, and NFPA 13R might not be the appropriate sprinkler system standard for the nonresidential occupancies.

A.3.3.11 Shadow Area. Water is not required to fall on every square inch of floor space of the occupancy. This definition establishes a term that will be used to address the rules for acceptable dry spaces that occur when walls interfere with the sprinkler's spray pattern. Angled walls, wing walls, and slightly indented walls can disrupt water discharging from a sprinkler, which does not travel only in an absolute straight line, as if it were beams of light. Where small (typically triangular) shadowed areas are formed on the floor adjacent to the wall, these shadowed areas are purely on paper and do not take into account the dynamic variables of sprinkler discharge. In order to be acceptable, the shadow area needs to be within the coverage area of a sprinkler, meaning that water would discharge to the space directly if the structural or architectural feature was not there. The purpose of the shadow area is not to replace any existing obstruction requirements. Instead, the shadow area concept has been added to the standard to provide clarity to specific situations in which walls form non-rectangular-shaped rooms, as shown in Figure A.3.3.11.

A.5.1.1.1 Compatible thread sealant or Teflon tape can be used in a CPVC sprinkler adapter. However, a combination of the two cannot be used together. The manufacturer of the sprinkler adapter has listed installation instructions that must be followed for each sprinkler adapter used.

A.5.1.1.1.1 Sprinklers should be permitted to be reinstalled when the sprinkler being removed from the system remains attached to the original fitting or welded outlet, provided care has been taken to ensure the sprinkler has not been damaged. Flexible hose connections are considered a fitting.




FIGURE A.3.3.11 Shadow Area Created by Wall.

In new installations, where sprinklers are installed on pendent drop nipples or sidewall sprinklers prior to final cut-back, protective caps and/or straps should remain in place until after the drop nipple has been cut to fit to the final ceiling elevation.

A.5.1.1.2 It is recognized that the flow and pressure available to the replacement sprinkler might be less than its current flow and pressure requirement.

A.5.1.1.3 The four- to six-character sprinkler identification number, with no intervening spaces, is intended to identify the sprinkler operating characteristics in lieu of the traditional laboratory approval marking (e.g., SSU, SSP, EC, QR, etc.). The number, marked on the deflector of most sprinklers and elsewhere on decorative ceiling sprinklers, consists of one or two characters identifying the manufacturer, followed by three or four digits.

Sprinkler manufacturers have identified their manufacturer designations for the listing organizations. Each change in orifice size, response characteristics, or deflector (distribution) characteristics results in a new sprinkler identification number. The numbers do not identify specific characteristics of sprinklers but can be referenced in the database information compiled by the listing organizations. At the plan review stage, the sprinkler identification number should be checked against such a database or the manufacturer's literature to ensure that sprinklers are being used properly and within the limitations of their listings. Field inspections can include spot checks to ensure that the model numbers on the plans are those actually installed.

A.5.1.1.6 Information regarding the highest temperature that can be encountered in any location in a particular installation can be obtained by use of a thermometer that registers the highest temperature encountered. It should be hung for several days in the location in question.

A.5.1.1.7.2 The use of the wrong type of escutcheon with recessed or flush-type sprinklers can result in severe disruption of the spray pattern, which can destroy the effectiveness of the sprinkler.

A.5.1.1.9.1 Protective caps and straps are intended to provide temporary protection for sprinklers during shipping and installation.

A.5.1.1.9.2 Protective caps and straps can be removed from upright sprinklers, from sprinklers that are fitted with sprinkler guards, and from sprinklers that are not likely to be subject to damage due to construction activities or other events. In general, protective caps and straps should not be removed until construction activities or other events have progressed to the point where the sprinklers will not be subjected to conditions that could cause them to be damaged. Consideration should be given to leaving the protective caps and straps in place where other construction work is expected to take place, adjacent to the sprinklers following their installation, until that activity is complete. Protective caps and straps on sidewall and pendent sprinklers, for example, should be left in place pending installation of the wall and ceiling systems and then removed as finish escutcheons are being installed.

In retrofit applications, with minimal follow-on trade construction activity, and with upright sprinklers, it would be reasonable to remove the caps and straps immediately following the installation on the sprinkler piping.

A.5.2.3 CPVC is a plastic material, and consideration is necessary when other materials or chemicals come in contact with CPVC that can cause degradation of performance of the pipe due to interaction of materials. Other construction materials include, but are not limited to, materials used in the fabrication of the sprinkler system, additives to water supplies, cable and wiring, and certain insecticides and fungicides. Compliance with 5.2.3 combined with following the manufacturer's guidance on installation and compatible materials will help prevent premature performance degradation of nonmetallic piping. Mechanical stress caused by hanging methods or bending on nonmetallic piping beyond the manufacturer's recommended limitations can cause stress failure over time and should be avoided.

A.5.2.3.4 When fabricating steel pipe for a combination (CPVC–steel) system, the cutting oil and lubricants can cause performance degradation of the CPVC piping. Cutting oils and lubricants found to be compatible are available and should be used.

Δ A.5.2.12.2 Not all fittings made to ASTM F437, *Standard Specification for Threaded Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80*; ASTM F438, *Standard Specification for Socket-Type Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40*; and ASTM F439, *Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80*, as described in 5.2.12.2 are listed for fire sprinkler service. Listed fittings are identified by the logo of the listing agency.

CPVC is a plastic material and consideration is necessary when other materials or chemicals come in contact with CPVC that can cause degradation of performance of the fitting due to interaction of materials. Compliance with 5.2.1.4 combined with following manufacturer's guidance on installation and compatible materials will help prevent premature performance degradation of nonmetallic fittings. Mechanical stress caused by hanging methods or bending on nonmetallic piping beyond the manufacturer's recommended limitations can cause stress failure over time and should be avoided.

A.5.2.12.2.1.3 When fabricating steel pipe for a system using non-metallic and steel pipe, the cutting oil and lubricants can cause performance degradation of the non-metallic fitting.

A.5.2.12.2.1.5 Rubber-gasketed pipe fittings and couplings should not be installed where ambient temperatures can be expected to exceed 150°F (66°C) unless listed for this service. If the manufacturer further limits a given gasket compound, those recommendations should be followed. Other construction materials include, but are not limited to, materials used in fabrication of the sprinkler system, additives to water supplies, cable and wiring, and certain insecticides and fungicides.

A.5.2.14.4 The intent of 5.2.14.4 is to provide assistance in determining the area of a building served by a particular control valve.

A.5.2.14.4.4 Care should be taken to ensure that all water supplies are isolated before work begins. Work on systems by shutting one valve and not knowing about another valve can result in unexpected water damage.

A.5.2.14.5.1 Backflow preventers that are "UL Classified" meet the definition of *listed* in accordance with this standard.

A.5.4.2 Piping covered by insulation, as shown in Figure A.5.4.2(a) through Figure A.5.4.2(f), is considered part of the area below the ceiling and not part of the unheated attic area.

A.5.4.2(1) The use of antifreeze solutions in all new sprinkler systems should be restricted to listed antifreeze solutions only.

A.5.4.4 There are some geographic regions where the temperature will get below 40°F (4°C) for brief periods of time. However, the water in the pipe has sufficient thermal mass to keep it from freezing and thus additional freeze protection is not required.

A.6.2.3.1 Sprinklers with a temperature rating of 135°F to 170°F (57°C to 77°C) are classified as ordinary temperature-rated sprinklers.

A.6.2.3.2 Sprinklers with a temperature rating of 175°F to 225°F (79°C to 107°C) are classified as intermediate temperature-rated sprinklers.




FIGURE A.5.4.2(a) Insulation Recommendations — Arrangement 1.




FIGURE A.5.4.2(b) Insulation Recommendations — Arrangement 2.




FIGURE A.5.4.2(c) Insulation Recommendations — Arrangement 3.




FIGURE A.5.4.2(d) Insulation Recommendations — Arrangement 4.

A.6.2.3.3 Care should be taken in positioning sprinklers in bathrooms near exhaust fan units. Some exhaust fan units have heaters built in to warm up the bathroom, and these units have the potential to activate sprinklers. Combination exhaust fan and heater units should be treated as wall-mounted diffusers for the purposes of using 6.2.3.3.3.1. Another area that should be avoided is directly in front of a vanity sink in a bathroom or dressing area with a low ceiling or over a kitchen sink. The use of hair dryers in vanity and bathroom areas can accidentally direct hot temperatures towards the sprinklers when installed above. In kitchens, sometimes steaming hot water is dumped into the sink, which could affect a sprinkler installed directly overhead.

A.6.2.3.3.3 See Figure A.6.2.3.3.3(a), Figure A.6.2.3.3.3(b), Figure A.6.2.3.3.3(c), and Figure A.6.2.3.3.3(d).

▲ A.6.2.4.1 Dry sprinklers must be of sufficient length to avoid freezing of the water-filled pipes due to conduction along the




FIGURE A.5.4.2(e) Insulation Recommendations — Arrangement 5.




FIGURE A.5.4.2(f) Insulation Recommendations — Arrangement 6.

barrel. The values of exposed barrel length in Table 6.2.4.1 have been developed using an assumption of a properly sealed penetration and an assumed maximum wind velocity on the exposed sprinkler of 30 mph (48 km/h). Where higher wind velocity is expected, longer exposed barrel lengths will help avoid freezing of the wet piping. The total length of the barrel of the dry sprinkler must be longer than the values shown in Table 6.2.4.1 because the length shown in the tables is the minimum length of the barrel that needs to be exposed to the warmer ambient temperature in the heated space. See Figure A.6.2.4.1(a) for examples of where to measure the exposed barrel length for a sidewall sprinkler penetrating an exterior wall and Figure A.6.2.4.1(b) for an example of where to measure the exposed barrel length for a pendent sprinkler penetrating a ceiling or top of an insulated structure.




FIGURE A.6.2.3.3.3(a) Recessed Fireplace — Ordinary Temperature Sprinkler Location.




FIGURE A.6.2.3.3.3(c) Open Fireplace — Ordinary Temperature Sprinkler Location.




FIGURE A.6.2.3.3.3(b) Recessed Fireplace — Intermediate Temperature Sprinkler Location.




FIGURE A.6.2.3.3.3(d) Open Fireplace — Intermediate Temperature Sprinkler Location.


A.6.4.4 Construction features such as large horizontal beamed ceilings, sloped ceilings having beams, and steeply sloped ceilings exist that are outside of the current listings. In these situations, sprinklers can be installed in a manner acceptable to the authority having jurisdiction to achieve the results specified in this standard. In making these determinations, consideration should be given to factors influencing sprinkler system performance such as sprinkler response characteristics, impact of obstructions on sprinkler discharge, and number of sprinklers anticipated to operate in the event of a fire.

A.6.4.6.1.1.1 Concealed sprinklers should not be considered flush-type sprinklers.


A.6.4.6.3 Where the obstruction criteria established by this standard are followed, sprinkler spray patterns will not necessa-

rily get water to every square foot of space within a room. As such, a sprinkler in a room with acceptable obstructions as outlined in this standard is not necessarily capable of passing the fire test (specified by UL 1626, *Residential Sprinklers for Fire Protection Service*, and other similar laboratory standards) if the fire is started in one of these dry areas. This result is not to be interpreted as a failure of the sprinklers. The laboratory fire tests are sufficiently challenging to the sprinkler without additional obstructions as a safety factor to account for the variables that actually occur in dwellings, including acceptable obstructions to spray patterns.

The objective is to position sprinklers so that the response time and discharge are not unduly affected by obstructions such as ceiling slope, beams, light fixtures, or ceiling fans. The



EXAMPLE 1



EXAMPLE 2

X = Minimum exposed barrel length
 X is measured from the face of the sprinkler fitting
 to the inside surface of the exterior wall or insulation —
 whichever is closer to the fitting.


▲ FIGURE A.6.2.4.1(a) Dry Sidewall Sprinkler Through Wall.

rules in this section, while different from the obstruction rules of NFPA 13, provide a reasonable level of life safety while maintaining the philosophy of keeping NFPA 13R relatively simple to apply and enforce.

Fire testing has indicated the need to wet walls in the area protected by residential sprinklers at a level closer to the ceiling than that accomplished by standard sprinkler distribution. Where beams, light fixtures, sloped ceilings, and other obstructions occur, additional residential sprinklers could be necessary to achieve proper response and distribution, and a greater water supply could be necessary.

The requirements of 6.4.6.3.4 and 6.4.6.3.5 were developed from a testing series conducted by the National Fire Sprinkler Association and The Viking Corporation that included fire modeling, sprinkler response tests, sprinkler distribution tests, and full-scale fire tests (Valentine and Isman, *Interaction of Residential Sprinklers, Ceiling Fans and Similar Obstructions*, National Fire Sprinkler Association, November 2005). This test series, along with additional industry experience, shows a difference between obstructions that are tight to the ceiling and obstructions that hang down from the ceiling, allowing spray over the top. Residential sprinklers require high wall wetting, which means that they tend to spray over obstructions that hang down from the ceiling. The test series showed that the fan blades were not significant obstructions and that as long as the sprinkler was far enough from the fan motor housing (measured from the center of the housing), the sprinkler could control a fire on the other side of the fan in a small room. In larger rooms, the sprinkler needs to be augmented by additional sprinklers on the other side of the fan. The test series showed that the fan on low or medium speed did not make a significant difference in sprinkler performance. On high speed (pushing air down) the fan did impact sprinkler performance, but fire control was still achieved in small rooms. In larger rooms, it is expected that additional sprinklers would be installed. The test series also showed that the fan blowing down was more significant than the fan pulling air up.

The rules in 6.4.6.3.8 were developed from years of experience with NFPA 13 obstruction rules and an additional test series conducted by the National Fire Sprinkler Association with the help of Tyco International (Valentine and Isman, *Kitchen Cabinets and Residential Sprinklers*, National Fire Sprinkler Association, November 2005), which included fire model-



X = Minimum exposed barrel length

X is measured from the face of the sprinkler fitting
 to the inside surface of the exterior wall or insulation —
 whichever is closer to the fitting.

▲ FIGURE A.6.2.4.1(b) Dry Pendent Sprinkler Through Ceiling or Top of Insulated Structure.

ing, distribution tests, and full-scale fire tests. The test series showed that pendent sprinklers definitely provide protection for kitchens, even for fires that start under the cabinets. The information in the series was less than definitive for sidewall sprinklers, but distribution data show that sprinklers in the positions in this standard provide adequate water distribution in front of the cabinets and that sidewall sprinklers should be able to control a fire that starts under the cabinets. When protecting kitchens or similar rooms with cabinets, the pendent sprinkler should be the first option. If pendent sprinklers cannot be installed, the next best option is a sidewall sprinkler on the opposite wall from the cabinets, spraying in the direction of the cabinets. The third best option is the sidewall sprinkler on the same wall as the cabinets on a soffit flush with the face of the cabinet. The last option should be putting sprinklers on the wall back behind the face of the cabinet because this location is subject to being blocked by items placed on top