

NFPA 30

Flammable and Combustible Liquids Code

2000 Edition



NFPA, 1 Batterymarch Park, PO Box 9101, Quincy, MA 02269-9101
An International Codes and Standards Organization

NFPA License Agreement

This document is copyrighted by the National Fire Protection Association (NFPA), 1 Batterymarch Park, Quincy, MA 02269-9101 USA.
All rights reserved.

NFPA grants you a license as follows: The right to download an electronic file of this NFPA document for temporary storage on one computer for purposes of viewing and/or printing one copy of the NFPA document for individual use. Neither the electronic file nor the hard copy print may be reproduced in any way. In addition, the electronic file may not be distributed elsewhere over computer networks or otherwise. The hard copy print may only be used personally or distributed to other employees for their internal use within your organization.

IMPORTANT NOTICE ABOUT THIS DOCUMENT

NFPA codes, standards, recommended practices, and guides, of which the document contained herein is one, are developed through a consensus standards development process approved by the American National Standards Institute. This process brings together volunteers representing varied viewpoints and interests to achieve consensus on fire and other safety issues. While the NFPA administers the process and establishes rules to promote fairness in the development of consensus, it does not independently test, evaluate, or verify the accuracy of any information or the soundness of any judgments contained in its codes and standards.

The NFPA disclaims liability for any personal injury, property or other damages of any nature whatsoever, whether special, indirect, consequential or compensatory, directly or indirectly resulting from the publication, use of, or reliance on this document. The NFPA also makes no guaranty or warranty as to the accuracy or completeness of any information published herein.

In issuing and making this document available, the NFPA is not undertaking to render professional or other services for or on behalf of any person or entity. Nor is the NFPA undertaking to perform any duty owed by any person or entity to someone else. Anyone using this document should rely on his or her own independent judgment or, as appropriate, seek the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

The NFPA has no power, nor does it undertake, to police or enforce compliance with the contents of this document. Nor does the NFPA list, certify, test or inspect products, designs, or installations for compliance with this document. Any certification or other statement of compliance with the requirements of this document shall not be attributable to the NFPA and is solely the responsibility of the certifier or maker of the statement.

See inside back cover for additional important notices and information.

NOTICES

All questions or other communications relating to this document and all requests for information on NFPA procedures governing its codes and standards development process, including information on the procedures for requesting Formal Interpretations, for proposing Tentative Interim Amendments, and for proposing revisions to NFPA documents during regular revision cycles, should be sent to NFPA headquarters, addressed to the attention of the Secretary, Standards Council, National Fire Protection Association, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02269-9101.

Users of this document should be aware that this document may be amended from time to time through the issuance of Tentative Interim Amendments, and that an official NFPA document at any point in time consists of the current edition of the document together with any Tentative Interim Amendments then in effect. In order to determine whether this document is the current edition and whether it has been amended through the issuance of Tentative Interim Amendments, consult appropriate NFPA publications such as the *National Fire Codes*® Subscription Service, visit the NFPA website at www.nfpa.org, or contact the NFPA at the address listed above.

A statement, written or oral, that is not processed in accordance with Section 6 of the Regulations Governing Committee Projects shall not be considered the official position of NFPA or any of its Committees and shall not be considered to be, nor be relied upon as, a Formal Interpretation.

The NFPA does not take any position with respect to the validity of any patent rights asserted in connection with any items which are mentioned in or are the subject of this document, and the NFPA disclaims liability for the infringement of any patent resulting from the use of or reliance on this document. Users of this document are expressly advised that determination of the validity of any such patent rights, and the risk of infringement of such rights, is entirely their own responsibility.

Users of this document should consult applicable federal, state, and local laws and regulations. NFPA does not, by the publication of this document, intend to urge action that is not in compliance with applicable laws, and this document may not be construed as doing so.

Licensing Policy

This document is copyrighted by the National Fire Protection Association (NFPA). By making this document available for use and adoption by public authorities and others, the NFPA does not waive any rights in copyright to this document.

1. Adoption by Reference—Public authorities and others are urged to reference this document in laws, ordinances, regulations, administrative orders, or similar instruments. Any deletions, additions, and changes desired by the adopting authority must be noted separately. Those using this method are requested to notify the NFPA (Attention: Secretary, Standards Council) in writing of such use. The term "adoption by reference" means the citing of title and publishing information only.

2. Adoption by Transcription—**A.** Public authorities with lawmaking or rule-making powers only, upon written notice to the NFPA (Attention: Secretary, Standards Council), will be granted a royalty-free license to print and republish this document in whole or in part, with changes and additions, if any, noted separately, in laws, ordinances, regulations, administrative orders, or similar instruments having the force of law, provided that: (1) due notice of NFPA's copyright is contained in each law and in each copy thereof; and (2) that such printing and republication is limited to numbers sufficient to satisfy the jurisdiction's lawmaking or rule-making process. **B.** Once this NFPA Code or Standard has been adopted into law, all printings of this document by public authorities with lawmaking or rule-making powers or any other persons desiring to reproduce this document or its contents as adopted by the jurisdiction in whole or in part, in any form, upon written request to NFPA (Attention: Secretary, Standards Council), will be granted a nonexclusive license to print, republish, and vend this document in whole or in part, with changes and additions, if any, noted separately, provided that due notice of NFPA's copyright is contained in each copy. Such license shall be granted only upon agreement to pay NFPA a royalty. This royalty is required to provide funds for the research and development necessary to continue the work of NFPA and its volunteers in continually updating and revising NFPA standards. Under certain circumstances, public authorities with lawmaking or rule-making powers may apply for and may receive a special royalty where the public interest will be served thereby.

3. Scope of License Grant—The terms and conditions set forth above do not extend to the index of this document.

(For further explanation, see the Policy Concerning the Adoption, Printing, and Publication of NFPA Documents, which is available upon request from the NFPA.)

Copyright © 2000 NFPA, All Rights Reserved

NFPA 30

Flammable and Combustible Liquids Code

2000 Edition

This edition of NFPA 30, *Flammable and Combustible Liquids Code*, was prepared by the Technical Committees involved with the Flammable and Combustible Liquids project, released by the Technical Correlating Committee on Flammable and Combustible Liquids, and acted on by the National Fire Protection Association, Inc., at its World Fire Safety Congress and Exposition™ held May 14–17, 2000, in Denver, CO. It was issued by the Standards Council on July 20, 2000, with an effective date of August 18, 2000, and supersedes all previous editions.

This edition of NFPA 30 was approved as an American National Standard on August 18, 2000.

Origin and Development of NFPA 30

From 1913 to 1957, this document was written as a model municipal ordinance known as the *Suggested Ordinance for the Storage, Handling, and Use of Flammable Liquids*. In 1957, the format was changed to a code, although the technical requirements and provisions remained the same. During the 87-year period of existence of NFPA 30, numerous revised editions have been published as dictated by experience and advances in technology.

A brief review of the major changes adopted over the previous five editions follows. In 1984, the chapter covering automotive and marine service stations was removed from NFPA 30 and was used as the basis for a separate document, NFPA 30A, *Automotive and Marine Service Station Code*. In 1987, Chapter 5 (Industrial Plants), Chapter 6 (Bulk Plants and Terminals), Chapter 7 (Process Plants), and Chapter 8 (Refineries, Chemical Plants, and Distilleries) were combined into a single chapter on operations. In 1990, a new section was added to Chapter 4 to address hazardous materials storage lockers, and more detailed guidance was added to Section 5-3 to address ventilation of enclosed process areas and for estimation of fugitive emissions. In 1993, Chapter 4, Container and Portable Tank Storage, was completely rewritten so that its requirements were presented more clearly, especially for mercantile occupancies. In addition, changes were made to the tank diking provisions to allow combined remote impounding and diking systems and to provide relief from the spill control requirements for certain secondary containment-type tanks.

In 1996, the following changes were made:

- (1) A new section on classification of liquids was added to Chapter 1, replacing NFPA 321, *Standard on Basic Classification of Flammable and Combustible Liquids*.
- (2) A new section, 2-4.4, was added to establish requirements for temporary and permanent closure of underground storage tanks.
- (3) Requirements for tightness testing of tanks were revised to apply to specific tank designs.
- (4) Intermediate bulk containers other than metal portable tanks were recognized in Chapter 4.
- (5) Mandatory fire protection design criteria for inside storage of liquids were incorporated into Chapter 4.
- (6) Chapter 5, Operations, was editorially revised for clarity and for easier use in conjunction with federal process safety management and process safety analysis rules.

This 2000 edition of NFPA 30 incorporates the following major changes:

- (1) Numerous new definitions have been added to Chapter 1, as necessary to deal with new material added to other parts of the code, including definitions for aboveground tank, heat transfer fluid, important building, protected aboveground tank, solvent distillation unit, vapor processing system, vapor recovery system, and vault.
- (2) Chapter 2, Tank Storage, and Chapter 3, Piping Systems, have both been completely editorially rewritten and reorganized to present the material in a more logical order. In addition, ambiguous text has been replaced.
- (3) A new 2.2.7 has been added to address the design, construction, and installation of vaults for aboveground tanks.
- (4) A new 2.2.9 has been added to address the design, construction, and installation of protected aboveground tanks.

- (5) The emergency vent reduction factors are now allowed for any tank containing a stable liquid, not just atmospheric storage tanks.
- (6) Under certain specified conditions, pipe joints that incorporate friction clamping components can now be used inside buildings. This recognizes certain types of clamp- and compression-type pipe joining methods that allow for quick disassembly for routine cleaning and maintenance, such as those commonly used in the food, pharmaceutical, and semiconductor industries.
- (7) Certain rigid nonmetallic intermediate bulk containers are now recognized in Chapter 4.
- (8) The requirements for spill containment and drainage have been simplified, and new design criteria for warehouse drainage systems have been added to the Appendix A material to Section 4.8.
- (9) Explanatory information has been added to explain what Section 4.8 recognizes as a relieving-style container.
- (10) Guidance has been added to Section 4.8 to aid the user in determining what commodities are considered to be viscous liquids.
- (11) A new fire protection design decision tree has been added for water-miscible liquids in plastic containers.
- (12) New fire protection design criteria have been added to Section 4.8 to address the following:
 - a. Expanded foam-water sprinkler protection for palletized storage of metal containers
 - b. New criteria for sprinkler protection of rack storage of Class IIIB liquids in plastic containers
 - c. New criteria for sprinkler protection of rack storage of water-miscible liquids in plastic containers
 - d. Additional criteria for sprinkler protection of rack and palletized storage of liquids on open wire-mesh shelving
 - e. New criteria for sprinkler protection of nonmetallic intermediate bulk containers in both palletized and rack configurations
- (13) Subsection 5.3.3.1 on construction and separation of process buildings has been greatly expanded, and specific separation criteria based on building construction types are given.
- (14) Guidance for staging of liquids in operating areas has been added.
- (15) A new Section 5.4 has been added to address recirculating heat transfer fluid heating systems.
- (16) Section 5.6, Loading and Unloading Operations, has been reorganized to better present the material.
- (17) A new Section 5.11 has been added to address solvent recovery distillation units.
- (18) All of the requirements for hazardous location electrical area classification have been consolidated and placed in a new Chapter 6.

Prior editions of this document have been translated into languages other than English, including Spanish and French.

Technical Correlating Committee on Flammable and Combustible Liquids (FLC-AAC)

Edward Hildebrandt, *Chair*
Village of Morton Grove, IL [E]

John A. Davenport, West Hartford, CT [I]
Rep. HSB Industrial Risk Insurers
Gary R. Glowinski, Glowinski & Assoc., Inc., WI [SE]
James D. Kieffer, Kieffer & Assoc., Inc., ON, Canada [SE]
Richard S. Kraus, Petroleum Safety Consultants, VA [M]
Rep. American Petroleum Inst.
William E. Rehr, BOCA International, Inc., IL [E]

Douglas A. Rivers, 3M Co., MN [U]
Gerald J. Rosicky, General Motors Corp., MI [U]
Rep. NFPA Industrial Fire Protection Section
Orville M. Slye, Jr., Loss Control Assoc. Inc., PA [SE]
Hugh Patrick Toner, Society of the Plastics Industry, Inc., DC [M]

Alternates

Richard D. Gottwald, Society of the Plastics Industry, Inc., DC [M]
(Alt. to H. P. Toner)

Kenneth H. Turnbull, Texaco, TX [M]
(Alt. to R. S. Kraus)

Nonvoting

David L. Blomquist, Blomquist Fire Protection Engr., CA
(Member Emeritus)
John J. Hawley, Underwriters Laboratories Inc., IL,
Chair FLC-FUN
Donald M. Johnson, Walnut Creek, CA
(Member Emeritus)

Anthony M. Ordile, Loss Control Assoc., Inc., PA,
Chair FLC-SWC
Brooke B. Smith, Jr., Aspen Engineering Inc., CO,
Chair FLC-TAN
Jack Woycheese, Gage-Babcock & Assoc., Inc., CA,
Chair FLC-OPS

Robert P. Benedetti, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on safeguarding against the fire and explosion hazards associated with the storage, handling, and use of flammable and combustible liquids; and classifying flammable and combustible liquids.

Technical Committee on Fundamentals (FLC-FUN)
(Chapter 1)

John J. Hawley, *Chair*
Underwriters Laboratories Inc., IL [RT]

Robert P. Benedetti, *Nonvoting Secretary*
Nat'l Fire Protection Assn., MA

Gary R. Glowinski, Glowinski & Assoc., Inc., WI [SE]
Gerald A. Gordon, Greif Bros. Corp., IL [M]
Dwight H. Havens, City of Phoenix Fire Dept., AZ [E]
Jay J. Jablonski, HSB Professional Loss Control, TX [I]

James D. Kieffer, Kieffer & Assoc., Inc., ON, Canada [SE]
Richard S. Kraus, Petroleum Safety Consultants, VA [M]
Rep. American Petroleum Inst.
Jack Woycheese, Gage-Babcock & Assoc., Inc., CA [SE]

Alternate

Cherilyn A. Zeisset, Pennzoil Co., TX [M]
(Alt. to R. S. Kraus)

Robert P. Benedetti, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents or portions of documents on the basic requirements for safeguarding against the fire and explosion hazards associated with the storage and handling of flammable and combustible liquids. This Committee shall also have responsibility for definitions related to flammable and combustible liquids and for criteria for the classification of flammable and combustible liquids.

Technical Committee on Operations (FLC-OPS)

(Chapters 5 and 6)

Jack Woycheese, Chair

Gage-Babcock & Assoc., Inc., CA [SE]

James C. Brundage, III, Atlanta Fire Dept., GA [E]**Brian J. Clark**, Liberty Mutual Insurance Group, CT [I]

Rep. The Alliance of American Insurers

Gary R. Glowinski, Glowinski & Assoc., Inc., WI [SE]**John P. Hartmann**, Hartmann Mgmt. Services Inc., IL [SE]**Dwight H. Havens**, City of Phoenix Fire Dept., AZ [E]**Richard J. Hild**, DuPont Performance Coatings, DE [M]**Edward Hildebrandt**, Village of Morton Grove, IL [E]**Jay J. Jablonski**, HSB Professional Loss Control, TX [I]**Joshy Paul Kallungal**, Office of the Fire Marshal, ON, Canada [E]**James D. Kieffer**, Kieffer & Assoc., Inc., ON, Canada [SE]**David C. Kirby**, Union Carbide Corp., WV [U]

Rep. Chemical Manufacturers Assn.

Donald J. Kohn, Kohn Engineering, PA [SE]**John A. LeBlanc**, Factory Mutual Research Corp., MA [I]**Robert E. McClay**, East Carolina University, NC [SE]

Rep. American Society of Safety Engineers

Christopher M. Moore, Kemper Insurance Cos., MA [I]**Francisco N. Nazario**, Exxon Research & Engr Co., NJ [M]**Thaddeus A. Nosal**, American Insurance Services Group, NY [I]**Anthony M. Ordile**, Loss Control Assoc., Inc., PA [SE]**Susan M. Preske**, Reliance Insurance Co., NY [I]**Robert N. Renkes**, Petroleum Equipment Inst., OK [M]**Gerald J. Rosicky**, General Motors Corp., MI [U]

Rep. NFPA Industrial Fire Protection Section

George A. Seuss, Jr., Verlan Fire Insurance Co., MD [I]**Brooke B. Smith, Jr.**, Aspen Engineering Inc., CO [SE]**C. Charles Snow, Jr.**, 3M Co., MN [U]**William A. Thornberg**, HSB Industrial Risk Insurers, CT [I]**Kenneth H. Turnbull**, Texaco, TX [M]

Rep. American Petroleum Inst.

Scott M. Tyler, Duke Engineering and Services, IL [U]

Rep. Edison Electric Inst.

Alternates**Frederick C. Bradley**, Gage-Babcock & Assoc., Inc., GA [SE]

(Alt. to J. Woycheese)

John A. Davenport, West Hartford, CT [I]

(Alt. to W. A. Thornberg)

Gregory D. Kirby, CYTEC Industries, Inc., WV [U]

(Alt. to D. C. Kirby)

Richard S. Kraus, Petroleum Safety Consultants, VA [M]

(Alt. to K. H. Turnbull)

Douglas A. Rivers, 3M Co., MN [U]

(Alt. to C. C. Snow)

Orville M. Slye, Jr., Loss Control Assoc., Inc., PA [SE]

(Alt. to A. M. Ordile)

Kevin F. Sykora, The Sherwin-Williams Co., OH [SE]

(Alt. to R. E. McClay)

Richard E. Thonnings, AISG Engr & Safety Service, NY [I]

(Alt. to T. A. Nosal)

Laurence D. Watrous, HSB Professional Loss Control, TN [I]

(Alt. to J. J. Jablonski)

Nonvoting**Michael B. Moore**, U.S. Occupational Safety & Health Admin., DC**Terence P. Smith**, U.S. Occupational Safety & Health Admin., DC

(Alt. to M. B. Moore)

Robert P. Benedetti, NFPA Staff Liaison*This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.***NOTE:** Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.**Committee Scope:** This Committee shall have primary responsibility for documents or portions of documents on safeguarding against the fire and explosion hazards associated with operations that involve the handling, transfer, and use of flammable and combustible liquids, either as a principal activity or as an incidental activity.

Technical Committee on Storage and Warehousing of Containers and Portable Tanks (FLC-SWC) (Chapter 4)

Anthony M. Ordile, Chair
Loss Control Assoc., Inc., PA [SE]

Frederick C. Bradley, Gage-Babcock & Assoc., Inc., GA [SE]
William M. Carey, Underwriters Laboratories Inc., IL [RT]
John A. Davenport, West Hartford, CT [I]
 Rep. HSB Industrial Risk Insurers
John J. Foley, The RJA Group, Inc., GA [SE]
Gary R. Glowinski, Glowinski & Assoc., Inc., WI [SE]
Gerald A. Gordon, Greif Bros. Corp., IL [M]
Dwight H. Havens, City of Phoenix Fire Dept., AZ [E]
Richard J. Hild, DuPont Performance Coatings, DE [M]
 Rep. Nat'l Paint & Coatings Assn.
Edward Hildebrandt, Village of Morton Grove, IL [E]
Joshy Paul Kallungal, Office of the Fire Marshal, ON, Canada [E]
David C. Kirby, Union Carbide Corp., WV [U]
 Rep. Chemical Manufacturers Assn.
Dale H. Kolisch, Kemper Insurance, IL [I]
Richard S. Kraus, Petroleum Safety Consultants, VA [M]
 Rep. American Petroleum Inst.
John A. LeBlanc, Factory Mutual Research Corp., MA [I]
Jerry Massa, CP Louisiana, Inc., LA [M]
 Rep. Steel Shipping Container Inst.
Navin D. Mehta, U.S. DOD, Defense Logistic Agency, VA [U]

Charles L. Milles, Jr., AgrEvo USA Co., PA [M]
 Rep. American Crop Protection Assn.
Lee Rindfuss, Marsh Risk Consulting, MA [I]
Douglas A. Rivers, 3M Co., MN [U]
Gerald J. Rosicky, General Motors Corp., MI [U]
 Rep. NFPA Industrial Fire Protection Section
Joseph L. Scheffey, Hughes Assoc. Inc., MD [SE]
Mike Spence, Brown Sprinkler Corp., KY [IM]
 Rep. Nat'l Fire Sprinkler Assn.
Arthur M. Stevens, Stevens Assoc., FL [M]
 Rep. Justrite Manufacturing Co., LLC
David C. Tabar, The Sherwin-Williams Co., OH [M]
Richard E. Thonnings, AISG Engr & Safety Service, NY [I]
 Rep. American Insurance Services Group
William J. Tomes, TVA Fire and Life Safety, GA [U]
 Rep. The Home Depot
Hugh Patrick Toner, Society of the Plastics Industry, Inc., DC [M]
William W. Woodfill, Wausau Insurance Co., IL [I]
 Rep. The Alliance of American Insurers
Martin H. Workman, Viking Corp., MI [M]
 Rep. American Fire Sprinkler Assn., Inc.

Alternates

Robert H. Christopher, R-C Associates, DE [M]
 (Alt. to R. J. Hild)
Brian J. Clark, Liberty Mutual Insurance Group, CT [I]
 (Alt. to W. W. Woodfill)
Charles L. Gandy, TVA Fire and Life Safety, NJ [U]
 (Alt. to W. J. Tomes)
Richard D. Gottwald, Society of the Plastics Industry, DC [M]
 (Alt. to H. P. Toner)
Gregory D. Kirby, CYTEC Industries, Inc., WV [U]
 (Alt. to D. C. Kirby)
Craig A. Martens, Lake Havasu City Fire Dept., AZ [E]
 (Alt. to D. H. Havens)
Jaime A. Moncada, The RJA Group, Inc., VA [SE]
 (Alt. to J. J. Foley)
Thaddeus A. Nosal, American Insurance Services Group, NY [I]
 (Alt. to R. E. Thonnings)
Martin J. Pabich, Underwriters Laboratories Inc., IL [RT]
 (Alt. to W. M. Carey)

Orville M. Slye, Jr., Loss Control Assoc., Inc., PA [SE]
 (Alt. to A. M. Ordile)
C. Charles Snow, Jr., 3M Co., MN [U]
 (Alt. to D. A. Rivers)
Ronald J. Stephens, Allan Automatic Sprinkler Corp. of Southern California, CA [IM]
 (Alt. to M. Spence)
David C. Swenson, The Sherwin-Williams Co., OH [M]
 (Alt. to D. C. Tabar)
William A. Thornberg, HSB Industrial Risk Insurers, CT [I]
 (Alt. to J. A. Davenport)
Daniel J. Venier, Marsh USA, Inc., MI [I]
 (Alt. to L. Rindfuss)
Jack Woycheese, Gage-Babcock & Assoc., Inc., CA [SE]
 (Alt. to F. C. Bradley)
Cherilyn A. Zeisset, Pennzoil Co., TX [M]
 (Alt. to R. S. Kraus)

Robert P. Benedetti, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents or portions of documents on safeguarding against the fire and explosion hazards associated with the storage, warehousing, and display merchandising of flammable and combustible liquids in containers and in portable tanks whose capacity does not exceed 2500 liters (660 gallons).

Technical Committee on Tank Storage and Piping Systems (FLC-TAN)

(Chapters 2 and 3)

Brooke B. Smith, Jr., Chair
Aspen Engineering Inc., CO [SE]

Gary T. Austerman, Burns & McDonnell Engr Co., MO [SE]
Frederick C. Bradley, Gage-Babcock & Assoc., Inc., GA [SE]
Jon V. Brannan, Underwriters Laboratories Inc., IL [RT]
James C. Brundage, III, Atlanta Fire Dept. GA [E]
Murray A. Cappers, Jr., Marsh USA, Inc., NJ [I]
Sullivan D. Curran, Fiberglass Tank & Pipe Inst., TX [M]
Charles A. Davis, URS Greiner, Inc., FL [SE]
Wayne Geyer, Steel Tank Inst., IL [M]
Robert D. Grausam, PARTNER RE US, NY [I]
John P. Hartmann, Hartmann Mgmt. Services Inc., IL [SE]
Dwight H. Havens, City of Phoenix Fire Dept., AZ [E]
Gregory D. Kirby, CYTEC Industries, Inc., WV [U]
 Rep. Chemical Manufacturers Assn.
Michael D. Lattner, Morrison Bros., Co., IA [M]

Joseph E. Meyer, Joseph E. Seagram & Sons, Inc., NY [U]
 Rep. Distilled Spirits Council of the U.S.
Armin E. Mittermaier, Data Action, IN [U]
 Rep. Petroleum Marketers Assn. of America
Joseph R. Natale, Exxon Mobil Research & Engr, NJ [U]
 Rep. Nat'l Petroleum Refiners Assn.
Francisco N. Nazario, Exxon Research & Engr Co., NJ [U]
Albert S. Pela, Jr., Exxon Mobil Research & Engr, NJ [U]
 Rep. American Petroleum Inst.
Robert N. Renkes, Petroleum Equipment Inst., OK [M]
David P. Saporito, Kemper Insurance, AZ [I]
Orville M. Slye, Jr., Loss Control Assoc. Inc., PA [SE]
Brian P. Stuber, Oldcastle Precast/Utility Vault, AZ [M]
William A. Thornberg, HSB Industrial Risk Insurers, CT [I]

Alternates

Angela Campisi, UDV North America, CT [U]
 (Alt. to J. E. Meyer)
James W. Cragun, Phillips Petroleum Co., OK [U]
 (Alt. to A. S. Pela)
John A. Davenport, West Hartford, CT [I]
 (Alt. to W. A. Thornberg)
Rodney Hoke, URS Greiner Woodward Clyde, FL [SE]
 (Alt. to C. A. Davis)
Shari L. Hunter, Underwriters Laboratories Inc., CA [RT]
 (Alt. to J. V. Brannan)

David C. Kirby, Union Carbide Corp., WV [U]
 (Alt. to G. D. Kirby)
Patrick A. McLaughlin, McLaughlin & Assoc., CA [M]
 (Alt. to S. D. Curran)
Anthony M. Ordile, Loss Control Assoc., Inc., PA [SE]
 (Alt. to O. M. Slye)
Jeffrey M. Shapiro, Int'l Code Consultants, TX [M]
 (Alt. to B. P. Stuber)
Jack Woycheese, Gage-Babcock & Assoc., Inc., CA [SE]
 (Alt. to F. C. Bradley)

Nonvoting

David L. Blomquist, Blomquist Fire Protection Engr., CA
 (Member Emeritus)

Donald M. Johnson, Walnut Creek, CA
 (Member Emeritus)

Robert P. Benedetti, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents or portions of documents on safeguarding against the fire and explosion hazards associated with the storage of flammable and combustible liquids in fixed aboveground and underground tanks of any size, including tanks in buildings, except as specifically covered by other NFPA documents, and with the installation of piping systems for flammable and combustible liquids. This Committee shall also have primary responsibility for documents or portions of documents on safeguarding against the fire and explosion hazards associated with the storage of flammable and combustible liquids in portable tanks whose capacity exceeds 2500 liters (660 gallons).

Contents

Chapter 1 General Provisions	30- 9	Chapter 5 Operations	30-61
1.1 Scope	30- 9	5.1 Scope	30-61
1.2 Purpose	30- 9	5.2 General	30-61
1.3 Applicability	30- 9	5.3 Facility Design	30-62
1.4 Equivalency	30- 9	5.4 Recirculating Heat Transfer Systems	30-64
1.5 Retroactivity	30- 9	5.5 Incidental Operations	30-65
1.6 Definitions	30- 9	5.6 Loading and Unloading Operations and Facilities	30-65
1.7 Definition and Classification of Liquids	30-12	5.7 Wharves	30-67
1.8 Use of Other Units	30-13	5.8 Reserved	30-69
1.9 General Requirements	30-13	5.9 Control of Ignition Sources	30-69
Chapter 2 Tank Storage	30-13	5.10 Vapor Recovery and Vapor Processing Systems	30-69
2.1 General	30-13	5.11 Solvent Distillation Units	30-70
2.2 Design and Construction of Tanks	30-13	5.12 Management of Fire Hazards	30-70
2.3 Installation of Tanks and Tank Appurtenances	30-18	5.13 Fire Protection and Fire Suppression	30-70
2.4 Testing Requirements for Tanks	30-28	Chapter 6 Electrical Equipment and Installations	30-71
2.5 Fire Prevention and Control	30-28	6.1 Scope	30-71
2.6 Operations and Maintenance of Tanks	30-29	6.2 General	30-71
Chapter 3 Piping Systems	30-31	Chapter 7 Referenced Publications	30-74
3.1 Scope	30-31	Appendix A Explanatory Material	30-75
3.2 General Requirements	30-31	Appendix B Emergency Relief Venting for Fire Exposure for Aboveground Tanks	30-89
3.3 Materials for Piping Systems	30-31	Appendix C Temporarily Out of Service, Closure in Place, or Closure by Removal of Underground Tanks	30-93
3.4 Pipe Joints	30-32	Appendix D Development of Fire Protection Criteria Shown in Section 4.8 and Suggested Fire Protection for Some Containers of Flammable and Combustible Liquids Not Covered in Section 4.8	30-95
3.5 Installation of Piping Systems	30-32	Appendix E Suggested Fire Protection for Containers of Flammable and Combustible Liquids	30-100
3.6 Testing	30-33	Appendix F Fugitive Emissions Calculations	30-104
3.7 Vent Piping	30-33	Appendix G Referenced Publications	30-106
3.8 Static Electricity	30-34	Index	30-108
3.9 Identification	30-34		
Chapter 4 Container and Portable Tank Storage	30-34		
4.1 General	30-34		
4.2 Design, Construction, and Capacity of Containers	30-34		
4.3 Design, Construction, and Capacity of Storage Cabinets	30-35		
4.4 Design, Construction, and Operation of Inside Liquid Storage Areas	30-36		
4.5 Requirements for Liquid Storage Areas in Other Occupancies	30-39		
4.6 Hazardous Materials Storage Lockers	30-41		
4.7 Outdoor Storage	30-42		
4.8 Automatic Fire Protection for Inside Storage	30-43		
4.9 Manual Fire Protection	30-61		
4.10 Control of Ignition Sources	30-61		

NFPA 30

Flammable and Combustible Liquids Code

2000 Edition

NOTICE: An asterisk (*) following the number or letter designating a paragraph indicates that explanatory material on the paragraph can be found in Appendix A.

Changes other than editorial are indicated by a vertical rule in the margin of the pages on which they appear. These lines are included as an aid to the user in identifying changes from the previous edition. Where one or more complete paragraph(s) has been deleted, the deletion is indicated by a bullet between the paragraphs that remain.

Information on referenced publications can be found in Chapter 7 and Appendix G.

Chapter 1 General Provisions

1.1 Scope.

1.1.1* This code shall apply to the storage, handling, and use of flammable and combustible liquids, including waste liquids, as herein defined and classified.

1.1.2 This code shall not apply to the following:

- (1)* Any liquid that has a melting point equal to or greater than 100°F (37.8°C) or that does not meet the criteria for fluidity given in the definition for *liquid* in Section 1.7
- (2) Any liquefied gas or cryogenic liquid as defined in Section 1.6
- (3)* Any liquid that does not have a flash point, which can be flammable under some conditions, such as certain halogenated hydrocarbons and mixtures containing halogenated hydrocarbons
- (4)* Any aerosol product
- (5) Any mist, spray, or foam
- (6) Storage of flammable and combustible liquids as covered by NFPA 395, *Standard for the Storage of Flammable and Combustible Liquids at Farms and Isolated Sites*

1.1.3 This code shall also not apply to the following:

- (1)* Transportation of flammable and combustible liquids as governed by the U.S. Department of Transportation
- (2)* Storage, handling, and use of fuel oil tanks and containers connected with oil burning equipment

1.2* **Purpose.** The purpose of this code shall be to provide reasonable requirements for the safe storage and handling of flammable and combustible liquids.

1.3 **Applicability.** Chapters 2 and 3 shall apply to bulk storage of liquids in tanks and similar vessels. Chapter 4 shall apply to storage of liquids in containers and portable tanks in storage areas and in warehouses. Chapter 5 shall apply to handling of liquids in manufacturing and related operations and processes. Chapter 6 shall apply to electrical systems.

1.4 Equivalency.

1.4.1 Nothing in this code shall be intended to prevent the use of systems, methods, or devices of equivalent or superior quality, strength, fire resistance, effectiveness, durability, or safety over those prescribed by this code, provided that technical documentation is submitted to the authority having jurisdiction

to demonstrate equivalency and the system, method, or device is approved for the intended purpose.

1.4.2 The provisions of this code shall be permitted to be altered at the discretion of the authority having jurisdiction after consideration of special situations, such as topographical conditions of the site, presence or absence of protective features (e.g., barricades, walls, etc.), adequacy of building exits, the nature of the occupancy, proximity to buildings or adjoining property and the construction of such buildings, capacity and construction of proposed storage tanks and the nature of the liquids to be stored, the nature of the process, the degree to which private fire protection is provided, and the capabilities of the local fire department. Such alternate arrangements shall provide protection at least equivalent to that required by this code.

1.4.3 The provisions of this code shall also be permitted to be altered at the discretion of the authority having jurisdiction in cases where other regulations, such as for environmental protection, impose requirements that are not anticipated by this code. Such alternate arrangements shall provide protection at least equivalent to that required by this code.

1.4.4 Installations made in accordance with the applicable requirements of the following standards shall be deemed to be in compliance with this code:

- (1) NFPA 30A, *Code for Motor Fuel Dispensing Facilities and Repair Garages*
- (2) NFPA 32, *Standard for Drycleaning Plants*
- (3) NFPA 33, *Standard for Spray Application Using Flammable or Combustible Materials*
- (4) NFPA 34, *Standard for Dipping and Coating Processes Using Flammable or Combustible Liquids*
- (5) NFPA 35, *Standard for the Manufacture of Organic Coatings*
- (6) NFPA 36, *Standard for Solvent Extraction Plants*
- (7) NFPA 37, *Standard for the Installation and Use of Stationary Combustion Engines and Gas Turbines*
- (8) NFPA 45, *Standard on Fire Protection for Laboratories Using Chemicals*
- (9) Chapter 10 of NFPA 99, *Standard for Health Care Facilities*

1.5* **Retroactivity.** The provisions of this code shall be considered necessary to provide a reasonable level of protection from loss of life and property from fire and explosion. They shall reflect situations and the state of the art prevalent at the time the code was issued. Unless otherwise noted, it shall not be intended that the provisions of this code be applied to facilities, equipment, structures, or installations that were existing or approved for construction or installation prior to the effective date of this code, except in those cases where it is determined by the authority having jurisdiction that the existing situation involves a distinct hazard to life or adjacent property.

1.6 **Definitions.** For the purpose of this code, the following terms shall be defined as follows:

1.6.1 **Apartment House.** A building or that portion of a building containing more than two dwelling units.

1.6.2* **Approved.** Acceptable to the authority having jurisdiction.

1.6.3* **Authority Having Jurisdiction.** The organization, office, or individual responsible for approving equipment, materials, an installation, or a procedure.

1.6.4 **Barrel.** A volume of 42 U.S. gal (158.9 L).

1.6.5 Basement. A story of a building or structure having one-half or more of its height below ground level and to which access for fire-fighting purposes is unduly restricted.

1.6.6 Boiling Point. See 1.7.2.1.

1.6.7* Boil-Over. An event in the burning of certain oils in an open-top tank when, after a long period of quiescent burning, there is a sudden increase in fire intensity associated with expulsion of burning oil from the tank. Boil-over occurs when the residues from surface burning become more dense than the unburned oil and sink below the surface to form a hot layer, which progresses downward much faster than the regression of the liquid surface. When this hot layer, called a "heat wave," reaches water or water-in-oil emulsion in the bottom of the tank, the water is first superheated and then boils almost explosively, overflowing the tank. Oils subject to boil-over consist of components having a wide range of boiling points, including both light ends and viscous residues. These characteristics are present in most crude oils and can be produced in synthetic mixtures.

1.6.8 Building.

1.6.8.1* Important Building. A building that is considered not expendable in an exposure fire.

1.6.8.2 Storage Tank Building. A three-dimensional space that is enclosed by a roof and a wall that covers more than one-half of the possible area of the sides of the space, is of sufficient size to allow entry by personnel, will likely limit the dissipation of heat or dispersion of vapors, and restricts access for fire fighting. (See 2.3.4.)

1.6.9 Container. Any vessel of 60 U.S. gal (227 L) or less capacity used for transporting or storing liquids.

1.6.9.1 Closed Container. A container as herein defined, so sealed by means of a lid or other device that neither liquid nor vapor will escape from it at ordinary temperatures.

1.6.10 Crude Petroleum. Hydrocarbon mixtures that have a flash point below 150°F (65.6°C) and that have not been processed in a refinery.

1.6.11 Distillery. A plant or that portion of a plant where liquids produced by fermentation are concentrated and where the concentrated products are also mixed, stored, or packaged.

1.6.12 Dwelling. A building that is occupied exclusively for residence purposes and has not more than two dwelling units. Also, a building that is used as a boarding or rooming house and that serves not more than 15 persons with meals or sleeping accommodations or both.

1.6.13 Dwelling Unit. One or more rooms arranged for the use of one or more individuals living together as a single housekeeping unit, with cooking, living, sanitary, and sleeping facilities.

1.6.14 Emergency Relief Venting. An opening, construction method, or device that will automatically relieve excessive internal pressure due to an exposure fire.

1.6.15 Fire Area. An area of a building separated from the remainder of the building by construction having a fire resistance of at least 1 hour and having all communicating openings properly protected by an assembly having a fire resistance rating of at least 1 hour.

1.6.16 Fire Point. The lowest temperature at which a liquid will ignite and achieve sustained burning when exposed to a test flame in accordance with ASTM D 92, *Standard Test Method for Flash and Fire Points by Cleveland Open Cup*.

1.6.17 Flash Point. See 1.7.2.2.

1.6.18 Fugitive Emissions. Releases of flammable vapor that continuously or intermittently occur from process equipment during normal operations. These include leaks from pump seals, valve packing, flange gaskets, compressor seals, process drains, etc.

1.6.19 Hazardous Material or Hazardous Chemical. Material presenting dangers beyond the fire problems relating to flash point and boiling point. These dangers can arise from but are not limited to toxicity, reactivity, instability, or corrosivity.

1.6.20 Hazardous Materials Storage Locker. A movable prefabricated structure, manufactured primarily at a site other than the final location of the structure and transported completely assembled or in a ready-to-assemble package to the final location. It is intended to meet local, state, and federal requirements for outside storage of hazardous materials.

1.6.21 Hazardous Reaction or Hazardous Chemical Reaction. Reactions that result in dangers beyond the fire problems relating to flash point and boiling point of either the reactants or of the products. These dangers might include, but are not limited to, toxic effects, reaction speed (including detonation), exothermic reaction, or production of unstable or reactive materials.

1.6.22 Heat Transfer Fluid (HTF). A liquid that is used as a medium to transfer heat energy from a heater or vaporizer to a remote heat consumer (e.g., injection molding machine, oven, or dryer, or jacketed chemical reactor).

1.6.23 Hotel. Buildings or groups of buildings under the same management in which there are sleeping accommodations for hire, primarily used by transients who are lodged with or without meals, including, but not limited to, inns, clubs, motels, and apartment hotels.

1.6.24 Incidental Liquid Use or Storage. Use or storage as a subordinate activity to that which establishes the occupancy or area classification.

1.6.25 Inside Liquid Storage Area. A room or building used for the storage of liquids in containers or portable tanks, separated from other types of occupancies.

1.6.25.1 Inside Room. A room totally enclosed within a building and having no exterior walls.

1.6.25.2 Cutoff Room. A room within a building and having at least one exterior wall.

1.6.25.3 Attached Building. A building having only one common wall with another building having other types of occupancies.

1.6.25.4 Liquid Warehouse. A separate, detached building or attached building used for warehousing-type operations for liquids.

1.6.26 Labeled. Equipment or materials to which has been attached a label, symbol, or other identifying mark of an organization that is acceptable to the authority having jurisdiction and concerned with product evaluation, that maintains periodic inspection of production of labeled equipment or materials, and by whose labeling the manufacturer indicates compliance with appropriate standards or performance in a specified manner.

1.6.27 Liquefied Gas. A gas that, under its charged pressure, is partially liquid at 70°F (21°C).

1.6.28 Liquid. See 1.7.2.3.

1.6.28.1 Cryogenic Liquid. A refrigerated liquid gas having a boiling point below -130°F (-90°C) at atmospheric pressure.

1.6.28.2 Stable Liquid. Any liquid not defined as unstable.

1.6.28.3 Unstable Liquid. A liquid that, in the pure state or as commercially produced or transported, will vigorously polymerize, decompose, undergo condensation reaction, or become self-reactive under conditions of shock, pressure, or temperature.

1.6.28.4* Water-Miscible Liquid. A liquid that mixes in all proportions with water without the use of chemical additives, such as emulsifying agents.

1.6.29* Listed. Equipment, materials, or services included in a list published by an organization that is acceptable to the authority having jurisdiction and concerned with evaluation of products or services, that maintains periodic inspection of production of listed equipment or materials or periodic evaluation of services, and whose listing states that either the equipment, material, or service meets appropriate designated standards or has been tested and found suitable for a specified purpose.

1.6.30 Occupancies.

1.6.30.1 Assembly Occupancy. All buildings or portions of buildings used for gathering 50 or more persons for such purposes as deliberation, worship, entertainment, dining, amusement, or awaiting transportation.

1.6.30.2 Educational Occupancy. A building or structure or any portion thereof used for the purpose of learning or of receiving educational instruction.

1.6.30.3 Institutional Occupancy. A building or structure or any portion thereof used by persons who are harbored or detained to receive medical, charitable, or other care or treatment or by persons involuntarily detained.

1.6.30.4 Mercantile Occupancy. The occupancy or use of a building or structure or that portion thereof used for the wholesale or retail display, storage, and merchandising of goods or wares.

1.6.30.5 Office Occupancy. A building or structure or any portion thereof used for the transaction of business or the rendering or receiving of professional services.

1.6.31 Occupancy Classification. The system of defining the predominant operating characteristic of a portion of a building or plant for purposes of applying relevant sections of this code. This can include, but is not limited to, distillation, oxidation, cracking, and polymerization.

1.6.31.1 Outdoor Occupancy Classification. Similar to occupancy classification, except that it applies to outdoor operations not enclosed in a building or shelter.

1.6.32 Operating Unit (Vessel) or Process Unit (Vessel). The equipment in which a unit operation or unit process is conducted. (See also definition 1.6.44, *Unit Operation or Unit Process*.)

1.6.33 Operations. A general term that includes, but is not limited to, the use, transfer, storage, and processing of liquids.

1.6.34* Pier. A structure, usually of greater length than width and projecting from the shore into a body of water. A pier can be either open-deck or can be provided with a superstructure.

1.6.35 Plants.

1.6.35.1 Bulk Plant or Terminal. That portion of a property where liquids are received by tank vessel, pipelines, tank car, or tank vehicle and are stored or blended in bulk for the purpose of distributing such liquids by tank vessel, pipeline, tank car, tank vehicle, portable tank, or container.

1.6.35.2 Chemical Plant. A large integrated plant or that portion of such a plant, other than a refinery or distillery, where liquids are produced by chemical reactions or used in chemical reactions.

1.6.36 Pressure Vessel. Any fired or unfired vessel within the scope of the applicable section of the ASME *Boiler and Pressure Vessel Code*.

1.6.37 Process or Processing. An integrated sequence of operations. The sequence can be inclusive of both physical and chemical operations, unless the term is modified to restrict it to one or the other. The sequence can involve, but is not limited to, preparation, separation, purification, or change in state, energy content, or composition.

1.6.38 Protection for Exposures. Fire protection for structures on property adjacent to liquid storage. Fire protection for such structures shall be acceptable when located either within the jurisdiction of any public fire department or adjacent to plants having private fire brigades capable of providing cooling water streams on structures on property adjacent to liquid storage.

1.6.39 Refinery. A plant in which flammable or combustible liquids are produced on a commercial scale from crude petroleum, natural gasoline, or other hydrocarbon sources.

1.6.40 Safety Can. A listed container, of not more than 5-gal (18.9-L) capacity, having a spring-closing lid and spout cover and so designed that it will safely relieve internal pressure when subjected to fire exposure.

1.6.41 Solvent Distillation Unit. An appliance that distills a flammable or combustible liquid to remove contaminants and recover the liquid.

1.6.42 Staging. Temporary storage in a process area of liquids in containers, intermediate bulk containers, and portable tanks.

1.6.43 Tanks.

1.6.43.1 Aboveground Tank. A tank that is installed above grade, at grade, or below grade without backfill.

1.6.43.2* Atmospheric Tank. A storage tank that has been designed to operate at pressures from atmospheric through 1.0 psig (760 mm Hg through 812 mm Hg) measured at the top of the tank.

1.6.43.3 Fire-Resistant Tank. A listed aboveground tank that provides fire-resistive protection from exposure to a high-intensity liquid pool fire.

1.6.43.4 Low-Pressure Tank. A storage tank designed to withstand an internal pressure above 1.0 psig (6.9 kPa) but not more than 15 psig (103.4 kPa) measured at the top of the tank.

1.6.43.5 Portable Tank. Any closed vessel having a liquid capacity over 60 U.S. gal (227 L) and not intended for fixed installation. This includes intermediate bulk containers (IBCs) as defined and regulated by the U.S. Department of Transportation.

1.6.43.6 Protected Aboveground Tank. An aboveground storage tank that is listed in accordance with UL 2085, *Standard for Insulated Aboveground Tanks for Flammable and Combustible Liquids*, or an equivalent test procedure that consists of a primary tank provided with protection from physical damage and fire-resistive protection from exposure to a high-intensity liquid pool fire.

1.6.43.7 Secondary Containment Tank. A tank that has an inner and outer wall with an interstitial space (annulus) between the walls and that has a means for monitoring the interstitial space for a leak.

1.6.43.8 Storage Tank. Any vessel having a liquid capacity that exceeds 60 gal (227 L), is intended for fixed installation, and is not used for processing.

1.6.44 Unit Operation or Unit Process. A segment of a physical or chemical process that might or might not be integrated with other segments to constitute the manufacturing sequence.

1.6.45 Vapor Pressure. See 1.7.2.4.

1.6.46 Vapor Processing Equipment. Those components of a vapor processing system designed to process vapors or liquids captured during transfer or filling operations.

1.6.47 Vapor Processing System. A system designed to capture and process vapors displaced during transfer or filling operations by use of mechanical or chemical means. Examples are systems using blower-assist for capturing vapors and refrigeration, absorption, and combustion systems for processing vapors.

1.6.48 Vapor Recovery System. A system designed to capture and retain, without processing, vapors displaced during transfer or filling operations. Examples are balanced-pressure vapor displacement systems and vacuum-assist systems without vapor processing.

1.6.49 Vault. An enclosure consisting of four walls, a floor, and a top for the purpose of containing a liquid storage tank and not intended to be occupied by personnel other than for inspection, repair, or maintenance of the vault, the storage tank, or related equipment.

1.6.50 Ventilation. As specified in this code, movement of air that is provided for the prevention of fire and explosion. It is considered adequate if it is sufficient to prevent accumulation of significant quantities of vapor-air mixtures in concentrations over one-fourth of the lower flammable limit.

1.6.51* Warehouses.

1.6.51.1 General-Purpose Warehouse. A separate, detached building or portion of a building used only for warehousing-type operations.

1.6.51.2 Liquid Warehouse. See definition 1.6.25.4, Liquid Warehouse.

1.6.52* Wharf. A structure having a platform built along and parallel to a body of water. A wharf can be either open-deck or can be provided with a superstructure.

1.7 Definition and Classification of Liquids.

1.7.1 Scope. This section shall establish a uniform system of defining and classifying flammable and combustible liquids for the purpose of proper application of this code. This section shall apply to any liquid within the scope of and subject to the requirements of this code.

1.7.1.1 This section shall not apply to mists, sprays, or foams.

1.7.1.2 This section shall not apply to liquids that do not have flash points, but are capable of burning under certain conditions, such as certain halogenated hydrocarbons and certain mixtures of flammable or combustible liquids and halogenated hydrocarbons. [See A.1.1.2(3).]

1.7.2 Definitions. For the purpose of this section, the following terms shall have the definitions given.

1.7.2.1* Boiling Point. The temperature at which the vapor pressure of a liquid equals the surrounding atmospheric pressure. For purposes of defining the boiling point, atmospheric pressure shall be considered to be 14.7 psia (760 mm Hg). For

mixtures that do not have a constant boiling point, the 20 percent evaporated point of a distillation performed in accordance with ASTM D 86, *Standard Method of Test for Distillation of Petroleum Products*, shall be considered to be the boiling point.

1.7.2.2* Flash Point. The minimum temperature of a liquid at which sufficient vapor is given off to form an ignitable mixture with the air, near the surface of the liquid or within the vessel used, as determined by the appropriate test procedure and apparatus specified in 1.7.4.

1.7.2.3 Liquid. Any material that has a fluidity greater than that of 300 penetration asphalt when tested in accordance with ASTM D 5, *Standard Method of Test for Penetration of Bituminous Materials*.

1.7.2.4* Vapor Pressure. The pressure, measured in pounds per square inch, absolute (psia), exerted by a liquid, as determined by ASTM D 323, *Standard Method of Test for Vapor Pressure of Petroleum Products (Reid Method)*.

1.7.3* Classification of Liquids. Any liquid within the scope of this code and subject to the requirements of this code shall be known generally as either a flammable liquid or a combustible liquid and shall be defined and classified in accordance with this subsection.

1.7.3.1 Combustible Liquid. Any liquid that has a closed-cup flash point at or above 100°F (37.8°C), as determined by the test procedures and apparatus set forth in 1.7.4. Combustible liquids are classified as Class II or Class III as follows: (a) *Class II Liquid* — any liquid that has a flash point at or above 100°F (37.8°C) and below 140°F (60°C); (b) *Class IIIA* — any liquid that has a flash point at or above 140°F (60°C), but below 200°F (93°C); (c) *Class IIIB* — any liquid that has a flash point at or above 200°F (93°C).

1.7.3.2 Flammable Liquid. Any liquid that has a closed-cup flash point below 100°F (37.8°C), as determined by the test procedures and apparatus set forth in 1.7.4. Flammable liquids are classified as Class I as follows: (a) *Class I Liquid* — any liquid that has a closed-cup flash point below 100°F (37.8°C) and a Reid vapor pressure not exceeding 40 psia (2068.6 mm Hg) at 100°F (37.8°C), as determined by ASTM D 323, *Standard Method of Test for Vapor Pressure of Petroleum Products (Reid Method)*. Class I liquids are further classified as follows: (1) Class IA liquids — those liquids that have flash points below 73°F (22.8°C) and boiling points below 100°F (37.8°C); (2) Class IB liquids — those liquids that have flash points below 73°F (22.8°C) and boiling points at or above 100°F (37.8°C); (3) Class IC liquids — those liquids that have flash points at or above 73°F (22.8°C), but below 100°F (37.8°C).

1.7.4 Determination of Flash Point. The flash point of a liquid shall be determined according to the methods specified in this subsection.

1.7.4.1 The flash point of a liquid having a viscosity below 5.5 centiStokes at 104°F (40°C) or below 9.5 centiStokes at 77°F (25°C) shall be determined in accordance with ASTM D 56, *Standard Method of Test for Flash Point by the Tag Closed Cup Tester*. *Exception: Cut-back asphalts, liquids that tend to form a surface film, and liquids that contain suspended solids shall not be tested in accordance with ASTM D 56, even if they otherwise meet the viscosity criteria.*

1.7.4.2 The flash point of a liquid having a viscosity of 5.5 centiStokes or more at 104°F (40°C) or 9.5 centiStokes or more at 77°F (25°C) or a flash point of 200°F (93.4°C) or higher shall

be determined in accordance with ASTM D 93, *Standard Test Methods for Flash Point by the Pensky-Martens Closed Tester*.

1.7.4.3 As an alternative, ASTM D 3278, *Standard Method of Tests for Flash Point of Liquids by Setaflash Closed Tester*, shall be permitted to be used for paints, enamels, lacquers, varnishes, and related products and their components that have flash points between 32°F (0°C) and 230°F (110°C) and viscosities below 150 Stokes at 77°F (25°C).

1.7.4.4 As an alternative, ASTM D 3828, *Standard Test Methods for Flash Point by Small Scale Closed Tester*, shall be permitted to be used for materials other than those for which ASTM D 3278, *Standard Method of Tests for Flash Point of Liquids by Setaflash Closed Tester*, is specifically required.

1.8 Use of Other Units. If a value for measurement given in this standard is followed by an equivalent value in other units, the first stated shall be regarded as the requirement. The given equivalent value shall be considered to be approximate.

1.9 General Requirements.

1.9.1 Storage. Liquids shall be stored in tanks in accordance with Chapter 2 or in containers, portable tanks, and intermediate bulk containers in accordance with Chapter 4.

1.9.2 Exits. Egress from buildings and areas covered by this code shall meet the requirements of NFPA 101®, *Life Safety Code*®.

Chapter 2 Tank Storage

2.1 General.

2.1.1 Scope. This chapter shall apply to the following:

- (1) The storage of flammable and combustible liquids, as defined in 1.7.3, in fixed aboveground and underground tanks
- (2) The storage of flammable and combustible liquids in portable tanks and bulk containers whose capacity exceeds 793 gal (3000 L)
- (3) The design, installation, testing, operation, and maintenance of such tanks, portable tanks, and bulk containers

2.1.2 Applicability. Reserved.

2.1.3 Definitions. For the purposes of this chapter, the following term shall be defined as follows.

2.1.3.1 Floating Roof Tank. A tank that incorporates one of the following designs:

- (1) A closed-top pontoon or double-deck metal floating roof in an open-top tank constructed in accordance with API Standard 650, *Welded Steel Tanks for Oil Storage*
- (2) A fixed metal roof with ventilation at the top and roof eaves constructed in accordance with API 650 and containing a closed-top pontoon or double-deck metal floating roof meeting the requirements of API 650
- (3) A fixed metal roof with ventilation at the top and roof eaves constructed in accordance with API 650 and containing a metal floating cover supported by liquidtight metal floating devices that provide sufficient buoyancy to prevent the liquid surface from being exposed when half of the flotation is lost

An internal metal floating pan, roof, or cover that does not meet this definition or one that uses plastic foam (except for

seals) for flotation, even if encapsulated in metal or fiberglass, shall be considered a fixed roof tank.

2.2 Design and Construction of Tanks.

2.2.1 General Requirements. Tanks shall be permitted to be of any shape, size, or type consistent with sound engineering design. Metal tanks shall be welded, riveted and caulked, or bolted, or constructed using a combination of these methods.

2.2.2 Materials of Construction. Tanks shall be designed and built in accordance with recognized good engineering standards for the material of construction being used. Tanks shall be of steel or other approved noncombustible material, with the following limitations and exceptions:

(a) The materials of construction for tanks and their appurtenances shall be compatible with the liquid to be stored. In case of doubt about the properties of the liquid to be stored, the supplier, producer of the liquid, or other competent authority shall be consulted.

(b) Tanks shall be permitted to be constructed of combustible materials only when approved by the authority having jurisdiction. Tanks constructed of combustible materials shall be limited to any of the following:

- (1) Underground installation
- (2) Use where required by the properties of the liquid stored
- (3) Aboveground storage of Class IIIB liquids in areas not exposed to a spill or leak of Class I or Class II liquid
- (4) Storage of Class IIIB liquids inside a building protected by an approved automatic fire-extinguishing system

(c) Unlined concrete tanks shall be permitted to be used for storing liquids that have a gravity of 40° API or heavier. Concrete tanks with special linings shall be permitted to be used for other liquids provided they are designed and constructed in accordance with good engineering practice.

(d) Tanks shall be permitted to have combustible or noncombustible linings. The choice of the lining material and its required thickness shall depend on the properties of the liquid to be stored.

(e) Special engineering consideration shall be required if the specific gravity of the liquid to be stored exceeds that of water or if the tank is designed to contain liquids at a liquid temperature below 0°F (−17.8°C).

2.2.3 Design Standards.

2.2.3.1 Design Standards for Atmospheric Tanks.

2.2.3.1.1 Atmospheric tanks, including those incorporating secondary containment, shall be designed and constructed in accordance with recognized standards or approved equivalents. Atmospheric tanks that meet any of the following standards shall be deemed as meeting the requirements of 2.2.3.1:

- (1) UL 58, *Standard for Steel Underground Tanks for Flammable and Combustible Liquids*; UL 80, *Standard for Steel Inside Tanks for Oil Burner Fuel*; UL 142, *Standard for Steel Aboveground Tanks for Flammable and Combustible Liquids*; UL 2080, *Standard for Fire Resistant Tanks for Flammable and Combustible Liquids*; or UL 2085, *Standard for Protected Aboveground Tanks for Flammable and Combustible Liquids*
- (2) API Specification 12B, *Bolted Tanks for Storage of Production Liquids*; API Specification 12D, *Field Welded Tanks for Storage of Production Liquids*; API Specification 12F, *Shop Welded Tanks for Storage of Production Liquids*; or API Standard 650, *Welded Steel Tanks for Oil Storage*

- (3) UL 1316, *Standard for Glass-Fiber Reinforced Plastic Underground Storage Tanks for Petroleum Products, Alcohols, and Alcohol-Gasoline Mixtures*
- (4) UL 1746, *Standard for External Corrosion Protection Systems for Steel Underground Storage Tanks*

2.2.3.1.2 Atmospheric tanks designed and constructed in accordance with Appendix F of API Standard 650, *Welded Steel Tanks for Oil Storage*, shall be permitted to operate at pressures from atmospheric to 1.0 psig (gauge pressure of 6.9 kPa). All other tanks shall be limited to operation from atmospheric to 0.5 psig (gauge pressure of 3.5 kPa).

Exception No. 1: Atmospheric tanks that are not designed and constructed in accordance with Appendix F of API Standard 650, Welded Steel Tanks for Oil Storage, shall be permitted to operate at pressures from atmospheric to 1.0 psig (gauge pressure of 6.9 kPa) only if an engineering analysis is performed to determine that the tank can withstand the elevated pressure.

Exception No. 2: Horizontal cylindrical and rectangular tanks built according to any of the standards specified in 2.2.3.1.1 shall be permitted to operate at pressures from atmospheric to 1 psig (gauge pressure of 6.9 kPa) and shall be limited to 2.5 psig (gauge pressure of 17.2 kPa) under emergency venting conditions.

2.2.3.1.3 Low-pressure tanks and pressure vessels shall be permitted to be used as atmospheric tanks.

2.2.3.1.4 Atmospheric tanks shall not be used to store a liquid at a temperature at or above its boiling point.

2.2.3.2 Design Standards for Low-Pressure Tanks.

2.2.3.2.1 Low-pressure tanks shall be designed and constructed in accordance with recognized standards or approved equivalents. Low-pressure tanks that meet either of the following standards shall be deemed as meeting the requirements of 2.2.3.2:

- (1) API 620, *Recommended Rules for the Design and Construction of Large, Welded, Low-Pressure Storage Tanks*
- (2) ASME *Code for Unfired Pressure Vessels*, Section VIII, Division I

2.2.3.2.2 Low-pressure tanks shall not be operated above their design pressures.

2.2.3.2.3 Pressure vessels shall be permitted to be used as low-pressure tanks.

2.2.3.3 Design Standards for Pressure Vessels.

2.2.3.3.1 Tanks with storage pressures above 15 psig (gauge pressure of 103.4 kPa) shall be designed and constructed in accordance with recognized standards or approved equivalents. Pressure vessels that meet any of the following standards shall be deemed as meeting the requirements of 2.2.3.3:

- (1) Fired pressure vessels shall be designed and constructed in accordance with Section I (Power Boilers), or Section VIII, Division 1 or Division 2 (Pressure Vessels), as applicable, of the ASME *Boiler and Pressure Vessel Code*.
- (2) Unfired pressure vessels shall be designed and constructed in accordance with Section VIII, Division 1 or Division 2, of the ASME *Boiler and Pressure Vessel Code*.

2.2.3.3.2* Pressure vessels that do not meet the requirements of 2.2.3.3.1(1) or (2) shall be permitted to be used provided approval has been obtained from the state or other governmental jurisdiction in which they are to be used.

2.2.3.3.3 Pressure vessels shall not be operated above their design pressures. The normal operating pressure of the vessel shall not exceed the design pressure of the vessel.

2.2.4 Design of Tank Supports.

2.2.4.1* Supports for tanks shall be designed and constructed in accordance with recognized standards or approved equivalents.

2.2.4.2 Tanks shall be supported in a manner that prevents excessive concentration of loads on the supported portion of the shell.

2.2.4.3 In areas subject to earthquakes, tank supports and connections shall be designed to resist damage as a result of such shocks.

2.2.5 Design of Tank Vents.

2.2.5.1 Normal Venting for Tanks.

2.2.5.1.1 Atmospheric storage tanks shall be adequately vented to prevent the development of vacuum or pressure that can distort the roof of a cone roof tank or that exceeds the design pressure of other atmospheric tanks when filling or emptying the tank or because of atmospheric temperature changes.

2.2.5.1.2 Normal vents shall be sized in accordance with either API Standard 2000, *Venting Atmospheric and Low-Pressure Storage Tanks*, or another accepted standard. Alternatively, the normal vent shall be at least as large as the largest filling or withdrawal connection but in no case shall it be less than 1.25 in. (32 mm) nominal inside diameter.

2.2.5.1.3 Low-pressure tanks and pressure vessels shall be adequately vented to prevent the development of pressure or vacuum that exceeds the design pressure of the tank or vessel when filling or emptying the tank or vessel or because of atmospheric temperature changes. Means shall also be provided to prevent overpressure from any pump discharging into the tank or vessel when the pump discharge pressure can exceed the design pressure of the tank or vessel.

2.2.5.1.4 If any tank or pressure vessel has more than one fill or withdrawal connection and simultaneous filling or withdrawal can be made, the vent size shall be based on the maximum anticipated simultaneous flow.

2.2.5.1.5 For tanks equipped with vents that permit pressures to exceed 2.5 psig (gauge pressure of 17.2 kPa) and for low-pressure tanks and for pressure vessels, the outlet of all vents and vent drains shall be arranged to discharge in a manner that prevents localized overheating of or flame impingement on any part of the tank, if vapors from the vents are ignited.

2.2.5.1.6 Tanks and pressure vessels that store Class IA liquids shall be equipped with venting devices that are normally closed except when venting under pressure or vacuum conditions.

2.2.5.1.7 Tanks and pressure vessels that store Class IB and Class IC liquids shall be equipped with venting devices or with listed flame arrestors. When used, vent devices shall be normally closed except when venting under pressure or vacuum conditions.

2.2.5.1.8 Tanks of 3000 bbl (476,910 L) capacity or less that store crude petroleum in crude-producing areas and outside aboveground atmospheric tanks of less than 23.8 bbl (3785 L) capacity that contain other than Class IA liquids shall be permitted to have open vents. (*See exception to 2.2.5.2.1.*)

2.2.5.1.9* Flame arrestors or venting devices required in 2.2.5.1.6 and 2.2.5.1.7 shall be permitted to be omitted on tanks that store Class IB or Class IC liquids where conditions are such that their use can, in case of obstruction, result in damage to the tank.

2.2.5.2 Emergency Relief Venting for Fire Exposure for Above-ground Tanks.

2.2.5.2.1 Every aboveground storage tank shall have emergency relief venting in the form of construction or a device or devices that will relieve excessive internal pressure caused by an exposure fire. This requirement shall also apply to each compartment of a compartmented tank, the interstitial space (annulus) of a secondary containment-type tank, and the enclosed space of tanks of closed-top dike construction. This requirement shall also apply to spaces or enclosed volumes, such as those intended for insulation, membranes, or weather shields, that can contain liquid because of a leak from the primary vessel and can inhibit venting during fire exposure. The insulation, membrane, or weather shield shall not interfere with emergency venting.

Exception: Tanks storing Class IIIB liquids that are larger than 285 bbl (45,306 L) capacity and are not within the diked area or the drainage path of tanks storing Class I or Class II liquids do not need to meet this requirement.

2.2.5.2.2 For vertical tanks, the emergency relief venting construction referred to in 2.2.5.2.1 shall be permitted to be a floating roof, a lifter roof, a weak roof-to-shell seam, or another approved pressure-relieving construction. If used, a weak roof-to-shell seam shall be constructed to fail preferential to any other seam and shall be designed in accordance with API Standard 650, *Welded Steel Tanks for Oil Storage*, or UL 142, *Standard for Steel Aboveground Tanks for Flammable and Combustible Liquids*.

2.2.5.2.3 Where entire dependence for emergency relief venting is placed upon pressure-relieving devices, the total venting capacity of both normal and emergency vents shall be sufficient to prevent rupture of the shell or bottom of a vertical tank or of the shell or heads of a horizontal tank. If unstable liquids are stored, the effects of heat or gas resulting from polymerization, decomposition, condensation, or self-reactivity shall be taken into account. The total emergency relief venting capacity of both normal and emergency venting devices shall be not less than that determined in Table 2.2.5.2.3.

Exception: As provided for in 2.2.5.2.5 and 2.2.5.2.6.

The following requirements shall also apply:

(a) Emergency relief vent devices shall be vaportight and shall be permitted to be any one of the following:

- (1) Self-closing manway cover
- (2) Manway cover provided with long bolts that permit the cover to lift under internal pressure
- (3) Additional or larger relief valve or valves

(b) The wetted area of the tank shall be calculated on the basis of 55 percent of the total exposed area of a sphere or spheroid, 75 percent of the total exposed area of a horizontal tank, 100 percent of the exposed shell and floor area of a rectangular tank, but excluding the top surface of the tank, and the first 30 ft (9 m) above grade of the exposed shell area of a vertical tank.

(See Appendix B for the square footage of typical tank sizes.)

Table 2.2.5.2.3 Wetted Area Versus Cubic Feet Free Air per Hour* [14.7 psia and 60°F (101.3 kPa and 15.6°C)]

ft ²	CFH	ft ²	CFH	ft ²	CFH
20	21,100	160	168,000	900	493,000
30	31,600	180	190,000	1,000	524,000
40	42,100	200	211,000	1,200	557,000
50	52,700	250	239,000	1,400	587,000
60	63,200	300	265,000	1,600	614,000
70	73,700	350	288,000	1,800	639,000
80	84,200	400	312,000	2,000	662,000
90	94,800	500	354,000	2,400	704,000
100	105,000	600	392,000	2,800	742,000
				and over	
120	126,000	700	428,000		
140	147,000	800	462,000		

For SI units, 10 ft² = 0.93 m²; 36 ft³ = 1.0 m³.

*Interpolate for intermediate values.

2.2.5.2.4 The total emergency relief venting capacity for tanks and storage vessels designed to operate at pressures above 1 psig (gauge pressure of 6.9 kPa) shall be not less than that determined in Table 2.2.5.2.3.

Exception: When the exposed wetted area of the tank is greater than 2800 ft² (260 m²), the total emergency relief venting capacity shall be not less than that determined in Table 2.2.5.2.4 or shall be not less than that calculated by the following formula:

$$CFH = 1107A^{0.82}$$

where:

CFH = venting requirement (ft³ of free air per hour)

A = exposed wetted surface (ft²)

Table 2.2.5.2.4 Wetted Area over 2800 ft² (260 m²) and Pressures over 1 psig (gauge pressure of 6.9 kPa)

ft ²	CFH	ft ²	CFH
2,800	742,000	9,000	1,930,000
3,000	786,000	10,000	2,110,000
3,500	892,000	15,000	2,940,000
4,000	995,000	20,000	3,720,000
4,500	1,100,000	25,000	4,470,000
5,000	1,250,000	30,000	5,190,000
6,000	1,390,000	35,000	5,900,000
7,000	1,570,000	40,000	6,570,000
8,000	1,760,000		

For SI units, 10 ft² = 0.93 m²; 36 ft³ = 1.0 m³.

2.2.5.2.5 The total emergency relief venting capacity for any specific stable liquid shall be permitted to be determined by the following formula:

$$\text{ft}^3 \text{ of free air per hour} = V \frac{1337}{L\sqrt{M}}$$

where:

V = ft³ of free air per hour from Table 2.2.5.2.3

L = latent heat of vaporization of specific liquid (Btu/lb)

M = molecular weight of specific liquids

2.2.5.2.6 For tanks containing stable liquids, the required emergency relief venting capacity determined by 2.2.5.2.3, 2.2.5.2.4, or 2.2.5.2.5 shall be permitted to be multiplied by one of the following reduction factors when protection is provided as indicated. Only one of the following factors shall be used for any one tank:

(a) A reduction factor of 0.5 shall be allowed for tanks with wetted area greater than 200 ft² (18.6 m²) that are provided with drainage that meets the requirements of 2.3.2.3.1.

(b) A reduction factor of 0.3 shall be allowed for tanks that are protected with a water spray system that meets the requirements of NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*, and that are provided with drainage that meets the requirements of 2.3.2.3.1.

(c) A reduction factor of 0.3 shall be allowed for tanks protected with insulation that meets the requirements of 2.2.5.2.7.

(d) A reduction factor of 0.15 shall be allowed for tanks that: are protected with a water spray system that meets the requirements of NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*; that have insulation that meets the requirements of 2.2.5.2.7; and that are provided with drainage that meets the requirements of 2.3.2.3.1.

Exception No. 1: Where water-miscible liquids whose heats of combustion and rates of burning are equal to or less than those of ethyl alcohol (ethanol) are stored, processed, or handled and where there is no potential fire exposure from liquids other than these liquids, the emergency relief venting capacity shall be permitted to be reduced by an additional 50 percent. Drainage shall not be required to obtain this reduction. In no case shall the factors in 2.2.5.2.6(a) through (d) be reduced to less than 0.15.

Exception No. 2: Where liquids that are not water-miscible and whose heats of combustion and rates of burning are equal to or less than those of ethyl alcohol (ethanol) are stored, processed, or handled and where there is no potential fire exposure from liquids other than these liquids, the emergency relief venting capacity determined by 2.2.5.2.6(a) or (c) shall be permitted to be reduced by an additional 50 percent. No further reduction shall be allowed for protection by means of water spray. Drainage shall not be required to obtain this reduction. In no case shall the factors in 2.2.5.2.6(a) through (d) be reduced to less than 0.15.

2.2.5.2.7 Insulation for which credit is taken in 2.2.5.2.6 shall meet the following performance criteria:

- (1) The insulation shall remain in place under fire exposure conditions.
- (2) The insulation shall withstand dislodgment when subjected to hose stream impingement during fire exposure.

Exception: This requirement shall not apply where use of solid hose streams is not contemplated or would not be practical.

- (3) The insulation shall maintain a maximum conductance value of 4.0 Btu per hr per ft² per degree Fahrenheit (Btu/hr/ft²/°F) when the outer insulation jacket or cover is at a temperature of 1660°F (904.4°C) and when the mean temperature of the insulation is 1000°F (537.8°C).

2.2.5.2.8 The outlets of all vents and vent drains on tanks equipped with emergency relief venting that permits pressures to exceed 2.5 psig (gauge pressure of 17.2 kPa) shall be arranged to discharge so that localized overheating or flame impingement on any part of the tank will not occur if vapors from the vents are ignited.

2.2.5.2.9 Each commercial tank venting device shall have stamped on it the start-to-open pressure, the pressure at which the valve reaches the full open position, and the flow capacity at the latter pressure. If the start-to-open pressure is less than 2.5 psig (gauge pressure of 17.2 kPa) and the pressure at the full open position is greater than 2.5 psig (gauge pressure of 17.2 kPa), the flow capacity at 2.5 psig (gauge pressure of 17.2 kPa) shall also be stamped on the venting device. The flow capacity shall be expressed in cubic feet per hour of air at 60°F (15.6°C) and 14.7 psia (760 mm Hg).

2.2.5.2.9.1 The flow capacity of tank venting devices less than 8 in. (200 mm) in nominal pipe size shall be determined by actual test. These tests shall be permitted to be conducted by a qualified, impartial outside agency or by the manufacturer if certified by a qualified, impartial observer.

2.2.5.2.9.2* The flow capacity of tank venting devices equal to or greater than 8 in. (200 mm) nominal pipe size, including manway covers with long bolts, shall be determined by test or by calculation. If determined by calculation, the opening pressure shall be measured by test, the calculation shall be based on a flow coefficient of 0.5 applied to the rated orifice, the rating pressure and corresponding free orifice area shall be stated, and the word *calculated* shall appear on the nameplate.

2.2.5.2.10* **Extension of Emergency Vent Piping.** Piping to or from approved emergency vent devices for atmospheric and low-pressure tanks shall be sized to provide emergency vent flows that limit the back pressure to less than the maximum pressure permitted by the design of the tank. Piping to or from approved emergency vent devices for pressure vessels shall be sized in accordance with the ASME *Boiler and Pressure Vessel Code*.

2.2.5.3* **Normal Venting for Underground Storage Tanks.** Tank venting systems shall be provided with sufficient capacity to prevent blowback of vapor or liquid at the fill opening while the tank is being filled. Vent pipes shall be sized in accordance with Table 2.2.5.3, but shall not be less than 1.25 in. (32 mm) nominal inside diameter. Where tank venting devices are installed in vent lines, their flow capacities shall be determined in accordance with 2.2.5.2.9.

2.2.5.4 Vent Piping. Piping for normal and emergency relief venting shall be designed in accordance with Chapter 3.

Table 2.2.5.3 Vent Line Diameters

Maximum Flow (gpm)	Pipe Length*		
	50 ft (in.)	100 ft (in.)	200 ft (in.)
100	1 ¹ / ₄	1 ¹ / ₄	1 ¹ / ₄
200	1 ¹ / ₄	1 ¹ / ₄	1 ¹ / ₄
300	1 ¹ / ₄	1 ¹ / ₄	1 ¹ / ₂
400	1 ¹ / ₄	1 ¹ / ₂	2
500	1 ¹ / ₂	1 ¹ / ₂	2
600	1 ¹ / ₂	2	2
700	2	2	2
800	2	2	3
900	2	2	3
1000	2	2	3

For SI units, 1 in. = 25 mm; 1 ft = 0.3 m; 1 gal = 3.8 L.

*Vent lines of 50 ft, 100 ft, and 200 ft of pipe plus 7 ell.

2.2.6* Design of Storage Tank System Corrosion Protection. Metal used to fabricate the tank shall be thick enough to compensate for internal corrosion expected during the design life of the tank or other approved means of corrosion protection shall be provided.

2.2.6.1 External Corrosion Protection for Underground Tanks.

2.2.6.1.1 Underground tanks and their piping shall be protected by either of the following:

- (1)* A properly engineered, installed, and maintained cathodic protection system in accordance with recognized standards of design
- (2)* Approved or listed corrosion-resistant materials or systems.

2.2.6.1.2* Selection of the type of protection to be employed shall be based upon the corrosion history of the area and the judgment of a qualified engineer. The authority having jurisdiction shall be permitted to waive the requirements for corrosion protection where evidence is provided that such protection is not necessary.

2.2.6.2 Internal Corrosion Protection for All Tanks. Where tanks are not designed in accordance with 2.2.6, or with standards of the American Petroleum Institute, American Society of Mechanical Engineers, or the Underwriters Laboratories Inc. or if corrosion is anticipated beyond that provided for in the design formulas or standards used, additional metal thickness or suitable protective coatings or linings shall be provided to compensate for the corrosion loss expected during the design life of the tank.

2.2.7 Vaults for Aboveground Tanks.

2.2.7.1 General. Aboveground tanks shall be permitted to be installed in vaults that meet the requirements of 2.2.7. Except as modified by the provisions of 2.2.7, vaults shall meet all other applicable provisions of this code. Vaults shall be constructed and listed in accordance with UL 2245, *Standard for Below-Grade Vaults for Flammable Liquid Storage Tanks*. Vaults shall be permitted to be either above or below grade.

2.2.7.2 Vault Design and Construction. Vaults shall be designed and constructed to meet the following requirements:

- (a) The walls and floor of the vault shall be constructed of reinforced concrete at least 6 in. (150 mm) thick.
- (b) The top of an abovegrade vault shall be constructed of noncombustible material and shall be designed to be weaker than the walls of the vault to ensure that the thrust of any explosion occurring inside the vault is directed upward before destructive internal pressure develops within the vault. The top of an at-grade or belowgrade vault shall be designed to relieve or contain the force of any explosion occurring inside the vault.
- (c) The top and floor of the vault and the tank foundation shall be designed to withstand all anticipated loading, including loading from vehicular traffic, where applicable.
- (d) The walls and floor of a belowgrade vault shall be designed to withstand anticipated soil and hydrostatic loading. The vault shall be liquidtight.
- (e) Adjacent vaults shall be permitted to share a common wall.
- (f) The vault enclosure shall have no openings except those necessary for access to, inspection of, and filling, emptying, and venting of the tank.

(g) When required, the vault shall be designed to be wind and earthquake resistant, in accordance with good engineering practice.

(h) The vault shall be provided with connections to permit ventilation to dilute, disperse, and remove any vapors prior to personnel entering the vault.

(i) The vault shall be provided with a means for personnel entry.

(j) The vault shall be provided with an approved means to admit a fire suppression agent.

2.2.7.3 Tank Selection and Arrangement. Tanks shall be listed for aboveground use. Each tank shall be in its own vault and shall be completely enclosed by the vault. Sufficient clearance between the tank and the vault shall be provided to allow for visual inspection and maintenance of the tank and its appurtenances. Backfill shall not be permitted around the tank.

2.2.7.4 Tank Appurtenances.

2.2.7.4.1 Vent pipes that are provided for normal tank venting shall terminate outside and at least 12 ft (3.6 m) above ground level.

2.2.7.4.2 Emergency vents shall be vaportight and shall be permitted to discharge inside the vault. Long-bolt manhole covers shall not be permitted for this purpose.

2.2.7.4.3 An approved means of overfill protection shall be provided for the tanks in the vaults. The use of ball float valves shall be prohibited.

2.2.7.5 Exhaust Ventilation Systems. Vaults that contain tanks storing Class I liquids shall be ventilated at a rate of not less than 1 ft³/min/ft² of floor area (0.3 m³/min/m²), but not less than 150 cfm (4 m³/min). Such ventilation shall operate continuously or shall be designed to operate upon activation of a vapor and liquid detection system. Failure of the exhaust air flow shall automatically shut down the dispensing system. The exhaust system shall be designed to provide air movement across all parts of the vault floor. Supply and exhaust ducts shall extend to within 3 in. (75 mm), but not more than 12 in. (300 mm), of the floor. The exhaust system shall be installed in accordance with the provisions of NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Noncombustible Particulate Solids*.

2.2.7.6 Vapor and Liquid Detection Systems.

2.2.7.6.1 The vault shall be provided with an approved vapor and liquid detection system and equipped with on-site audible and visual warning devices with battery back-up.

2.2.7.6.2 Vapor detection systems shall sound an alarm when the system detects vapors that reach or exceed 25 percent of the lower flammable limit of the liquid stored. Vapor detectors shall be located no higher than 12 in. (305 mm) above the lowest point in the vault.

2.2.7.6.3 Liquid detection systems shall sound an alarm upon detection of any liquid, including water. Liquid detectors shall be located in accordance with the manufacturer's instructions.

2.2.7.6.4 Activation of either the vapor detection system or the liquid detection system shall cause a signal to be sounded at an approved, constantly attended location within the facility serving the tanks or at an approved location.

2.2.7.7 Vault Installation. The vault shall be installed in accordance with the following requirements:

(a) Each vault and its tank shall be anchored to resist uplifting by groundwater or flooding, including when the tank is empty.

(b) Vaults that are not resistant to damage from the impact of a motor vehicle shall be protected by collision barriers.

(c) Dispensing devices shall be permitted to be installed on the tops of vaults.

(d) Means shall be provided to recover liquid from the vault. If a pump is used to meet this requirement, the pump shall not be permanently installed in the vault. Electric-powered portable pumps shall be approved for use in Class I, Division 1 locations, as defined in NFPA 70, *National Electrical Code*®.

(e) At each entry point, a warning sign indicating the need for procedures for safe entry into confined spaces shall be posted. Each entry point shall be secured against unauthorized entry and vandalism.

2.2.8 Fire-Resistant Tanks. Reserved.

2.2.9 Protected Tanks. Protected tanks shall be listed and shall be tested in accordance with UL 2085, *Standard for Protected Aboveground Tanks for Flammable and Combustible Liquids*. Protected tanks shall also meet both of the following requirements:

(a) The construction that provides the required fire-resistive protection shall prevent release of liquid, failure of the primary tank, failure of the supporting structure, and impairment of venting for a period of not less than 2 hours when tested using the fire exposure specified in UL 2085.

(b) The size of the emergency vent shall not be permitted to be reduced, as would otherwise be permitted by 2.2.5.2.6.

2.3 Installation of Tanks and Tank Appurtenances.

2.3.1 Foundations for and Anchoring of Tanks.

2.3.1.1* Tanks shall rest on the ground or on foundations made of concrete, masonry, piling, or steel. Tank foundations shall be designed to minimize the possibility of uneven settling of the tank and to minimize corrosion in any part of the tank resting on the foundation.

2.3.1.2 Where tanks are supported above their foundations, tank supports shall be installed on firm foundations. Supports for tanks storing Class I, Class II, or Class IIIA liquids shall be of concrete, masonry, or protected steel.

Exception: Single wood timber supports (not cribbing), laid horizontally, shall be permitted to be used for outside aboveground tanks if not more than 12 in. (0.3 m) high at their lowest point.

2.3.1.3* Steel structures or exposed piling for tanks storing Class I, Class II, or Class IIIA liquids shall be protected by materials having a fire resistance rating of not less than 2 hours.

Exception No. 1: Steel saddles do not need to be protected if less than 12 in. (0.3 m) high at their lowest point.

Exception No. 2: At the discretion of the authority having jurisdiction, water spray protection in accordance with NFPA 15, Standard for Water Spray Fixed Systems for Fire Protection, or NFPA 13, Standard for the Installation of Sprinkler Systems, or equivalent shall be permitted to be used.

2.3.1.4 Where a tank is located in an area subject to flooding, provisions shall be taken to prevent tanks, either full or empty, from floating during a rise in water level up to the established maximum flood stage.

2.3.2* Installation of Aboveground Tanks.

2.3.2.1 Location with Respect to Property Lines, Public Ways, and Important Buildings on the Same Property.

2.3.2.1.1 Tanks storing Class I, Class II, or Class IIIA stable liquids and operating at pressures not in excess of 2.5 psig (gauge pressure of 17.2 kPa) shall be located in accordance with Tables 2.3.2.1.1(a) and 2.3.2.1.1(b). Where tank spacing is based on a weak roof-to-shell seam design, the user shall present evidence certifying such construction to the authority having jurisdiction upon request.

Exception: Vertical tanks with weak roof-to-shell seams (see 2.2.5.2.2) that store Class IIIA liquids shall be permitted to be located at one-half the distances specified in Table 2.3.2.1.1(a), provided the tanks are not within the same diked area as or the drainage path of a tank storing a Class I or Class II liquid.

2.3.2.1.2 Tanks storing Class I, Class II, or Class IIIA stable liquids and operating at pressures that exceed 2.5 psig (gauge pressure of 17.2 kPa), or are equipped with emergency venting that will permit pressures to exceed 2.5 psig (gauge pressure of 17.2 kPa), shall be located in accordance with Tables 2.3.2.1.2 and 2.3.2.1.1(b).

2.3.2.1.3 Tanks storing liquids with boil-over characteristics shall be located in accordance with Table 2.3.2.1.3. Liquids with boil-over characteristics shall not be stored in fixed roof tanks larger than 150 ft (45.7 m) in diameter, unless an approved inerting system is provided on the tank.

2.3.2.1.4 Tanks storing unstable liquids shall be located in accordance with Tables 2.3.2.1.4 and 2.3.2.1.1(b).

Table 2.3.2.1.1(a) Stable Liquids [Operating Pressure 2.5 psig (gauge pressure of 17.2 kPa) or Less]

Type of Tank	Protection	Minimum Distance in Feet from Property Line that Is or Can Be Built Upon, Including the Opposite Side of a Public Way, and Shall Not Be Less than 5 ft	Minimum Distance in Feet from Nearest Side of Any Public Way or from Nearest Important Building on the Same Property and Shall Not Be Less than 5 ft
Floating roof	Protection for exposures ¹	$1/2$ times diameter of tank	$1/6$ times diameter of tank
	None	Diameter of tank but need not exceed 175 ft	$1/6$ times diameter of tank
Vertical with weak roof-to-shell seam	Approved foam or inerting system ² on tanks not exceeding 150 ft in diameter ³	$1/2$ times diameter of tank	$1/6$ times diameter of tank
	Protection for exposures ¹	Diameter of tank	$1/3$ times diameter of tank
	None	2 times diameter of tank but need not exceed 350 ft	$1/3$ times diameter of tank
Horizontal and vertical tanks with emergency relief venting to limit pressures to 2.5 psig (gauge pressure of 17.2 kPa)	Approved inerting system ² on the tank or approved foam system on vertical tanks	$1/2$ times Table 2.3.2.1.1(b)	$1/2$ times Table 2.3.2.1.1(b)
	Protection for exposures ¹	Table 2.3.2.1.1(b)	Table 2.3.2.1.1(b)
	None	2 times Table 2.3.2.1.1(b)	Table 2.3.2.1.1(b)

For SI units, 1 ft = 0.3 m.

¹See definition 1.6.38, Protection for Exposures.²See NFPA 69, *Standard on Explosion Prevention Systems*.³For tanks over 150 ft in diameter, use "Protection for Exposures" or "None," as applicable.**Table 2.3.2.1.1(b) Reference Table for Use in Tables 2.3.2.1.1(a), 2.3.2.1.2, and 2.3.2.1.4**

Tank Capacity (gal)	Minimum Distance from Property Line that Is or Can Be Built Upon, Including the Opposite Side of a Public Way (ft)	Minimum Distance from Nearest Side of Any Public Way or from Nearest Important Building on the Same Property (ft)
275 or less	5	5
276 to 750	10	5
751 to 12,000	15	5
12,001 to 30,000	20	5
30,001 to 50,000	30	10
50,001 to 100,000	50	15
100,001 to 500,000	80	25
500,001 to 1,000,000	100	35
1,000,001 to 2,000,000	135	45
2,000,001 to 3,000,000	165	55
3,000,001 or more	175	60

For SI units, 1 ft = 0.3 m; 1 gal = 3.8 L.

Table 2.3.2.1.2 Stable Liquids [Operating Pressure Greater than 2.5 psig (gauge pressure of 17.2 kPa)]

Type of Tank	Protection	Minimum Distance in Feet from Property Line that Is or Can Be Built Upon, Including the Opposite Side of a Public Way	Minimum Distance in Feet from Nearest Side of Any Public Way or from Nearest Important Building on the Same Property
Any type	Protection for exposures*	$1 1/2$ times Table 2.3.2.1.1(b) but shall not be less than 25 ft	$1 1/2$ times Table 2.3.2.1.1(b) but shall not be less than 25 ft
	None	3 times Table 2.3.2.1.1(b) but shall not be less than 50 ft	$1 1/2$ times Table 2.3.2.1.1(b) but shall not be less than 25 ft

For SI units, 1 ft = 0.3 m.

*See definition 1.6.38, Protection for Exposures.

Table 2.3.2.1.3 Boil-Over Liquids

Type of Tank	Protection	Minimum Distance in Feet from Property Line that Is or Can Be Built Upon, Including the Opposite Side of a Public Way, and Shall Not Be Less than 5 ft	Minimum Distance in Feet from Nearest Side of Any Public Way or from Nearest Important Building on the Same Property and Shall Not Be Less than 5 ft
Floating roof [see Table 2.3.2.1.1(a)]	Protection for exposures ¹	$1\frac{1}{2}$ times diameter of tank	$1\frac{1}{6}$ times diameter of tank
	None	Diameter of tank	$1\frac{1}{6}$ times diameter of tank
Fixed roof	Approved foam or inerting system ²	Diameter of tank	$1\frac{1}{3}$ times diameter of tank
	Protection for exposures ¹	2 times diameter of tank	$\frac{2}{3}$ times diameter of tank
	None	4 times diameter of tank but need not exceed 350 ft	$\frac{2}{3}$ times diameter of tank

For SI units, 1 ft = 0.3 m.

¹See definition 1.6.38, Protection for Exposures.

²See NFPA 69, *Standard on Explosion Prevention Systems*.

Table 2.3.2.1.4 Unstable Liquids

Type of Tank	Protection	Minimum Distance in Feet from Property Line that Is or Can Be Built Upon, Including the Opposite Side of a Public Way	Minimum Distance in Feet from Nearest Side of Any Public Way or from Nearest Important Building on the Same Property
Horizontal and vertical tanks with emergency relief venting to permit pressure not in excess of 2.5 psig (gauge pressure of 17.2 kPa)	Tank protected with any one of the following: approved water spray, approved inerting, ¹ approved insulation and refrigeration, approved barricade	Table 2.3.2.1.1 (b) but not less than 25 ft	Not less than 25 ft
	Protection for exposures ²	$2\frac{1}{2}$ times Table 2.3.2.1.1 (b) but not less than 50 ft	Not less than 50 ft
	None	5 times Table 2.3.2.1.1 (b) but not less than 100 ft	Not less than 100 ft
Horizontal and vertical tanks with emergency relief venting to permit pressure over 2.5 psig (gauge pressure of 17.2 kPa)	Tank protected with any one of the following: approved water spray, approved inerting, ¹ approved insulation and refrigeration, approved barricade	2 times Table 2.3.2.1.1 (b) but not less than 50 ft	Not less than 50 ft
	Protection for exposures ²	4 times Table 2.3.2.1.1 (b) but not less than 100 ft	Not less than 100 ft
	None	8 times Table 2.3.2.1.1 (b) but not less than 150 ft	Not less than 150 ft

For SI units, 1 ft = 0.3 m.

¹See NFPA 69, *Standard on Explosion Prevention Systems*.

²See definition 1.6.38, Protection for Exposures.

2.3.2.1.5 Tanks storing Class IIIB stable liquids shall be located in accordance with Table 2.3.2.1.5.

Exception: If located within the same diked area as or the drainage path of a tank storing a Class I or Class II liquid, the tank storing Class IIIB liquid shall be located in accordance with 2.3.2.1.1.

2.3.2.1.6 Where two tank properties of diverse ownership have a common boundary, the authority having jurisdiction

shall be permitted, with the written consent of the owners of the two properties, to substitute the distances provided in 2.3.2.2 for the minimum distances set forth in 2.3.2.1.

2.3.2.1.7 Where end failure of a horizontal pressure tank or vessel can expose property, the tank or vessel shall be placed with its longitudinal axis parallel to the nearest important exposure.

Table 2.3.2.1.5 Class IIIB Liquids

Tank Capacity (gal)	Minimum Distance from Property Line that Is or Can Be Built Upon, Including the Opposite Side of a Public Way (ft)	Minimum Distance from Nearest Side of Any Public Way or from Nearest Important Building on the Same Property (ft)
12,000 or less	5	5
12,001 to 30,000	10	5
30,001 to 50,000	10	10
50,001 to 100,000	15	10
100,001 or more	15	15

For SI units, 1 ft = 0.3 m; 1 gal = 3.8 L.

2.3.2.2 Shell-to-Shell Spacing Between Any Two Adjacent Aboveground Tanks.

2.3.2.2.1 Tanks storing Class I, Class II, or Class III stable liquids shall be separated by the distances given in Table 2.3.2.2.1.

Exception No. 1: Tanks storing crude petroleum that have individual capacities not exceeding 126,000 gal (3000 bbl) and are located at production facilities in isolated locations do not need to be separated by more than 3 ft (0.9 m).

Exception No. 2: Tanks used only for storing Class IIIB liquids need not be separated by more than 3 ft (0.9 m) provided they are not within the same diked area as or drainage path of a tank storing a Class I or Class II liquid.

2.3.2.2.2 Tanks storing unstable liquids shall be separated by a distance not less than one-half the sum of their diameters.

2.3.2.2.3 Where tanks are in a diked area containing Class I or Class II liquids or in the drainage path of Class I or Class II liquids and are compacted in three or more rows or in an irregular pattern, greater spacing or other means shall be permitted to be required by the authority having jurisdiction to make tanks in the interior of the pattern accessible for fire-fighting purposes.

2.3.2.2.4 The minimum horizontal separation between an LP-Gas container and a Class I, Class II, or Class IIIA liquid storage tank shall be 20 ft (6 m). Suitable measures shall be taken to prevent the accumulation of Class I, Class II, or Class IIIA liquids under adjacent LP-Gas containers such as by dikes, diversion curbs, or grading. Where flammable or combustible liquid storage tanks are within a diked area, the LP-Gas containers shall be outside the diked area and at least 10 ft (3 m) away from the centerline of the wall of the diked area.

Exception No. 1: If a tank storing a Class I, Class II, or Class IIIA liquid operates at pressures exceeding 2.5 psig (gauge pressure of 17.2 kPa) or is equipped with emergency relief venting that will permit pressures to exceed 2.5 psig (gauge pressure of 17.2 kPa), it shall be separated from an LP-gas container by the distance given in 2.3.2.2.1.

Exception No. 2: These requirements shall not apply where LP-Gas containers of 125 gal (475 L) or less capacity are installed adjacent to fuel oil supply tanks of 660 gal (2498 L) or less capacity.

2.3.2.3 Control of Spills from Aboveground Tanks. Every tank that contains a Class I, Class II, or Class IIIA liquid shall be provided with means to prevent an accidental release of liquid from endangering important facilities and adjoining property or from reaching waterways. Such means shall meet the requirements of 2.3.2.3.1, 2.3.2.3.2, or 2.3.2.3.3, whichever is applicable.

2.3.2.3.1 Remote Impounding. Where control of spillage is by means of drainage to a remote impounding area, so that impounded liquid will not be held against tanks, such systems shall comply with the following:

(a) A slope of not less than 1 percent away from the tank shall be provided for at least 50 ft (15 m) toward the impounding area.

(b) The impounding area shall have a capacity not less than that of the largest tank that can drain into it.

Exception: Where this is not possible because there is not enough open area around the tanks or is impractical, "partial" remote impounding for some percentage of the required capacity remote from any tank or adjoining property shall be permitted to be provided. The required volume exceeding the capacity of the partial remote impoundment shall be provided for by diking meeting the requirements of 2.3.2.3.2.

Table 2.3.2.2.1 Minimum Tank Spacing (Shell-to-Shell)

	Floating Roof Tanks	Fixed or Horizontal Tanks	
		Class I or II Liquids	Class IIIA Liquids
All tanks not over 150 ft in diameter	$\frac{1}{6}$ sum of adjacent tank diameters but not less than 3 ft	$\frac{1}{6}$ sum of adjacent tank diameters but not less than 3 ft	$\frac{1}{6}$ sum of adjacent tank diameters but not less than 3 ft
Tanks larger than 150 ft in diameter			
If remote impounding is provided in accordance with 2.3.2.3.1	$\frac{1}{6}$ sum of adjacent tank diameters	$\frac{1}{4}$ sum of adjacent tank diameters	$\frac{1}{6}$ sum of adjacent tank diameters
If diking is provided in accordance with 2.3.2.3.2	$\frac{1}{4}$ sum of adjacent tank diameters	$\frac{1}{3}$ sum of adjacent tank diameters	$\frac{1}{4}$ sum of adjacent tank diameters

For SI units, 1 ft = 0.3 m.

(c) The route of the drainage system shall be so located that, if the liquid in the drainage system is ignited, the fire will not seriously expose tanks or adjoining property.

(d) The confines of the impounding area shall be located so that, when filled to capacity, the liquid level will not be closer than 50 ft (15 m) from any property line that is or can be built upon or from any tank. Where "partial" remote impounding is used, the liquid level in the partial impounding shall meet the requirement of 2.3.2.3.1. The excess volume shall meet the requirements of impounding by diking as provided or as in 2.3.2.3.2. Tank spacing shall be determined based on the diked tank provisions of Table 2.3.2.2.1.

2.3.2.3.2 Impounding around Tanks by Diking. Where protection of adjoining property or waterways is by means of impounding by diking around the tanks, such systems shall comply with the following:

(a) A slope of not less than 1 percent away from the tank shall be provided for at least 50 ft (15 m) or to the dike base, whichever is less.

(b)*The volumetric capacity of the diked area shall not be less than the greatest amount of liquid that can be released from the largest tank within the diked area, assuming a full tank. To allow for volume occupied by tanks, the capacity of the diked area enclosing more than one tank shall be calculated after deducting the volume of the tanks, other than the largest tank, below the height of the dike.

(c) To permit access, the outside base of the dike at ground level shall be no closer than 10 ft (3 m) to any property line that is or can be built upon.

(d)*Walls of the diked area shall be of earth, steel, concrete, or solid masonry designed to be liquidtight and to withstand a full hydrostatic head. Earthen walls 3 ft (0.9 m) or more in height shall have a flat section at the top not less than 2 ft (0.6 m) wide. The slope of an earthen wall shall be consistent with the angle of repose of the material of which the wall is constructed.

(e) The walls of the diked area shall be restricted to an average interior height of 6 ft (1.8 m) above interior grade.

Exception: Dikes shall be permitted to exceed this height where provisions are made for normal access and necessary emergency access to tanks, valves, and other equipment, and safe egress from the diked enclosure and where the following requirements are met:

(a) *Where the average height of the dike containing Class I liquids is over 12 ft (3.6 m) high, measured from interior grade, or where the distance between any tank and the top inside edge of the dike wall is less than the height of the dike wall, provisions shall be made for normal operation of valves and for access to tank roof(s) without entering below the top of the dike. These provisions shall be permitted to be met through the use of remote-operated valves, elevated walkways, or similar arrangements.*

(b) *Piping passing through dike walls shall be designed to prevent excessive stresses as a result of settlement or fire exposure.*

(c) *The minimum distance between tanks and toe of the interior dike walls shall be 5 ft (1.5 m).*

(f) Each diked area containing two or more tanks shall be subdivided, preferably by drainage channels or at least by intermediate dikes, in order to prevent spills from endangering adjacent tanks within the diked area as follows:

(1) Where storing normally stable liquids in vertical cone roof tanks constructed with weak roof-to-shell seams or in floating roof tanks, or when storing crude petroleum

in producing areas in any type of tank, one subdivision shall be provided for each tank greater than 10,000 bbl (1,590,000 L) capacity. In addition, one subdivision shall be provided for each group of tanks [no individual tank exceeding 10,000 bbl (1,590,000 L) capacity] having an aggregate capacity not greater than 15,000 bbl (2,385,000 L).

(2) Where storing normally stable liquids in tanks not covered in 2.3.2.3.2(f)(1), one subdivision shall be provided for each tank greater than 2380 bbl (378,500 L) capacity. In addition, one subdivision shall be provided for each group of tanks [no individual tank exceeding 2380 bbl (378,500 L) capacity] having an aggregate capacity not greater than 3570 bbl (567,750 L).

(3)* Where storing unstable liquids in any type of tank, one subdivision shall be provided for each tank.

Exception: Tanks installed with drainage meeting the requirements of NFPA 15, Standard for Water Spray Fixed Systems for Fire Protection, need not meet this requirement.

(4) Whenever two or more tanks storing Class I liquids, any one of which is over 150 ft (45 m) in diameter, are located in a common diked area, intermediate dikes shall be provided between adjacent tanks to hold at least 10 percent of the capacity of the tank so enclosed, not including the volume displaced by the tank.

(5) The drainage channels or intermediate dikes shall be located between tanks so as to take full advantage of the available space with due regard for the individual tank capacities. Intermediate dikes, where used, shall be not less than 18 in. (450 mm) in height.

(g) Where provision is made for draining water from diked areas, such drains shall be controlled to prevent liquids from entering natural water courses, public sewers, or public drains. Control of drainage shall be accessible under fire conditions from outside the dike.

(h) Storage of combustible materials, empty or full drums, or barrels, shall not be permitted within the diked area.

2.3.2.3.3 Secondary Containment Tanks. Where a secondary containment tank is used to provide spill control, the tank shall meet all of the following requirements:

(a) The capacity of the tank shall not exceed 12,000 gal (45,420 L).

(b) All piping connections to the tank shall be made above the normal maximum liquid level.

(c) Means shall be provided to prevent the release of liquid from the tank by siphon flow.

(d) Means shall be provided for determining the level of liquid in the tank. This means shall be accessible to the delivery operator.

(e) Means shall be provided to prevent overfilling by sounding an alarm when the liquid level in the tank reaches 90 percent of capacity and by automatically stopping delivery of liquid to the tank when the liquid level in the tank reaches 95 percent of capacity. In no case shall these provisions restrict or interfere with the proper functioning of the normal vent or the emergency vent.

(f) Spacing between adjacent tanks shall be not less than 3 ft (0.9 m).

(g) The tank shall be capable of resisting the damage from the impact of a motor vehicle or suitable collision barriers shall be provided.

(h) Where the means of secondary containment is enclosed, it shall be provided with emergency venting in accordance with 2.2.5.2.

(i) Means shall be provided to establish the integrity of the secondary containment, in accordance with 2.4.2.3 and 2.4.2.4. The secondary containment shall be designed to withstand the hydrostatic head resulting from a leak from the primary tank of the maximum amount of liquid that can be stored in the primary tank.

2.3.2.3.4 Equipment, Piping, and Fire Protection Systems in Remote Impoundment Areas or Diked Areas.

2.3.2.3.4.1* Piping Location. Only piping for product, utility, or fire protection purposes directly connected to a tank or tanks within a single diked area shall be routed through a diked area, a remote impoundment area, a spillway draining to a remote impoundment area, or above a storage tank drain-area area where the piping can be exposed to a fire.

Exception: Piping for other product lines and from adjacent tanks shall be permitted to be routed through such areas if engineering designs are provided to incorporate features to prevent the piping from creating an exposure hazard.

2.3.2.3.4.2 Drainage. Drainage shall be arranged to prevent accumulation of any liquid under the piping by sloping the grade in accordance with 2.3.2.3.2. Corrosion-resistant piping and piping that is protected against corrosion shall be permitted to be buried where such drainage is not provided or is not practical.

2.3.2.3.4.3* Equipment Location. If located in a remote impoundment area, a diked area, or a spillway draining to a remote impoundment area, process equipment, pumps, instrumentation, and electrical utilization equipment shall be located or protected so that a fire involving such equipment does not constitute an exposure hazard to the tank or tanks in the same area for a period of time consistent with the response and suppression capabilities of the fire-fighting operations available to the location.

2.3.2.3.4.4 Fire Protection Systems. Hose connections, controls, and control valves for application of fire protection foam or water to tanks shall be located outside remote impoundment areas, diked areas, or spillways draining to a remote impoundment area.

2.3.2.3.4.5 Combustible Materials. Structures such as stairways, walkways, instrumentation shelters, and supports for piping and equipment that are located in a remote impoundment area, diked area, or spillway draining to a remote impoundment area shall be constructed of noncombustible materials.

2.3.2.4 Vent Piping for Aboveground Tanks. Piping for normal and emergency relief venting shall be constructed in accordance with Chapter 3.

2.3.2.5 Tank Openings Other than Vents for Aboveground Tanks.

2.3.2.5.1 Each connection to an aboveground tank through which liquid can normally flow shall be provided with an internal or an external valve located as close as practical to the shell of the tank.

2.3.2.5.2 Each connection below the liquid level through which liquid does not normally flow shall be provided with a liquidtight closure such as a valve, plug, or blind, or a combination of these.

2.3.2.5.3 Openings for gauging on tanks storing Class I liquids shall be provided with a vaportight cap or cover.

2.3.2.5.4* Fill pipes that enter the top of a tank shall terminate within 6 in. (150 mm) of the bottom of the tank. Fill pipes shall be installed or arranged so that vibration is minimized.

Exception No. 1: Fill pipes in tanks whose vapor space under the expected range of normal operating conditions is not in the flammable range or is inerted need not meet this requirement.

Exception No. 2: Fill pipes in tanks handling liquids with minimal potential for accumulation of static electricity need not meet this requirement provided that the fill line is designed and the system is operated to avoid mist generation and an adequate level of residence time is provided downstream of filters or screens such that the charge generated is dissipated.

2.3.2.5.5 Filling and emptying connections for Class I, Class II, and Class IIIA liquids that are connected and disconnected shall be located outside of buildings at a location free from any source of ignition. They shall be located not less than 5 ft (1.5 m) away from any building opening. Such connections for any liquid shall be closed and liquidtight when not in use and shall be properly identified.

2.3.2.6 Requirements for Aboveground Tanks Located in Areas Subject to Flooding.

2.3.2.6.1 Vertical tanks shall be located so that the tops of the tanks extend above the maximum flood stage by at least 30 percent of their allowable storage capacity.

2.3.2.6.2 Horizontal tanks that are located where more than 70 percent of the tank's storage capacity will be submerged at the established flood stage shall be secured by one of the following methods:

- (1) Anchored to resist movement
- (2) Attached to a foundation of steel and concrete or of concrete having sufficient weight to provide adequate load for the tank when filled with liquid and submerged by flood water to the established flood stage
- (3) Adequately secured from floating by other means

Tank vents or other openings that are not liquidtight shall extend above the maximum flood stage water level.

2.3.2.6.3 A dependable water supply shall be available for filling an empty or partially filled tank.

Exception: Where filling the tank with water is impractical or hazardous because of the contents of the tank, the tank shall be protected by other means against movement or collapse.

2.3.2.6.4 Spherical or spheroid tanks shall be protected by any of the methods specified in this subsection.

2.3.2.7 Installation Instructions. Factory-built aboveground tanks shall be provided with instructions for testing and for installation of the normal and emergency vents.

2.3.3 Installation of Underground Tanks.

2.3.3.1 Location. Excavation for underground tanks shall be made with due care to avoid undermining of foundations of existing structures. Underground tanks or tanks under buildings shall be so located with respect to existing building foundations and supports that the loads carried by the latter cannot be transmitted to the tank. The distance from any part of a tank storing Class I liquids to the nearest wall of any basement or pit shall be not less than 1 ft (0.3 m), and to any property line that can be built upon, not less than 3 ft (0.9 m). The

distance from any part of a tank storing Class II or Class III liquids to the nearest wall of any basement, pit, or property line shall be not less than 1 ft (0.3 m).

2.3.3.2 Burial Depth and Cover.

2.3.3.2.1* All underground tanks shall be installed in accordance with the manufacturer's instructions and shall be set on firm foundations and surrounded with at least 6 in. (150 mm) of noncorrosive inert material such as clean sand or gravel well tamped in place. The tank shall be placed in the hole with care.

2.3.3.2.2 Underground tanks shall be covered with not less than 2 ft (0.6 m) of earth, or with not less than 1 ft (0.3 m) of earth on top of which shall be placed a slab of reinforced concrete not less than 4 in. (100 mm) thick. Where they are, or are likely to be, subjected to traffic, they shall be protected against damage from vehicles passing over them by at least 3 ft (0.9 m) of earth cover, or 18 in. (450 mm) of well-tamped earth plus either 6 in. (150 mm) of reinforced concrete or 8 in. (200 mm) of asphaltic concrete. When asphaltic or reinforced concrete paving is used as part of the protection, it shall extend at least 1 ft (0.3 m) horizontally beyond the outline of the tank in all directions.

2.3.3.2.3 Maximum depth of cover shall be specified by the tank manufacturer and marked on the tank.

When the depth of cover is greater than the diameter of the tank or if the pressure at the bottom of the tank can exceed 10 psig (69 kPa), the manufacturer of the tank shall be consulted to determine if reinforcement of the tank is required. The specific gravity of the liquid to be stored shall be a design factor.

2.3.3.3 Vent Piping for Underground Tanks. Vent pipes from underground tanks shall be installed in accordance with Chapter 3.

2.3.3.4 Tank Openings Other than Vents for Underground Tanks.

2.3.3.4.1 Connections for all tank openings shall be liquidtight.

2.3.3.4.2 Openings for manual gauging, if independent of the fill pipe, shall be provided with a liquidtight cap or cover. Covers shall be kept closed when not gauging. If inside a building, each such opening shall be protected against liquid overflow and possible vapor release by means of a spring-loaded check valve or other approved device.

2.3.3.4.3 Fill and discharge lines shall enter tanks only through the top. Fill lines shall be sloped toward the tank. Underground tanks for Class I liquids having a capacity of more than 1000 gal (3785 L) shall be equipped with a tight fill device for connecting the fill hose to the tank.

2.3.3.4.4 Fill pipes that enter the top of a tank shall terminate within 6 in. (150 mm) of the bottom of the tank. Fill pipes shall be installed or arranged so that vibration is minimized.

Exception No. 1: Fill pipes in tanks whose vapor space under the expected range of normal operating conditions is not in the flammable range or is inerted need not meet this requirement.

Exception No. 2: Fill pipes in tanks handling liquids with minimal potential for accumulation of static electricity need not meet this requirement provided that the fill line is designed and the system operated to avoid mist generation and an adequate level of residence time is provided downstream of filters or screens such that the charge generated is dissipated. (See A.2.3.2.5.4.)

2.3.3.4.5 Filling and emptying and vapor recovery connections for Class I, Class II, or Class IIIA liquids that are connected and disconnected shall be located outside of buildings at a location free from any source of ignition and not less than 5 ft (1.5 m) away from any building opening. Such connections shall be closed and liquidtight when not in use and shall be properly identified.

2.3.3.4.6 Tank openings provided for purposes of vapor recovery shall be protected against possible vapor release by means of a spring-loaded check valve or dry-break connection, or other approved device, unless the opening is pipe connected to a vapor processing system. Openings designed for combined fill and vapor recovery shall also be protected against vapor release unless connection of the liquid delivery line to the fill pipe simultaneously connects the vapor recovery line. All connections shall be vaportight.

2.3.3.5 Requirements for Underground Tanks Located in Areas Subject to Flooding.

2.3.3.5.1 At locations where an ample and dependable water supply is available, underground tanks containing flammable or combustible liquids, so placed that more than 70 percent of their storage capacity will be submerged at the maximum flood stage, shall be so anchored, weighted, or secured as to prevent movement when filled or loaded with water and submerged by floodwater to the established flood stage. Tank vents or other openings that are not liquidtight shall be extended above maximum flood stage water level.

2.3.3.5.2 At locations where an ample and dependable water supply is not available or where filling of underground tanks with water is impractical because of the contents, each tank shall be safeguarded against movement when empty and submerged by high groundwater or floodwater by anchoring or by securing by other means. Each such tank shall be so constructed and installed that it will safely resist external pressures if submerged.

2.3.4 Storage Tank Buildings.

2.3.4.1* Scope. Subsection 2.3.4 shall apply to installations of tanks storing Class I, Class II, and Class IIIA liquids in storage tank buildings. This subsection shall not specifically apply to such tanks in process areas. (See Chapter 5.) Tanks storing Class IIIB liquids shall not be required to comply with the provisions of this subsection. A tank installation that has a canopy or roof that does not limit the dissipation of heat or dispersion of flammable vapors and does not restrict fire-fighting access and control shall be treated as an outside aboveground tank. (See 1.6.8.2.)

Exception: Tanks that meet the requirements of Section 5.5.

2.3.4.2 Location. Tanks and any associated equipment within the storage tank building shall be so located that a fire in the area shall not constitute an exposure hazard to adjoining buildings or tanks for a period of time consistent with the response and suppression capabilities of the fire-fighting operations available to the location. Compliance with 2.3.4.2.1 through 2.3.4.2.5 shall be deemed as meeting the requirements of 2.3.4.2.

2.3.4.2.1 The minimum distance from exposed property lines and buildings for tank installations within structures having walls with a fire resistance rating of less than 2 hours shall be in accordance with Table 2.3.4.2.1. Capacity of any individual tank shall not exceed 100,000 gal (380,000 L) without the approval of the authority having jurisdiction.

Exception: As modified by 2.3.4.2.2.

Table 2.3.4.2.1 Location of Storage Tank Buildings with Respect to Property Lines, Public Ways, and the Nearest Important Building on the Same Property*

Largest Tank — Operating Liquid Capacity (gal)	Minimum Distance from Property Line that Is or Can Be Built Upon, Including Opposite Side of Public Way (ft)				Minimum Distance from Nearest Side of Any Public Way or from Nearest Important Building on Same Property (ft)			
	Stable Liquid Emergency Relief		Unstable Liquid Emergency Relief		Stable Liquid Emergency Relief		Unstable Liquid Emergency Relief	
	Not over 2.5 psig	Over 2.5 psig	Not over 2.5 psig	Over 2.5 psig	Not over 2.5 psig	Over 2.5 psig	Not over 2.5 psig	Over 2.5 psig
Up to 12,000	15	25	40	60	5	10	15	20
12,001 to 30,000	20	30	50	80	5	10	15	20
30,001 to 50,000	30	45	75	120	10	15	25	40
50,001 to 100,000	50	75	125	200	15	25	40	60

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 psig = 6.9 kPa.

*Double all distances shown if protection for exposures is not provided. Distances need not exceed 300 ft.

2.3.4.2.2 Where a storage tank building has an exterior wall facing an exposure, the distances in Table 2.3.4.2.1 shall be permitted to be modified as follows:

(a) Where the wall is a blank wall having a fire resistance rating of not less than 2 hours, separation distance between the storage tank building and its exposure need not be greater than 25 ft (7.6 m).

(b)*Where a blank wall having a fire resistance rating of not less than 4 hours is provided, the distance requirements of Table 2.3.4.2.1 shall not apply. In addition, where Class IA or unstable liquids are stored, the exposing wall shall have explosion resistance in accordance with good engineering practice, and adequate deflagration venting shall be provided in the nonexposing walls and roof.

2.3.4.2.3 Other equipment associated with tanks, such as pumps, heaters, filters, and exchangers, shall not be located closer than 25 ft (7.6 m) to property lines where the adjoining property is or can be built upon or the nearest important building on the same property that is not an integral part of the storage tank building.

Exception: This spacing requirement shall not apply where exposures are protected as outlined in 2.3.4.2.2.

2.3.4.2.4 Tanks in which unstable liquids are stored shall be separated from potential fire exposures by a clear space of at least 25 ft (7.6 m) or by a wall having a fire resistance rating of not less than 2 hours.

2.3.4.2.5 Each storage tank building and each tank within the building shall be accessible from at least two sides for fire fighting and fire control.

2.3.4.3 Construction of Tank Buildings.

2.3.4.3.1 Storage tank buildings shall be constructed so as to maintain structural integrity for 2 hours under fire exposure conditions and to provide adequate access and egress for unobstructed movement of all personnel and fire protection

equipment. Compliance with 2.3.4.3.2 through 2.3.4.3.7 shall be deemed as meeting the requirements of 2.3.4.3.1.

2.3.4.3.2* Buildings or structures shall be of at least 2-hour fire resistance rating except that noncombustible or combustible construction is permitted when protected by automatic sprinklers or equivalent protection subject to the approval of the authority having jurisdiction.

2.3.4.3.3 Class I liquids and Class II or Class IIIA liquids heated above their flash points shall not be stored in basements. Means shall be provided to prevent liquid spills from running into basements. Where Class I liquids are stored above grade within buildings with basements or other below-grade areas into which flammable vapors can travel, such belowgrade areas shall be provided with mechanical ventilation designed to prevent the accumulation of flammable vapors. Enclosed storage tank pits shall not be considered basements.

2.3.4.3.4* Storage tanks shall be separated from other occupancies within the building by construction having at least a 2-hour fire resistance rating. As a minimum, each opening shall be protected by either a listed, self-closing fire door or a listed fire damper having a minimum 1-hour fire protection rating. The fire door or fire damper shall be installed in accordance with NFPA 80, *Standard for Fire Doors and Fire Windows*; NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*; or NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Noncombustible Particulate Solids*; whichever is applicable. Where Class IA or unstable liquids are being stored, deflagration vents shall be provided to the exterior of the building, and any walls separating this storage from other occupancies shall have explosion resistance in accordance with good engineering practice. Adequate deflagration venting shall be provided for the nonexposing walls.

2.3.4.3.5* Storage tank buildings shall have exit facilities arranged to prevent occupants from being trapped in the event of fire. Exits shall not be exposed by the drainage facilities described in 2.3.4.5.

2.3.4.3.6 Access aisles of at least 3 ft (0.9 m) shall be maintained for movement of fire-fighting personnel and fire protection equipment.

2.3.4.3.7 Clearance between the top of the tank and the building structure shall be a minimum of 3 ft (0.9 m) for buildings protected in accordance with 2.3.4.12.3. For buildings without fixed fire suppression systems, space shall be provided to allow for the application of hose streams to the top of the tank(s) for cooling purposes.

2.3.4.4 Ventilation of Tank Buildings.

2.3.4.4.1 Storage tank buildings storing Class I liquids or Class II or Class IIIA liquids at temperatures above their flash points shall be ventilated at a rate sufficient to maintain the concentration of vapors within the building at or below 25 percent of the lower flammable limit. Compliance with 2.3.4.4.2 through 2.3.4.4.5 shall be deemed as meeting the requirements of 2.3.4.4.1.

2.3.4.4.2* Ventilation requirements shall be confirmed by one of the following procedures:

(a) Calculations based on the anticipated fugitive emissions. (*See Appendix F for calculation methods.*)

(b) Sampling of the actual vapor concentration under normal operating conditions. The sampling shall be conducted at a distance of 5 ft (1.5 m) radius from each potential vapor source extending to or toward the bottom and the top of the enclosed storage area. The vapor concentration used to determine the required ventilation rate shall be the highest measured concentration during the sampling procedure.

(c) Ventilation at a rate of not less than 1 ft³/min/ft² (0.3 m³/min/m²) of solid floor area.

2.3.4.4.3 Ventilation shall be accomplished by natural or mechanical ventilation, with discharge or exhaust to a safe location outside the building, without recirculation of the exhaust air.

Exception: Recirculation is permitted where it is monitored continuously using a fail-safe system that is designed to automatically sound an alarm, stop recirculation, and provide full exhaust to the outside in the event that vapor-air mixtures having concentrations over 25 percent of the lower flammable limit are detected.

2.3.4.4.4* Provision shall be made for introduction of make-up air in such a manner as to avoid short-circuiting the ventilation. Ventilation shall be arranged to include all floor areas or pits where flammable vapors can collect. Where natural ventilation is inadequate, mechanical ventilation shall be provided and shall be kept in operation while flammable liquids are being handled. Local or spot ventilation, if provided, shall be permitted to be used for up to 75 percent of the required ventilation.

2.3.4.4.5 For storage tank buildings with the interior grade more than 1 ft (300 mm) below the average exterior grade, continuous mechanical ventilation in accordance with 2.3.4.4.2(c) shall be provided or a vapor detection system shall be provided and set to give a warning alarm at 25 percent of the lower flammable limit and to start the mechanical ventilation system. The alarm shall sound at a constantly attended location.

2.3.4.5 Drainage from Tank Buildings.

2.3.4.5.1 Drainage systems shall be designed to minimize fire exposure to other tanks and adjacent properties or waterways.

Compliance with 2.3.4.5.2 through 2.3.4.5.6 shall be deemed as meeting the requirements of 2.3.4.5.1.

2.3.4.5.2 A facility shall be designed and operated to prevent the normal discharge of flammable or combustible liquids to public waterways, public sewers, or adjoining property.

2.3.4.5.3 Except for drains, solid floors shall be liquidtight and the room shall be liquidtight where the walls join the floor and for at least 4 in. (100 mm) above the floor.

2.3.4.5.4 Openings in interior walls to adjacent rooms or buildings shall be provided with noncombustible, liquidtight raised sills or ramps at least 4 in. (100 mm) in height or shall be otherwise designed to prevent the flow of liquids to the adjoining areas. An open-grated trench across the width of the opening inside of the room that drains to a safe location shall be permitted to be used as an alternative to a sill or ramp.

2.3.4.5.5* The containment area shall have a capacity not less than that of the largest tank that can drain into it. Emergency drainage systems shall be provided to direct flammable or combustible liquid leakage and fire protection water to a safe location. Curbs, scuppers, or special drainage systems shall be permitted to be used. (*See 2.3.2.3.*)

2.3.4.5.6 Emergency drainage systems, if connected to public sewers or discharged into public waterways, shall be equipped with traps or separators.

2.3.4.6 Vents for Tanks Inside Tank Buildings.

2.3.4.6.1 Vents for tanks inside tank buildings shall be designed to ensure that vapors are not released inside the building. Compliance with 2.3.4.6.2 and 2.3.4.6.3 shall be deemed as meeting the requirements of 2.3.4.6.1.

2.3.4.6.2 Vents for tanks inside tank buildings shall be as required in 2.2.5.1 and 2.2.5.2, except that emergency venting by the use of weak roof-to-shell seam shall not be permitted. Automatic sprinkler systems designed in accordance with the requirements of NFPA 13, *Standard for the Installation of Sprinkler Systems*, shall be accepted by the authority having jurisdiction as equivalent to water spray systems for purposes of calculating the required airflow rates for emergency vents in 2.2.5.2.6, provided the density and coverage requirements of NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*, are met. Vents shall terminate outside the building.

2.3.4.6.3 Piping for normal and emergency relief venting shall meet the requirements of Chapter 3.

2.3.4.7 Tank Openings Other than Vents for Tanks Inside Tank Buildings.

2.3.4.7.1 Tank openings other than vents for tanks inside tank buildings shall be designed to ensure that flammable liquids or vapors are not released inside the building. Compliance with 2.3.4.7.2 through 2.3.4.7.9 shall be deemed as meeting the requirements of 2.3.4.7.1.

2.3.4.7.2 All tank openings that are located at or below the maximum liquid level shall be liquidtight; those that are located above the maximum liquid level shall be normally closed and shall be mechanically secured to prevent release of vapors.

2.3.4.7.3 Each connection through which liquid can gravity flow from a tank inside a building shall be provided with an internal or an external valve located as close as practical to the shell of the tank.

2.3.4.7.4 Each liquid transfer connection on any tank storing Class I or Class II liquids inside buildings shall be provided with one of the following:

- (1) A normally closed remotely activated valve
- (2) An automatic-closing, heat-activated valve
- (3) Another approved device

Exception: Connections used for emergency disposal or to provide for quick cutoff of flow in the event of fire in the vicinity of the tank need not meet this requirement.

2.3.4.7.4.1 The requirements of 2.3.4.7.4 shall be permitted to be met by the valve required in 2.3.4.7.3. If a separate valve is used, it shall be located adjacent to the valve required in 2.3.4.7.3.

2.3.4.7.5* Openings for manual gauging of Class I or Class II liquids, if independent of the fill pipe, shall be provided with a vaportight cap or cover. Openings shall be kept closed when not in use. Each such opening for any liquid shall be protected against liquid overflow and possible vapor release by means of a spring-loaded check valve or other approved device.

2.3.4.7.6 Fill pipes that enter the top of a tank shall terminate within 6 in. (150 mm) of the bottom of the tank. Fill pipes shall be installed or arranged so that vibration is minimized.

Exception No. 1: Fill pipes in tanks whose vapor space under the expected range of normal operating conditions is not in the flammable range or is inerted need not meet this requirement.

Exception No. 2: Fill pipes in tanks handling liquids with minimal potential for accumulation of static electricity need not meet this requirement provided that the fill line is designed and the system operated to avoid mist generation and an adequate level of residence time is provided downstream of filters or screens such that the charge generated is dissipated. (See A.2.3.2.5.4.)

2.3.4.7.7 The inlet of the fill pipe and the outlet of a vapor recovery line for which connections to tank vehicles and tank cars are made and broken shall be located outside of buildings at a location free from any source of ignition and not less than 5 ft (1.5 m) away from any building opening. Such connections shall be closed tight and protected against tampering when not in use and shall be identified.

2.3.4.7.8* Tanks storing Class I, Class II, or Class IIIA liquids inside buildings shall be equipped with a device, or other means shall be provided, to prevent overflow into the building.

2.3.4.7.9 Tank openings provided for purposes of vapor recovery shall be protected against possible vapor release by means of a spring-loaded check valve or dry-break connection or other approved device, unless the opening is pipe-connected to a vapor processing system. Openings designed for combined fill and vapor recovery shall also be protected against vapor release unless connection of the liquid delivery line to the fill pipe simultaneously connects the vapor recovery line. All connections shall be vaportight.

2.3.4.8 Electrical Systems for Tank Buildings. Installation of electrical utilization equipment and wiring shall meet the requirements of Chapter 6. Chapter 6 shall be used to determine the extent of classified locations for the purpose of installation of electrical equipment. In establishing the extent of a classified location, it shall not extend beyond a floor, wall, roof, or other solid partition that has no openings, within the classified area.

2.3.4.9 Inspection and Maintenance for Tank Buildings.

2.3.4.9.1 Combustible waste material and residues in operating areas shall be kept to a minimum, stored in covered metal containers, and disposed of daily.

2.3.4.9.2 Storage of combustible materials and empty or full drums or barrels shall not be permitted within the storage tank building.

2.3.4.10 Detection and Alarm for Tank Buildings.

2.3.4.10.1 An approved means shall be provided to promptly notify those within the plant and the available public or mutual aid fire department of any fire or other emergency.

2.3.4.10.2 Those areas, including buildings, where the potential exists for a flammable liquid spill shall be monitored as appropriate. Such methods shall include both of the following:

- (1) Personnel observation or patrol
- (2) Monitoring equipment that indicates a spill or leak has occurred in an unattended area

2.3.4.11 Portable Fire Control Equipment for Tank Buildings.

2.3.4.11.1* Listed portable fire extinguishers shall be provided for facilities in such quantities, sizes, and types as could be needed for special storage hazards as determined in accordance with 2.5.2.

2.3.4.11.2* Where the need is indicated in accordance with 2.5.4, water shall be utilized through standpipe and hose systems, or through hose connections from sprinkler systems using combination spray and straight stream nozzles to permit effective fire control.

2.3.4.11.3 Where the need is indicated in accordance with 2.5.4, mobile foam apparatus shall be provided.

2.3.4.11.4 Automotive and trailer-mounted fire apparatus, where determined necessary, shall not be used for any purpose other than fire fighting or training.

2.3.4.12 Fixed Fire Control Equipment for Tank Buildings.

2.3.4.12.1 A reliable water supply or other suitable fire control agent shall be available in pressure and quantity to meet the fire demands indicated by special storage hazards or exposure as determined by 2.5.4.

2.3.4.12.2* Hydrants, with or without fixed monitor nozzles, shall be provided in accordance with accepted practice. The number and placement shall depend on the hazard of the storage, or exposure, as determined by 2.5.4.

2.3.4.12.3* Where the need is indicated by the hazards of storage or exposure as determined by 2.5.4, fixed protection shall be required utilizing approved foam, foam-water sprinkler systems, sprinkler systems, water spray systems, deluge systems, fire-resistive materials, or a combination of these.

When foam or foam-water fire protection systems are provided, discharge densities shall be determined based on the listing criteria for selected foam discharge devices, the foam concentrate, and the specific flammable or combustible liquids to be protected.

2.3.4.12.4 If provided, fire control systems shall be designed, installed, and maintained in accordance with the following NFPA standards:

- (1) NFPA 11, *Standard for Low-Expansion Foam*
- (2) NFPA 11A, *Standard for Medium- and High-Expansion Foam Systems*
- (3) NFPA 12, *Standard on Carbon Dioxide Extinguishing Systems*
- (4) NFPA 12A, *Standard on Halon 1301 Fire Extinguishing Systems*
- (5) NFPA 13, *Standard for the Installation of Sprinkler Systems*
- (6) NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*
- (7) NFPA 16, *Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems*
- (8) NFPA 17, *Standard for Dry Chemical Extinguishing Systems*
- (9) NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*

2.4 Testing Requirements for Tanks.

2.4.1 Initial Testing. All tanks, whether shop-built or field-erected, shall be tested before they are placed in service in accordance with the applicable requirements of the code under which they were built.

2.4.1.1 An approved listing mark on a tank shall be considered to be evidence of compliance with this requirement. Tanks not marked in accordance with this subsection shall be tested before they are placed in service in accordance with good engineering principles or in accordance with the requirements for testing in the codes listed in 2.2.3.1.1, 2.2.3.2.1, or 2.2.3.3.1.

2.4.1.2 Where the vertical length of the fill and vent pipes is such that, when filled with liquid, the static head imposed on the bottom of the tank exceeds 10 psig (69 kPa), the tank and its related piping shall be tested hydrostatically to a pressure equal to the static head thus imposed. In special cases where the height of the vent above the top of the tank is excessive, the hydrostatic test pressure shall be determined by using recognized engineering practice.

2.4.1.3 Before the tank is initially placed in service, all leaks or deformations shall be corrected in an acceptable manner. Mechanical caulking shall not be permitted for correcting leaks in welded tanks except for pinhole leaks in the roof.

2.4.1.4 Tanks to be operated at pressures below their design pressure shall be tested by the applicable provisions of 2.4.1.1 or 2.4.1.2 based upon the pressure developed under full emergency venting of the tank.

2.4.2* Tightness Testing. In addition to the tests called for in 2.4.1, all tanks and connections shall be tested for tightness after installation and before being placed in service in accordance with 2.4.2.1 through 2.4.2.4, as applicable. Except for underground tanks, this test shall be made at operating pressure with air, inert gas, or water. Air pressure shall not be used to test tanks that contain flammable or combustible liquids or vapors. (See Section 3.6 for testing pressure piping.)

Exception: For field-erected tanks, the tests required by 2.4.1.1 or 2.4.1.2 shall be permitted to be considered the test for tank tightness.

2.4.2.1 Horizontal shop-fabricated aboveground tanks shall be tested for tightness either hydrostatically or with air pressure at not less than 3 psig (gauge pressure of 20.6 kPa) and not more than 5 psig (gauge pressure of 34.5 kPa). Vertical shop-fabricated aboveground tanks shall be tested for tightness either hydrostatically or with air pressure at not less than 1.5 psig (gauge pressure of 10.3 kPa) and not more than 2.5 psig (gauge pressure of 17.3 kPa).

2.4.2.2 Single-wall underground tanks and piping, before being covered, enclosed, or placed in use, shall be tested for tightness either hydrostatically or with air pressure at not less than 3 psig (gauge pressure of 20.6 kPa) and not more than 5 psig (gauge pressure of 34.5 kPa).

2.4.2.3 Underground secondary containment tanks and horizontal aboveground secondary containment tanks shall have the primary (inner) tank tested for tightness either hydrostatically or with air pressure at not less than 3 psig (gauge pressure of 20.6 kPa) and not more than 5 psig (gauge pressure of 34.5 kPa). The interstitial space (annulus) of such tanks shall be tested either hydrostatically or with air pressure at 3 to 5 psig (gauge pressure of 20.6 to 34.5 kPa), by vacuum at 5.3 in. Hg (17.9 kPa), or in accordance with the tank's listing or manufacturer's instructions. The pressure or vacuum shall be held for not less than 1 hour or for the duration specified in the listing procedures for the tank. Care shall be taken to ensure that the interstitial space is not overpressured or subjected to excessive vacuum.

2.4.2.4 Vertical aboveground secondary containment-type tanks shall have their primary (inner) tank tested for tightness either hydrostatically or with air pressure at not less than 1.5 psig (gauge pressure of 10.3 kPa) and not more than 2.5 psig (gauge pressure of 17.3 kPa). The interstitial space (annulus) of such tanks shall be tested either hydrostatically at 1.5 to 2.5 psig (gauge pressure of 10.3 to 17.3 kPa), with air pressure at 1.5 to 2.5 psig (gauge pressure of 10.3 to 17.3 kPa), by vacuum at 5.3 in. Hg (17.9 kPa), or in accordance with the tank's listing or manufacturer's instructions. The pressure or vacuum shall be held for 1 hour without evidence of leaks. Care shall be taken to ensure that the interstitial space is not overpressured or subjected to excessive vacuum.

2.4.3* Additional Testing. Tanks that have been relocated, structurally damaged, repaired, or are suspected of leaking shall be tested in a manner acceptable to the authority having jurisdiction.

2.5 Fire Prevention and Control.

2.5.1 Scope. This section shall apply to the commonly recognized management techniques and fire control methods used to prevent or minimize the loss from fire or explosion in tank storage facilities. The wide range in size, design, and location of tank storage facilities shall preclude the inclusion of detailed fire prevention and control methods applicable to all such facilities. The authority having jurisdiction shall be permitted to be consulted on specific cases, where applicable; otherwise, qualified engineering judgment shall be exercised.

2.5.2 General Requirements. Tank storage facilities shall have fire prevention and control for life safety, for minimizing property loss, and for reducing fire exposure to adjoining facilities resulting from fire and explosion. Compliance with 2.5.3 through 2.5.7 shall be deemed as meeting the requirements of 2.5.2.

2.5.3 Control of Ignition Sources.

2.5.3.1 Precautions shall be taken to prevent the ignition of flammable vapors from sources such as the following:

- (1) Open flames
- (2) Lightning
- (3) Hot surfaces
- (4) Radiant heat
- (5) Smoking

- (6) Cutting and welding
- (7) Spontaneous ignition
- (8) Frictional heat or sparks
- (9) Static electricity
- (10) Electrical sparks
- (11) Stray currents
- (12) Ovens, furnaces, and heating equipment

2.5.3.2 Smoking shall be permitted only in designated and properly identified areas.

2.5.3.3* Welding, cutting, and similar spark-producing operations shall not be permitted in areas containing flammable liquids until a written permit authorizing such work has been issued. The permit shall be issued by a person in authority following inspection of the area to assure that proper precautions have been taken and will be followed until the job is completed.

2.5.3.4* Static Electricity. All equipment such as tanks, machinery, and piping shall be designed and operated to prevent electrostatic ignitions. All metallic equipment where an ignitable mixture could be present shall be bonded or grounded. The bond or ground or both shall be physically applied or shall be inherently present by the nature of the installation. Any electrically isolated section of metallic piping or equipment shall be bonded or grounded to prevent hazardous accumulation of static electricity. All nonmetallic equipment and piping where an ignitable mixture could be present shall be given special consideration.

2.5.3.5 Electrical Installations. Design, selection, and installation of electrical wiring and electrical utilization equipment shall meet the requirements of Chapter 6.

2.5.4 Management of Fire Hazards. The extent of fire prevention and control provided for tank storage facilities shall be determined by an engineering evaluation of the installation and operation, followed by the application of sound fire protection and process engineering principles. The evaluation shall include, but not be limited to, the following:

- (1) Analysis of fire and explosion hazards of the facility
- (2) Analysis of local conditions, such as exposure to and from adjacent properties, flood potential, or earthquake potential
- (3) Fire department or mutual aid response

2.5.5 Fire Control. A fire-extinguishing system in accordance with an applicable NFPA standard shall be provided or be available for vertical atmospheric fixed-roof storage tanks larger than 50,000 gal (189,250 L) capacity, storing Class I liquids, if located in a congested area where there is an unusual exposure hazard to the tank from adjacent property or to adjacent property from the tank. Fixed-roof tanks storing Class II or III liquids at temperatures below their flash points and floating-roof tanks storing any liquid generally shall not require protection when installed in compliance with Section 2.3.

2.5.6 Emergency Planning and Training.

2.5.6.1 An emergency action plan, consistent with the available equipment and personnel, shall be established to respond to fire or other emergencies. This plan shall include the following:

- (1) Procedures to be used in case of fire, such as sounding the alarm, notifying the fire department, evacuating personnel, and controlling and extinguishing the fire

- (2) Appointment and training of persons to carry out fire safety duties
- (3) Maintenance of fire protection equipment
- (4) Holding fire drills
- (5) Shutdown or isolation of equipment to reduce the escape of liquid
- (6) Alternate measures for the safety of personnel while any fire protection equipment is shut down

2.5.6.2 Personnel responsible for the use and operation of fire protection equipment shall be trained in the use of that equipment. Refresher training shall be conducted at least annually. The personnel responsible shall be able to demonstrate knowledge of the use or operation of the fire protection equipment.

2.5.6.3 Planning of effective fire control measures shall be coordinated with local emergency response agencies. This shall include, but not be limited to, the identification of all tanks by location, contents, size, and hazard identification as required in 2.6.2.1.

2.5.6.4 Procedures shall be established to provide for safe shutdown of tank storage facilities under emergency conditions. Provisions shall be made for periodic training, inspection, and testing of associated alarms, interlocks, and controls.

2.5.6.5 The emergency procedures shall be kept readily available in an operating area and updated regularly.

2.5.6.6 Where premises are likely to be unattended for considerable periods of time, a summary of the emergency plan shall be posted or located in a strategic and accessible location.

2.5.7 Inspection and Maintenance.

2.5.7.1 All fire protection equipment shall be properly maintained and periodic inspections and tests shall be done in accordance with both standard practice and equipment manufacturer's recommendations.

2.5.7.2 Maintenance and operating practices at tank storage facilities shall control leakage and prevent spillage of liquids.

2.5.7.3 Ground areas around tank storage facilities shall be kept free of weeds, trash, or other unnecessary combustible materials.

2.5.7.4 Accessways established for movement of personnel shall be maintained clear of obstructions to permit orderly evacuation and ready access for manual fire fighting.

2.5.7.5 Combustible waste material and residues in operating areas shall be kept to a minimum, stored in covered metal containers, and disposed of daily.

2.6 Operations and Maintenance of Tanks.

2.6.1 Prevention of Overfilling of Tanks.

2.6.1.1 Aboveground tanks at terminals that receive and transfer Class I liquids from mainline pipelines or marine vessels shall follow formal written procedures to prevent overfilling of tanks utilizing one of the following methods of protection:

(a) Tanks gauged at frequent intervals by personnel continuously on the premise during product receipt with frequent acknowledged communication maintained with the supplier so flow can be promptly shut down or diverted.

(b) Tanks equipped with a high-level detection device that is independent of any gauging equipment. Alarm shall be

located where personnel who are on duty throughout product transfer can promptly arrange for flow stoppage or diversion.

(c) Tanks equipped with an independent high-level detection system that will automatically shut down or divert flow.

(d) Alternatives to instrumentation described in 2.6.1.1(b) and (c) where approved by the authority having jurisdiction as affording equivalent protection.

2.6.1.2 Instrumentation systems covered in 2.6.1.1(b) and (c) shall be electrically supervised or equivalent.

2.6.1.3 Formal written procedures required in 2.6.1.1 shall include the following:

(a) Instructions covering methods to check for proper lineup and receipt of initial delivery to tank designated to receive shipment.

(b) Provision for training and monitoring the performance of operating personnel by terminal supervision.

(c) Schedules and procedures for inspection and testing of gauging equipment and high-level instrumentation and related systems. Inspection and testing intervals shall be acceptable to the authority having jurisdiction but shall not exceed 1 year.

2.6.1.4 An underground tank shall be equipped with overfill prevention equipment that will operate as follows:

- (1) Automatically shut off the flow of liquid into the tank when the tank is no more than 95 percent full
- (2) Alert the transfer operator when the tank is no more than 90 percent full by restricting the flow of liquid into the tank or triggering the high-level alarm
- (3) Other methods approved by the authority having jurisdiction

2.6.2 Identification and Security.

2.6.2.1 Emergency Response Identification. The application of NFPA 704, *Standard System for the Identification of the Hazards of Materials for Emergency Response*, to storage tanks containing liquids shall not be required except where the contents have a health or reactivity degree of hazard of 2 or more or a flammability rating of 4. The marking shall not need to be applied directly to the tank but shall be located where it can readily be seen, such as on the shoulder of an accessway or walkway to the tank or tanks or on the piping outside of the diked area. If more than one tank is involved, the markings shall be so located that each tank can readily be identified.

2.6.2.2 Unsupervised, isolated aboveground storage tanks shall be secured and marked in such a manner as to identify the fire hazards of the tank and the tank's contents to the general public. The area in which the tank is located shall be protected from tampering or trespassing, where necessary.

2.6.3 Tanks in Areas Subject to Flooding.

2.6.3.1 Water Loading. The filling of a tank to be protected by water loading shall be started as soon as floodwaters are predicted to reach a dangerous flood stage. Where independently fueled water pumps are relied upon, sufficient fuel shall be available at all times to permit continuing operations until all tanks are filled. Tank valves shall be locked in a closed position when water loading has been completed.

2.6.3.2 Operating Instructions. Operating instructions or procedures to be followed in a flood emergency shall be readily available.

2.6.3.3 Personnel Training. Personnel relied upon to carry out flood emergency procedures shall be informed of the location and operation of valves and other equipment necessary to effect the intent of these requirements.

2.6.4 Temporary or Permanent Removal from Service of Aboveground Tanks.

2.6.4.1* Closure of Storage Tanks. Aboveground tanks taken out of service or abandoned shall be emptied of liquid, rendered vapor-free, and safeguarded against trespassing.

2.6.4.2 Reuse of Aboveground Storage Tanks. Only those used tanks that comply with the applicable sections of this code and are approved by the authority having jurisdiction shall be installed for flammable or combustible liquids service.

2.6.5 Temporary or Permanent Removal from Service of Underground Tanks.

2.6.5.1 General. The procedures outlined in this subsection shall be followed when taking underground tanks temporarily out of service, closing them in place permanently, or removing them. All applicable safety procedures associated with working in proximity to flammable and combustible materials shall be strictly adhered to. (*See Appendix C for additional information.*)

2.6.5.2 Temporary Closure. Tanks shall be rendered temporarily out of service only when it is planned that they will be returned to active service, closed in place permanently, or removed within a reasonable period not exceeding 1 year. The following requirements shall be met:

- (1) Corrosion protection and release detection systems shall be maintained in operation.
- (2) The vent line shall be left open and functioning.
- (3) The tank shall be secured against tampering.
- (4) All other lines shall be capped or plugged.

Tanks remaining temporarily out of service for more than 1 year shall be permanently closed in place or removed in accordance with 2.6.5.3 or 2.6.5.4, as applicable.

2.6.5.3 Permanent Closure in Place. Tanks shall be permitted to be permanently closed in place if approved by the authority having jurisdiction. All of the following requirements shall be met:

(a) All applicable authorities having jurisdiction shall be notified.

(b)*A safe workplace shall be maintained throughout the prescribed activities.

(c) All flammable and combustible liquids and residues shall be removed from the tank, appurtenances, and piping and shall be properly disposed of.

(d) The tank shall be made safe by either purging it of flammable vapors or inerting the potential explosive atmosphere in the tank. Confirmation that the atmosphere in the tank is safe shall be by periodic testing of the atmosphere using a combustible gas indicator, if purging, or an oxygen meter, if inerting.

(e) Access to the tank shall be made by careful excavation to the top of the tank.

(f) All exposed piping, gauging and tank fixtures, and other appurtenances, except the vent, shall be disconnected and removed.

(g) The tank shall be completely filled with an inert solid material.

(h) The tank vent and remaining underground piping shall be capped or removed.

(i) The tank excavation shall be backfilled.

2.6.5.4 Removal and Disposal. Underground tanks shall be removed in accordance with the following requirements:

- (1) The steps described in 2.6.5.3(a) through (e) shall be followed.
- (2) All exposed piping, gauging and tank fixtures, and other appurtenances, including the vent, shall be disconnected and removed.
- (3) All openings shall be plugged, leaving a $\frac{1}{4}$ -in. (8-mm) opening to avoid buildup of pressure in the tank.
- (4) The tank shall be removed from the excavated site and shall be secured against movement.
- (5) Any corrosion holes shall be plugged.
- (6) The tank shall be labeled with its former contents, present vapor state, vapor-freeing method, and a warning against reuse.
- (7) The tank shall be removed from the site promptly, preferably the same day.

2.6.5.5 Temporary Storage of Removed Tanks. If it is necessary to temporarily store a tank that has been removed, it shall be placed in a secure area where public access is restricted. A $\frac{1}{4}$ -in. (8-mm) opening shall be maintained to avoid buildup of pressure in the tank.

2.6.5.6 Disposal of Tanks. Disposal of tanks shall meet the following requirements:

- (1) Before a tank is cut up for scrap or landfill, the atmosphere in the tank shall be tested in accordance with 2.6.5.3(d) to ensure that it is safe.
- (2) The tank shall be made unfit for further use by cutting holes in the tank heads and shell.

2.6.5.7 Documentation. All necessary documentation shall be prepared and maintained in accordance with all federal, state, and local rules and regulations.

2.6.5.8 Reuse of Underground Tanks. Only those used tanks that comply with the applicable sections of this code and are approved by the authority having jurisdiction shall be installed for flammable or combustible liquids service.

2.6.5.9 Change of Service of Underground Tanks. Tanks that undergo any change of stored product shall meet the requirements of Section 2.2.

2.6.6* Leak Detection and Inventory Records for Underground Tanks. Accurate inventory records or a leak detection program shall be maintained on all Class I liquid storage tanks for indication of possible leakage from the tanks or associated piping.

2.6.7 Tank Maintenance.

2.6.7.1 Each tank shall be maintained liquidtight. Each tank that is leaking shall be emptied of liquid or repaired in a manner acceptable to the authority having jurisdiction.

2.6.7.2 Tanks that have been structurally damaged, have been repaired or reconstructed, or are suspected of leaking shall be tested in accordance with 2.4.1 or in a manner acceptable to the authority having jurisdiction.

2.6.7.3* Tanks and all tank appurtenances, including normal vents and emergency vents and related devices, shall be properly maintained to ensure that they function as intended.

2.6.7.4 Openings for gauging on tanks storing Class I liquids shall be provided with a vaportight cap or cover. Such covers shall be closed when not gauging.

Chapter 3 Piping Systems

3.1 Scope.

3.1.1 This chapter shall apply to piping systems consisting of pipe, tubing, flanges, bolting, gaskets, valves, fittings, flexible connectors, the pressure-containing parts of other components such as expansion joints and strainers, and devices that serve such purposes as mixing, separating, snubbing, distributing, metering, controlling flow, or secondary containment of liquids and associated vapors.

3.1.2 This chapter shall not apply to any of the following:

- (1) Tubing or casing on any oil or gas wells and any piping connected directly thereto
- (2) Motor vehicles, aircraft, boats, or piping that are integral to a stationary engine assembly
- (3) Piping within the scope of any applicable boiler and pressure vessel code

3.2 General Requirements.

3.2.1 Performance Standards. The design, fabrication, assembly, test, and inspection of piping systems shall be suitable for the expected working pressures and structural stresses. Compliance with applicable sections of ASME B31, *Code for Pressure Piping*, and the provisions of this chapter shall be considered prima facie evidence of compliance with the foregoing provisions.

3.2.2 Tightness of Piping. Piping systems shall be maintained liquidtight. A piping system that has leaks that constitute a hazard shall be emptied of liquid or repaired in a manner acceptable to the authority having jurisdiction.

3.3 Materials for Piping Systems.

3.3.1 Material Specifications. Pipe, valves, faucets, couplings, flexible connectors, fittings, and other pressure-containing parts shall meet the material specifications and pressure and temperature limitations of ASME B31, *Code for Pressure Piping*, except as provided for in 3.3.2, 3.3.3, and 3.3.4.

3.3.2 Ductile Iron. Ductile (nodular) iron shall meet the specifications of ASTM A 395, *Ferritic Ductile Iron Pressure-Retaining Castings for Use at Elevated Temperatures*.

3.3.3 Materials of Construction of Valves. Valves at storage tanks, as required by 2.3.2.5.1 and 2.3.4.7.3, and their connections to the tank shall be of steel or ductile iron, except as provided for in 3.3.3.1, 3.3.3.2, or 3.3.4.

3.3.3.1 Valves at storage tanks shall be permitted to be other than steel or ductile iron where the chemical characteristics of the liquid stored are not compatible with steel or where the valves are installed internally to the tank. Valves installed externally to the tank shall be permitted to be other than steel or ductile iron if the material of construction has a ductility and melting point comparable to steel or ductile iron and is capable of withstanding the stresses and temperatures involved in fire exposure or the valves are otherwise protected from fire exposures, such as by materials having a fire resistance rating of not less than 2 hours.

3.3.3.2 Cast iron, brass, copper, aluminum, malleable iron, and similar materials shall be permitted to be used on tanks described in 2.3.2.2.1 or on tanks storing Class IIIB liquids where the tanks are located outdoors and not within a diked area or drainage path of a tank storing a Class I, Class II, or Class IIIA liquid.

3.3.4 Low Melting Point Materials. Low melting point materials such as aluminum, copper, and brass; materials that soften on fire exposure such as plastics; or nonductile material such as cast iron shall be permitted to be used underground within the pressure and temperature limitations of ASME B31, *Code for Pressure Piping*. Such materials shall be permitted to be used outdoors above ground or inside buildings provided that they are as follows:

- (1) Resistant to damage by fire
- (2) Located so that any leakage resulting from failure will not unduly expose persons, important buildings, or structures
- (3) Located where leakage can readily be controlled by operation of one or more accessible remotely located valves

The piping materials chosen shall be compatible with the liquids being handled. Piping systems of these materials shall be designed and built in accordance with recognized standards of design for the particular materials chosen or with acceptable equivalent standards or shall be listed.

3.3.5 Lining Materials. Piping, valves, and fittings shall be permitted to have combustible or noncombustible linings.

3.3.6 Nonmetallic Piping. Piping systems of nonmetallic materials, including piping systems incorporating secondary containment, shall be designed and built in accordance with recognized standards of design or approved equivalents and shall be installed in accordance with 3.3.4. Nonmetallic piping shall be built and used within the scope of their approvals or within the scope of UL 971, *Standard for Nonmetallic Underground Piping for Flammable Liquids*. Nonmetallic piping systems and components shall be installed in accordance with manufacturers' instructions.

3.4 Pipe Joints.

3.4.1 Tightness of Pipe Joints. Joints shall be made liquidtight and shall be welded, flanged, threaded, or mechanically attached. They shall be designed and installed so that the mechanical strength of the joint will not be impaired if exposed to a fire. Listed flexible connectors shall be permitted to be used where installed in accordance with 3.4.2. Threaded joints shall be made with a suitable thread sealant or lubricant. Joints in piping systems handling Class I liquids shall be welded when located in concealed spaces within buildings.

3.4.2 Flexible Connectors. Listed flexible connectors shall be permitted to be used where installed in accordance with 3.4.3.

3.4.3 Friction Joints. Pipe joints dependent upon the friction characteristics or resiliency of combustible materials for mechanical continuity or liquidtightness of piping shall only be used outside of buildings above ground or below ground. Where used above ground, either the piping shall be secured to prevent disengagement at the fitting, or the piping system shall be so designed that any spill resulting from disengagement could not unduly expose persons, important buildings, or structures and could be readily controlled by remote valves.

Exception: Pipe joints that depend on friction characteristics of their components shall be permitted to be used inside buildings provided both of the following are met:

- (a) They are located where leakage can be readily controlled by operation of an accessible remotely located valve that is outside the fire risk area.
- (b) The mechanical strength and liquidtightness of the joint is not dependent on the resiliency of a combustible material or component.

3.5 Installation of Piping Systems.

3.5.1 General. Piping systems shall be substantially supported and protected against physical damage and excessive stresses arising from settlement, vibration, expansion, or contraction. The installation of nonmetallic piping shall be in accordance with the manufacturer's instructions.

3.5.2* Load-Bearing Supports. Load-bearing piping supports that are located in areas with a high fire exposure risk shall be protected by one or more of the following:

- (1) Drainage to a safe location to prevent liquid from accumulating under pipeways
- (2) Fire-resistive construction
- (3) Fire-resistant protective coatings or systems
- (4) Water spray systems designed and installed in accordance with NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*
- (5) Other alternate means acceptable to the authority having jurisdiction

3.5.3 Pipe Penetrations. Piping that passes through or pierces a dike wall or the wall of a structure shall be designed to prevent excessive stresses and leakage due to settlement or fire exposure.

3.5.4* Protection Against Corrosion. Aboveground piping systems that are subject to external corrosion shall be suitably protected. Underground piping systems shall be protected against corrosion in accordance with 2.2.6.

3.5.5 Underground Piping.

3.5.5.1 Underground piping shall be installed on a bedding of at least 6 in. (150 mm) of well-compacted backfill material.

3.5.5.2 In areas subject to vehicle traffic, the pipe trench shall be of sufficient depth to permit a cover of at least 18 in. (450 mm) of well-compacted backfill material and pavement. In paved areas where a minimum 2 in. (50 mm) of asphalt is used, backfill between the pipe and the asphalt can be reduced to 8 in. (200 mm) minimum. In paved areas where a minimum 4 in. (100 mm) of reinforced concrete is used, backfill between the pipe and the concrete can be reduced to 4 in. (100 mm) minimum.

3.5.5.3 In areas not subject to vehicle traffic, the pipe trench shall be of sufficient depth to permit a cover of at least 6 in. (150 mm) of well-compacted backfill material. A greater burial depth shall be provided when required by the manufacturer's instructions or where frost conditions are present.

Piping within the same trench shall be separated by two pipe diameters.

3.5.5.4 Piping shall not need to be separated horizontally by more than 9 in. (230 mm).

3.5.5.5 Two or more levels of pipes within the same trench shall be separated vertically by a minimum 6 in. (150 mm) of well-compacted backfill.

3.5.6 Valves. Piping systems shall contain a sufficient number of valves to operate the system properly and to protect the equipment. Piping systems in connection with pumps shall contain a sufficient number of valves to properly control the flow of liquid both in normal operation and in the event of physical damage. Each connection to a piping system by which equipment such as tank cars, tank vehicles, or marine vessels discharges liquids into storage tanks shall be provided with a check valve for automatic protection against back-flow if the piping arrangement is such that back-flow from the system is possible. (*See also 2.3.2.5.1.*)

3.5.7 Common Loading and Unloading Piping. If loading and unloading is done through a common pipe system, a check valve shall not be required. However, an isolation valve shall be provided. This valve shall be located so that it is readily accessible or shall be remotely operable.

3.6 Testing.

3.6.1 Initial Testing. Unless tested in accordance with the applicable sections of ASME B31, *Code for Pressure Piping*, all piping shall be tested before being covered, enclosed, or placed in use. Testing shall be done hydrostatically to 150 percent of the maximum anticipated pressure of the system or pneumatically to 110 percent of the maximum anticipated pressure of the system, and the test pressure shall be maintained for a sufficient time to conduct a complete visual inspection of all joints and connections. In no case shall the test pressure be less than 5 psig (gauge pressure of 34.5 kPa) measured at the highest point of the system, and in no case shall the test pressure be maintained for less than 10 minutes.

3.6.2 Initial Testing of Secondary Containment Piping. The interstitial (annular) space of secondary containment-type piping shall be tested hydrostatically or with air pressure at 5 psig (gauge pressure of 34.5 kPa) or shall be tested in accordance with its listing or with the manufacturer's instructions. The pressure source shall be disconnected from the interstitial space to ensure that the test is being conducted on a closed system. The pressure shall be maintained for a minimum of 1 hour.

3.6.3 Testing During Maintenance. Existing piping shall be tested in accordance with this subsection if there is indication that the piping is leaking. Piping that could contain a Class I, Class II, or Class IIIA liquid or vapor shall not be tested using air.

3.7 Vent Piping. Vent piping shall be designed, constructed, and installed in accordance with this section.

3.7.1 Vent Piping for Aboveground Tanks.

3.7.1.1 Where the outlets of vent pipes for tanks storing Class I liquids are adjacent to buildings or public ways, they shall be located so that vapors are released at a safe point outside of buildings and not less than 12 ft (3.6 m) above the adjacent ground level. Vapors shall be discharged upward or horizontally away from adjacent walls. Vent outlets shall be located so that vapors will not be trapped by eaves or other obstructions and shall be at least 5 ft (1.5 m) from building openings.

3.7.1.2 Manifolding of vent piping shall be avoided except where required for special purposes such as vapor recovery, vapor conservation, or air pollution control. Where vent piping is manifolded, pipe sizes shall be capable of discharging, within the pressure limitations of the system, the vapors they

are required to handle when all manifolded tanks are subject to the same fire exposure.

3.7.1.3 Vent piping for tanks storing Class I liquids shall not be manifolded with vent piping for tanks storing Class II or Class III liquids unless positive means are provided to prevent the following:

- (1) Vapors of Class I liquids from entering tanks storing Class II or Class III liquids
- (2) Contamination (*see A.1.2*)
- (3) Possible change in classification of the less volatile liquid

3.7.1.4* Extension of Emergency Vent Piping. Piping to or from approved emergency vent devices for atmospheric and low-pressure tanks shall be sized to provide emergency vent flows that limit the back pressure to less than the maximum pressure permitted by the design of the tank. Piping to or from approved emergency vent devices for pressure vessels shall be sized in accordance with the ASME *Boiler and Pressure Vessel Code*.

3.7.2 Vent Piping for Underground Tanks.

3.7.2.1 Vent pipes from underground tanks storing Class I liquids shall be located so that the discharge point is outside of buildings, higher than the fill pipe opening, and not less than 12 ft (3.6 m) above the adjacent ground level. Vent pipe outlets shall be located and directed so that vapors will not accumulate or travel to an unsafe location, enter building openings, or be trapped under eaves, and shall be at least 5 ft (1.5 m) from building openings and at least 15 ft (4.5 m) from powered ventilation air intake devices.

3.7.2.2 Vent pipes shall not be obstructed by devices provided for vapor recovery or other purposes unless the tank and associated piping and equipment are otherwise protected to limit back-pressure development to less than the maximum working pressure of the tank and equipment by the provision of pressure-vacuum vents, rupture discs, or other tank-venting devices installed in the tank vent lines. Vent outlets and devices shall be protected to minimize the possibility of blockage from weather, dirt, or insect nests.

3.7.2.3 Vent piping shall be sized in accordance with 2.2.5.3.

3.7.2.4 Vent pipes from tanks storing Class II or Class IIIA liquids shall terminate outside of the building and higher than the fill pipe opening. Vent outlets shall be above normal snow level. They shall be permitted to be fitted with return bends, coarse screens, or other devices to minimize ingress of foreign material.

3.7.2.5 Vent pipes and vapor return piping shall be installed without sags or traps in which liquid can collect. Condensate tanks, if utilized, shall be installed and maintained so that blocking of the vapor return piping by liquid is prevented. Vent pipes and condensate tanks shall be located so that they will not be subjected to physical damage. The tank end of the vent pipe shall enter the tank through the top.

3.7.2.6 Where tank vent piping is manifolded, pipe sizes shall be such as to discharge, within the pressure limitations of the system, the vapors they can be required to handle when manifolded tanks are filled simultaneously. Float-type check valves installed in tank openings connected to manifolded vent piping to prevent product contamination shall be permitted to be used provided that the tank pressure will not exceed that permitted by 2.3.3.2.3 when the valves close.

3.7.2.7 Vent piping for tanks storing Class I liquids shall not be manifolded with vent piping for tanks storing Class II or Class III liquids unless positive means are provided to prevent the following:

- (1) Vapors of Class I liquids from entering tanks storing Class II or Class III liquids
- (2) Contamination (*see A.1.2*)
- (3) Possible change in classification of the less volatile liquid

3.8 Static Electricity. Piping systems shall be bonded and grounded in accordance with 2.5.3.4.

3.9* Identification. Each loading and unloading riser shall be marked to identify the product for which it is to be used.

Chapter 4 Container and Portable Tank Storage

4.1 General.

4.1.1* Scope.

4.1.1.1 This chapter shall apply to the storage of liquids in drums or other containers that do not exceed 60 gal (227 L) individual capacity, in portable tanks that do not exceed 660 gal (2498 L) individual capacity, and in intermediate bulk containers that do not exceed 793 gal (3000 L) and to limited transfers incidental thereto. For portable tanks that exceed 660 gal (2500 L), Chapter 2 shall apply.

This chapter shall also apply to overpack drums that do not exceed 85 gal (322 L) capacity when used for temporary containment of containers that do not exceed 60 gal (227 L) capacity. Such overpack containers shall be treated as containers as defined in Section 1.6.

4.1.1.2 This chapter shall not apply to the following:

- (1) Containers, intermediate bulk containers, and portable tanks that are used in process areas, as covered by Chapter 5
- (2) Liquids in the fuel tanks of motor vehicles, aircraft, boats, or portable or stationary engines
- (3) Beverages, where packaged in individual containers that do not exceed 1.3 gal (5 L) capacity
- (4) Medicines, foodstuffs, cosmetics, and other consumer products that contain not more than 50 percent by volume of water-miscible liquids, with the remainder of the solution not being flammable where packaged in individual containers that do not exceed 1.3 gal (5 L) capacity
- (5) Liquids that have no fire point when tested by ASTM D 92, *Standard Test Method for Flash and Fire Points by Cleveland Open Cup*, up to the boiling point of the liquid or up to a temperature at which the sample being tested shows an obvious physical change
- (6) Liquids with a flash point greater than 95°F (35°C) in a water-miscible solution or dispersion with a water and inert (noncombustible) solids content of more than 80 percent by weight, which do not sustain combustion when tested using the "Method of Testing for Sustained Combustibility," per 49 *CFR* 173, Appendix H, or the UN *Recommendations on the Transport of Dangerous Goods*
- (7) Distilled spirits and wines in wooden barrels or casks

4.1.2 General Provision.

4.1.2.1 For the purpose of this chapter, unstable liquids shall be treated as Class IA liquids.

4.1.2.2 For the purposes of this chapter, protected storage installed after January 1, 1997, shall mean storage installed after January 1, 1997, that is protected in accordance with Section 4.8. All other storage shall be considered to be unprotected storage unless an alternate means of protection has been approved by the authority having jurisdiction. (*See 4.8.2.3 and 4.8.3.*)

Exception: As provided for in Section 4.5.

4.2 Design, Construction, and Capacity of Containers.

4.2.1 Only the following approved containers, intermediate bulk containers, and portable tanks shall be used:

(a) Metal containers, metal intermediate bulk containers, and metal portable tanks meeting the requirements of, and containing products authorized by, Chapter I, 49 *CFR* (U.S. Department of Transportation Hazardous Materials Regulations), Chapter 6 of the United Nations *Recommendations on the Transport of Dangerous Goods*, shall be acceptable.

(b) Plastic containers meeting the requirements of, and used for petroleum products within the scope of, one or more of the following specifications shall be acceptable:

- (1) ASTM F 852, *Standard for Portable Gasoline Containers for Consumer Use*
- (2) ASTM F 976, *Standard for Portable Kerosene Containers for Consumer Use*
- (3) ANSI/UL 1313, *Nonmetallic Safety Cans for Petroleum Products*

(c) Plastic containers meeting the requirements of and containing products authorized by 49 *CFR* or by Chapter 6 of the United Nations *Recommendations on the Transport of Dangerous Goods* shall be acceptable.

(d) Fiber drums that meet the following shall be acceptable:

- (1) Requirements of Item 296 of the National Motor Freight Classification (NMFC) or Rule 51 of the Uniform Freight Classification (UFC) for Types 2A, 3A, 3B-H, 3B-L, or 4A
- (2) Requirements of and contain liquid products authorized either by Chapter I, 49 *CFR* (U.S. Department of Transportation Hazardous Materials Regulations) or by U.S. Department of Transportation exemption

(e)*Rigid nonmetallic intermediate bulk containers that meet the requirements of and contain products authorized by 49 *CFR* or Chapter 6 of the United Nations *Recommendations on the Transport of Dangerous Goods* for Classes 31H1, 31H2, and 31HZ1 shall be acceptable. For protected storage, rigid nonmetallic intermediate bulk containers shall be subjected to a standard fire test that demonstrates acceptable inside storage fire performance and shall be listed and labeled.

4.2.2 Each portable tank or intermediate bulk container shall be provided with one or more devices installed in the top with sufficient emergency venting capacity to limit internal pressure under fire exposure conditions to 10 psig (gauge pressure of 68.9 kPa) or 30 percent of the bursting pressure of the portable tank, whichever is greater. The total venting capacity shall be not less than that specified in 2.2.5.2.3 or 2.2.5.2.5. At least one pressure-actuated vent having a minimum capacity of 6000 ft³ (170 m³) of free air per hour [14.7 psia (760 mm Hg) and 60°F (15.6°C)] shall be used. It shall be set to open at not less than 5 psig (gauge pressure of 34.5 kPa). If fusible vents are used, they shall be actuated by elements that operate at a temperature not exceeding 300°F (148.9°C). Where plugging of a pressure-actuated vent can occur, such as when used for paints, drying oils, and similar materials, fusible plugs or vent-

ing devices that soften to failure at a maximum of 300°F (148.9°C) under fire exposure shall be permitted to be used for the entire emergency venting requirement.

4.2.3 The maximum allowable size of a container or metal portable tank shall not exceed that specified in Table 4.2.3.

Exception: As provided for in 4.1.1, 4.2.3.1, 4.2.3.2, and 4.2.3.3.

4.2.3.1 Medicines, beverages, foodstuffs, cosmetics, and other common consumer products, where packaged according to commonly accepted practices for retail sales, shall be exempt from the requirements of 4.2.1 and 4.2.3.

4.2.3.2 Class IA and Class IB liquids shall be permitted to be stored in glass containers of not more than 1 gal (3.8 L) capacity, if the required liquid purity (such as ACS analytical reagent grade or higher) would be affected by storage in metal containers or if the liquid can cause excessive corrosion of the metal container.

4.2.3.3 Leaking or damaged containers up to 60 gal (227 L) capacity shall be permitted to be stored temporarily in accordance with this chapter, provided they are enclosed in overpack containers that do not exceed 85 gal (322 L) capacity. To

be considered protected in accordance with Section 4.8, the overpack container shall be constructed of the same material as the leaking or damaged container. Metal overpack containers shall be considered nonrelieving containers.

4.3 Design, Construction, and Capacity of Storage Cabinets.

4.3.1 Not more than 120 gal (454 L) of Class I, Class II, and Class IIIA liquids shall be stored in a storage cabinet.

4.3.2 Not more than three storage cabinets shall be located in any one fire area.

Exception No. 1: In an industrial occupancy, additional storage cabinets shall be permitted to be located in the same fire area, if a minimum separation of 100 ft (30 m) is maintained between each group of not more than three cabinets.

Exception No. 2: In an industrial occupancy that is protected by an automatic sprinkler system that is designed and installed in accordance with NFPA 13, Standard for the Installation of Sprinkler Systems, the number of cabinets in any one group shall be permitted to be increased to six.

Table 4.2.3 Maximum Allowable Size—Containers, Intermediate Bulk Containers, and Portable Tanks

Type	Flammable Liquids			Combustible Liquids	
	Class IA	Class IB	Class IC	Class II	Class III
Glass	1 pt	1 qt	1 gal	1 gal	5 gal
Metal (other than DOT drums) or approved plastic	1 gal	5 gal	5 gal	5 gal	5 gal
Safety cans	2 gal	5 gal	5 gal	5 gal	5 gal
Metal drum (DOT Specification)	60 gal	60 gal	60 gal	60 gal	60 gal
Approved metal portable tanks and IBCs	793 gal	793 gal	793 gal	793 gal	793 gal
Rigid plastic IBCs (UN 31H1 or 31H2) and composite IBCs (UN 31HZ1)	NP	NP	NP	793 gal	793 gal
Polyethylene DOT Specification 34, UN 1H1, or as authorized by DOT exemption	1 gal	5 gal*	5 gal*	60 gal	60 gal
Fiber drum NMFC or UFC Type 2A; Types 3A, 3B-H, or 3B-L; or Type 4A	NP	NP	NP	60 gal	60 gal

For SI units, 1 pt = 0.473 L; 1 qt = 0.95 L; 1 gal = 3.8 L.

NP — Not permitted.

*For Class IB and IC water-miscible liquids, the maximum allowable size of plastic container is 60 gal (227 L), if stored and protected in accordance with Table 4.8.2(g).

4.3.3 Storage cabinets that meet at least one of the following sets of requirements shall be acceptable for storage of liquids:

(a) Storage cabinets that are designed and constructed to limit the internal temperature at the center of the cabinet and 1 in. (25 mm) from the top of the cabinet to not more than 325°F (162.8°C), when subjected to a 10-minute fire test that simulates the fire exposure of the standard time-temperature curve specified in NFPA 251, *Standard Methods of Tests of Fire Endurance of Building Construction and Materials*, shall be acceptable. All joints and seams shall remain tight and the door shall remain securely closed during the test.

(b) Metal storage cabinets that are constructed in the following manner shall be acceptable. The bottom, top, door, and sides of the cabinet shall be at least No. 18 gauge sheet steel and shall be double-walled, with 1½ in. (38 mm) air space. Joints shall be riveted, welded, or made tight by some equally effective means. The door shall be provided with a three-point latch arrangement, and the door sill shall be raised at least 2 in. (50 mm) above the bottom of the cabinet to retain spilled liquid within the cabinet.

(c) Wooden cabinets constructed in the following manner shall be acceptable. The bottom, sides, and top shall be constructed of exterior grade plywood that is at least 1 in. (25 mm) thick and of a type that will not break down or delaminate under fire conditions. All joints shall be rabbetted and shall be fastened in two directions with wood screws. Where more than one door is used, there shall be a rabbetted overlap of not less than 1 in. (25 mm). Doors shall be equipped with a means of latching and hinges shall be constructed and mounted in such a manner as to not lose their holding capacity when subjected to fire exposure. A raised sill or pan capable of containing a 2 in. (50 mm) depth of liquid shall be provided at the bottom of the cabinet to retain spilled liquid within the cabinet.

(d) Listed storage cabinets that have been constructed and tested in accordance with 4.3.3(a) shall be acceptable.

4.3.4* The storage cabinet shall not be required by this code to be vented for fire protection purposes, and vent openings shall be sealed with the bungs supplied with the cabinet or with bungs specified by the cabinet manufacturer. However, if the storage cabinet is vented for any reason, the cabinet shall be vented directly to outdoors in such a manner that will not compromise the specified performance of the cabinet and in a manner that is acceptable to the authority having jurisdiction.

4.3.5 Storage cabinets shall be marked in conspicuous lettering:

FLAMMABLE — KEEP FIRE AWAY.

4.4* Design, Construction, and Operation of Inside Liquid Storage Areas.

4.4.1 Scope. Section 4.4 shall apply to inside areas where the primary function is the storage of liquids. This shall include inside rooms, cutoff rooms, attached buildings, liquid warehouses, and hazardous material storage lockers that are used as inside storage areas. (See Section 4.5 for storage of liquids in other types of occupancies.)

4.4.2 Design and Construction Requirements.

4.4.2.1 All storage areas shall be constructed to meet the specified fire resistance ratings in Table 4.4.2.1. Such construction shall comply with the test specifications given in NFPA 251, *Standard Methods of Tests of Fire Endurance of Building Construction and Materials*.

Table 4.4.2.1 Fire Resistance Ratings for Inside Liquid Storage Areas

Type of Storage Area	Fire Resistance Rating (hr)		
	Interior Walls, ^a Ceilings, Intermediate Floors	Roofs	Exterior Walls
Inside Rooms			
Floor area <150 ft ²	1	—	—
Floor area >150 ft ² and <500 ft ²	2	—	—
Cutoff Rooms and Attached Buildings			
Floor area <300 ft ²	1	1 ^b	—
Floor area >300 ft ²	2	2 ^b	2 ^c
Liquid Warehouses ^{d,e}	4 ^f	—	2 ^g or 4 ^h

For SI units, 1 ft² = 0.09 m².

^aBetween liquid storage areas and any adjacent areas not dedicated to liquid storage.

^bRoofs of attached buildings, one story in height, shall be permitted to be of lightweight, noncombustible construction if the separating interior walls have minimum 3-ft (0.90-m) parapets.

^cWhere other portions of buildings or other properties are exposed.

^dFire resistance ratings for liquid warehouses storing only Class IIIB liquids, which are not heated above their flash point, shall be permitted to be reduced to 2 hours.

^eFire resistance ratings for liquid warehouses protected in accordance with 4.8.2 shall be permitted to be reduced to 2 hours.

^fThis shall be a fire wall as defined in NFPA 221, *Standard for Fire Walls and Fire Barrier Walls*.

^gFor exposing walls that are located more than 10 ft (3 m) but less than 50 ft (15 m) from an important building or line of adjoining property that can be built upon.

^hFor exposing walls that are located 10 ft (3 m) or less from an important building or line of adjoining property that can be built upon.

4.4.2.2 Openings in interior walls to adjacent rooms or buildings and openings in exterior walls with fire resistance ratings shall be provided with normally closed, listed fire doors with fire protection ratings corresponding to the fire resistance rating of the wall as specified in Table 4.4.2.2. Such doors shall be permitted to be arranged to stay open during material handling operations if the doors are designed to close automatically in a fire emergency by provision of listed closure devices. Fire doors shall be installed in accordance with NFPA 80, *Standard for Fire Doors and Fire Windows*.

Table 4.4.2.2 Fire Protection Ratings for Fire Doors

Fire Resistance Rating of Wall ^a (hr)	Fire Protection Rating of Door (hr)
1	³ / ₄
2	1 ¹ / ₂
4	3 ^b

^aAs required by Table 4.4.2.1.

^bOne fire door required on each side of interior openings for attached liquid warehouses.

4.4.2.3 Construction design of exterior walls shall provide ready accessibility for fire-fighting operations through provision of access openings, windows, or lightweight noncombustible wall panels.

Exception: This shall not apply to inside rooms.

4.4.2.4* Where Class IA or unstable liquids are dispensed or stored in containers larger than 1 gal (4 L), the exterior wall or roof construction shall incorporate deflagration venting.

Exception: This does not apply to inside rooms.

4.4.2.5* Curbs, scuppers, special drains, or other suitable means shall be provided to prevent the flow of liquids under emergency conditions into adjacent building areas. If a drainage system is used, it shall have sufficient capacity to carry the expected discharge of water from fire protection systems and hose streams.

Exception No. 1: Where none of the containers stored in a storage area exceed 10 gal (38 L), the storage area need not meet this requirement.

Exception No. 2: Where only Class IIIB liquids are stored in a storage area, regardless of container size, the storage area need not meet this requirement.

4.4.2.6 In inside storage rooms, electrical wiring and utilization equipment for Class I liquid storage shall be Class I, Division 2, and electrical wiring and utilization equipment in inside storage rooms used for the storage of Class II and Class III liquids shall be suitable for general purpose.

Installation of electrical wiring and utilization equipment shall meet the requirements of Chapter 6.

Exception: Class I, Division 2 requirements shall apply to Class II and III liquids when stored at temperatures above their flash points.

4.4.2.7 Liquid storage areas where dispensing is conducted shall be provided with either a gravity or a continuous mechanical exhaust ventilation system. Mechanical ventilation shall be used if Class I liquids are dispensed within the room.

4.4.2.7.1 Exhaust air shall be taken from a point near a wall on one side of the room and within 12 in. (300 mm) of the floor with one or more make-up inlets located on the opposite side of the room within 12 in. (300 mm) of the floor. The location of both the exhaust and inlet air openings shall be arranged to provide, as far as practicable, air movements across all portions of the floor to prevent accumulation of flammable vapors. Exhaust from the room shall be directly to the exterior of the building without recirculation.

Exception: Recirculation is permitted where it is monitored continuously using a fail-safe system that is designed to automatically sound

an alarm, stop recirculation, and provide full exhaust to the outside in the event that vapor-air mixtures in concentrations over one-fourth of the lower flammable limit are detected.

If ducts are used, they shall not be used for any other purpose and shall comply with NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Noncombustible Particulate Solids*. If make-up air to a mechanical system is taken from within the building, the opening shall be equipped with a fire door or damper, as required in NFPA 91. For gravity systems, the make-up air shall be supplied from outside the building.

4.4.2.7.2 Mechanical ventilation systems shall provide at least 1 ft³/min of exhaust/ft² (1 m³/min/3 m²) of floor area, but not less than 150 cfm (4 m³/min). The mechanical ventilation system for dispensing areas shall be equipped with an airflow switch or other equally reliable method that is interlocked to sound an audible alarm upon failure of the ventilation system.

4.4.3 General Storage Requirements.

4.4.3.1 The storage of any liquids shall not physically obstruct means of egress.

4.4.3.2 Wood at least 1 in. (25 mm) nominal thickness shall be permitted to be used for shelving, racks, dunnage, scuffboards, floor overlay, and similar installations.

4.4.3.3 Where storage on racks exists as permitted in this code, a minimum 4 ft (1.2 m) wide aisle shall be provided between adjacent rack sections and any adjacent storage of liquids. Main aisles shall be a minimum of 8 ft (2.4 m) wide.

4.4.3.4 Solid pile and palletized storage in liquid warehouses shall be arranged so that piles are separated from each other by at least 4 ft (1.2 m). Aisles shall be provided and so arranged that no container or portable tank is more than 20 ft (6 m) from an aisle. Main aisles shall be a minimum of 8 ft (2.4 m) wide.

Exception: For Class IIIB liquids in containers, the distance between piles shall be permitted to be reduced from 4 ft to 2 ft (1.2 m to 0.6 m) in proportion to commensurate reductions in maximum quantity per pile and maximum storage height, as given in Table 4.4.4.1.

4.4.3.5 Class I liquids shall not be permitted in basement areas. Class II and Class IIIA liquids shall be permitted to be stored in basements provided that automatic sprinkler protection and other fire protection facilities are provided in accordance with Section 4.8.

4.4.3.6 Limited quantities of combustible commodities, as defined in the scope of NFPA 230, *Standard for the Fire Protection of Storage*, shall be permitted to be stored in liquid storage areas if the ordinary combustibles, other than those used for packaging the liquids, are separated from the liquids in storage by a minimum of 8 ft (2.4 m) horizontally, either by aisles or by open racks, and if protection is provided in accordance with Section 4.8.

4.4.3.7 Storage of empty or idle combustible pallets inside an unprotected liquid storage area shall be limited to a maximum pile size of 2500 ft² (232 m²) and to a maximum storage height of 6 ft (1.8 m). Storage of empty or idle combustible pallets inside a protected liquid storage area shall comply with NFPA 230, *Standard for the Fire Protection of Storage*. Pallet storage shall be separated from liquid storage by aisles that are at least 8 ft (2.4 m) wide.

Table 4.4.4.1 Indoor Unprotected Storage of Liquids in Containers, Portable Tanks, and Intermediate Bulk Containers

Class	Container Storage			Portable Tank/Metallic IBC Storage			Rigid Plastic and Composite IBCs		
	Maximum Pile Height (ft)	Maximum Quantity per Pile (gal)	Maximum Total Quantity (gal)*	Pile Maximum Height (ft)	Maximum Quantity per Pile (gal)	Maximum Total Quantity (gal)*	Maximum Pile Height (ft)	Maximum Quantity per Pile (gal)	Maximum Total Quantity (gal)*
IA	5	660	660	—	NP	—	—	—	—
IB	5	1,375	1,375	7	2,000	2,000	—	—	—
IC	5	2,750	2,750	7	4,000	4,000	—	—	—
II	10	4,125	8,250	7	5,500	11,000	7	4,125	8,250
IIIA	15	13,750	27,500	7	22,000	44,000	7	13,750	27,500
IIIB	15	13,750	55,000	7	22,000	88,000	7	13,750	55,000

For SI units, 1 ft = 0.3 m; 1 gal = 3.8 L.

NP — Not permitted.

*Applies only to cut-off rooms and attached buildings, not to liquid warehouses.

4.4.3.8 Containers in piles shall be stacked in such a manner as to provide stability and to prevent excessive stress on container walls. Portable tanks stored over one tier high shall be designed to nest securely, without dunnage. Materials handling equipment shall be suitable to handle containers and tanks safely at the upper tier level.

4.4.3.9 Containers or portable tanks in unprotected liquid storage areas shall not be stored closer than 36 in. (0.9 m) to the nearest beam, chord, girder, or other roof member.

4.4.4 Allowable Quantities and Storage Heights.

4.4.4.1 Except as provided for in 4.4.3.4 and in 4.4.4.2 through 4.4.4.4, indoor unprotected liquid storage shall comply with Table 4.4.4.1. Where storage of liquids is protected, the protection shall meet the protection requirements of Section 4.8.

*Exception:** Other quantities and arrangements of storage shall be permitted to be used where the storage is suitably protected and approved by the authority having jurisdiction.

4.4.4.2 Storage in inside rooms shall meet the requirements specified in Table 4.4.4.2. In addition, containers over 30 gal (113.5 L) capacity that contain Class I or Class II liquids shall not be stored more than one container high in inside rooms.

Exception: This requirement shall not apply to inside rooms and hazardous materials storage lockers that are located in a liquid warehouse and are provided with equal or greater fire protection as is provided for the warehouse itself.

4.4.4.3 Unprotected storage of liquids in racks shall not exceed the maximum total quantities allowed by Table 4.4.4.1.

Exception: Liquid warehouses do not need to comply with this requirement.

4.4.4.4 The total quantity of liquids stored in a liquid warehouse shall not be restricted. However, the storage heights and maximum quantity per pile or rack section for unprotected storage shall comply with Table 4.4.4.1.

Table 4.4.4.2 Storage Limitations for Inside Rooms

Total Floor Area (ft²)	Automatic Fire Protection Provided? ^a		Total Allowable Quantity (gal/ft² of floor area)
≤150	No		2
	Yes		5
	No		4 ^b
	Yes		10

For SI units, 1 ft² = 0.09 m²; 1 gal = 3.8 L.

^aThe fire protection system shall be automatic sprinklers, water spray, carbon dioxide, dry chemical, or other approved system. (See Section 4.8.)

^bTotal allowable quantities of Class IA and IB liquids shall not exceed the quantities permitted in Table 4.4.4.1 or those permitted by 4.4.4.4.

Exception: An unprotected liquid warehouse that is located a minimum of 100 ft (30 m) from exposed buildings or any property line that is or can be built upon does not need to comply with 4.4.3.9 and Table 4.4.4.1 if there is protection for exposures. Where protection for exposures is not provided, this minimum distance shall be increased to 200 ft (61 m).

4.4.4.5 Where two or more classes of liquids are stored in a single pile or rack section, the maximum total quantity and the maximum storage height permitted in that pile or rack section shall be the smallest of the individual maximum total quantities and maximum storage heights for the specific classes present, respectively. The maximum total quantity permitted shall be limited to a sum of the proportional amounts that each class of liquid present bears to the maximum total quantity permitted for its respective class. The sum of the proportional amounts shall not exceed 100 percent.

Exception: The maximum total quantities in liquid warehouses shall not be restricted. (See 4.4.4.3.)

4.4.5 Operations.

4.4.5.1 Dispensing of Class I liquids or Class II or Class III liquids at temperatures at or above their flash points shall not be permitted in cutoff rooms or attached buildings that exceed 1000 ft² (93 m²) in floor area or in liquid warehouses unless the dispensing area is suitably cut off from the storage areas in accordance with Table 4.4.2.1 and meets all other requirements of 4.4.2.

4.4.5.2 Dispensing operations shall comply with the applicable requirements of Chapter 5.

4.5 Requirements for Liquid Storage Areas in Other Occupancies.

4.5.1 Scope. Section 4.5 shall apply to areas where the storage of liquids is incidental and not the primary purpose of the area.

Exception: See Chapter 5 for incidental storage of liquids used in processing, blending, and packaging areas, including areas where liquids in containers are staged after filling and prior to further use, warehousing, or shipment.

4.5.1.1 Where inside liquid storage areas are required in other occupancies, they shall meet all applicable requirements of Section 4.4 and all applicable requirements of this section. Where other factors substantially increase or decrease the hazard, the authority having jurisdiction shall be permitted to modify the quantities specified.

4.5.1.2 Storage of liquids shall not physically obstruct a means of egress. Class I liquids shall be so placed that a fire in the liquid storage area would not prevent egress from the area.

4.5.1.3 Liquids used for building maintenance, painting, or other similar infrequent maintenance purposes shall be permitted to be stored temporarily in closed containers outside of storage cabinets or inside liquid storage areas, if limited to an amount that does not exceed a 10-day supply at anticipated rates of use.

4.5.1.4 Class I liquids shall not be stored in basements.

4.5.2 General-Purpose Warehouses.

4.5.2.1 General. General-purpose warehouses storing liquids (see Section 1.6) shall be separate, detached buildings or shall be separated from other occupancies by a 4-hour fire wall as defined in NFPA 221, *Standard for Fire Walls and Fire Barrier Walls*, or, if approved, by a fire partition having a fire resistance rating of not less than 2 hours. Each opening shall be protected as provided for in 4.4.2.2.

Warehousing operations that involve storage of liquids shall be restricted to inside liquid storage areas in accordance with Section 4.4.

Exception: As provided for in 4.5.2.2.

4.5.2.2 Basic Requirements. Class IB and IC liquids in containers of 1 gal (3.8 L) or less capacity, Class II liquids in containers of 5 gal (19 L) or less capacity, and Class III liquids in containers of 60 gal (227 L) or less capacity shall be permitted to be stored in warehouses that handle combustible commodities, as defined in NFPA 230, *Standard for the Fire Protection of Storage*, provided that the storage area is protected with automatic sprinklers in accordance with the provisions of NFPA 230 for 20-ft (6-m) high storage of Class IV commodities and the quantities and height of liquid storage are limited to the following:

- (1) Class IA liquids: not permitted
- (2) Class IB and IC liquids: 660 gal (2498 L), maximum 5 ft (1.5 m) high
- (3) Class II liquid: 1375 gal (5204 L), maximum 5 ft (1.5 m) high
- (4) Class IIIA liquid: 2750 gal (10,409 L), maximum 10 ft (3.0 m) high
- (5) Class IIIB liquid: 13,750 gal (52,044 L), maximum 15 ft (4.6 m) high

The liquid storage shall also comply with 4.5.2.3 through 4.5.2.9.

4.5.2.3 Liquids in Plastic Containers. Class I and Class II liquids in plastic containers shall not be stored in general-purpose warehouses but shall be stored in inside liquid storage areas that meet the requirements of Section 4.4.

Exception No. 1: The following liquids, packaged in plastic containers, shall be permitted to be stored in general-purpose warehouses in accordance with the protection and storage limitations specified in 4.5.2.2 as follows:

(a) *Products containing not more than 50 percent by volume of water-miscible liquids, with the remainder of the solution not being a Class I liquid, where packaged in individual containers*

(b) *Products containing more than 50 percent water-miscible liquids in individual containers not exceeding 16 oz (0.5 L) capacity*

Exception No. 2: Class I and Class II liquids in plastic containers shall be permitted to be stored in a general-purpose warehouse if the packaging systems are listed and labeled for use with these materials. All other provisions of 4.5.2 shall also apply.

4.5.2.4 Palletized, Solid Pile, or Rack Storage. Liquids in containers shall be permitted to be stored on pallets, in solid piles, or on racks, subject to the maximum total quantity and maximum storage height provisions of 4.5.2.2.

4.5.2.5 Basement Storage Areas. Storage of liquids in basement areas of general-purpose warehouses shall only be permitted as provided for in 4.4.3.5.

4.5.2.6 Mixed Liquid Storage. Where two or more classes of liquids are stored in a single pile or single rack section, the maximum total quantity and maximum storage height permitted shall be as provided for in 4.4.4.4.

4.5.2.7 Separation and Aisles. Storage of liquids in general-purpose warehouses shall be arranged as provided for in 4.4.3.3 and 4.4.3.4.

4.5.2.8 Liquids and Ordinary Combustible Storage. The following shall apply to the storage of liquids and ordinary combustible commodities:

(a) Liquids shall not be stored in the same pile or in the same rack sections as ordinary combustible commodities [see 4.5.2.8(b)]. Where liquids are packaged together with ordinary combustibles, as in kits, the storage shall be considered on the basis of whichever commodity predominates.

(b) Except as provided for in 4.5.2.8(a), ordinary combustible commodities shall be separated from liquids in containers by a minimum distance of 8 ft (2.4 m).

4.5.2.9 Operations. Dispensing of Class I and Class II liquids in general-purpose warehouses shall not be permitted unless the dispensing area is suitably cut off from other ordinary combustible or liquid storage areas, as specified in 4.4.2, and otherwise complies with the applicable provisions of 4.4.2.

4.5.3 Dwellings and Residential Buildings Containing Not More than Three Dwelling Units and Accompanying Attached and Detached Garages. Storage in excess of 25 gal (94.6 L) of Class I and Class II liquids combined shall be prohibited. In addition, storage in excess of 60 gal (227 L) of Class IIIA liquid shall be prohibited.

4.5.4 Assembly Occupancies, Buildings Containing More than Three Dwelling Units, and Hotels. Storage in excess of 10 gal (37.8 L) of Class I and Class II liquids combined or 60 gal (227 L) of Class IIIA liquids shall be in containers stored in storage cabinets, in safety cans, or in an inside storage area that does not have openings that communicate with that portion of the building used by the public.

4.5.5 Office, Educational, and Institutional Occupancies, and Day Care Centers. The following requirements shall apply to office, educational, and institutional occupancies, and day care centers.

4.5.5.1 Storage shall be limited to that required for operation of office equipment, maintenance, demonstration, and laboratory work. This storage shall comply with the provisions of 4.5.5.2 through 4.5.5.5, except that the storage for industrial and educational laboratory work shall comply with NFPA 45, *Standard on Fire Protection for Laboratories Using Chemicals*.

4.5.5.2 Containers of Class I liquids that are stored outside of an inside liquid storage area shall not exceed a capacity of 1 gal (3.8 L).

Exception: Safety cans shall be permitted up to a 2-gal (7.6-L) capacity.

4.5.5.3 Not more than 10 gal (37.8 L) of Class I and Class II liquids combined shall be stored in a single fire area outside of a storage cabinet or an inside liquid storage area unless in safety cans.

4.5.5.4 Not more than 25 gal (95 L) of Class I and Class II liquids combined shall be stored in a single fire area in safety cans outside of an inside liquid storage area or storage cabinet.

4.5.5.5 Not more than 60 gal (227 L) of Class IIIA liquids shall be stored outside of an inside liquid storage area or storage cabinet.

4.5.6 Mercantile Occupancies.

4.5.6.1 This section shall apply to mercantile occupancies that handle, store, and display liquids, as defined in this code.

4.5.6.2 The display arrangement, storage arrangement, and maximum total quantity of liquids allowed shall meet the requirements of this subsection and Table 4.5.6.2.

4.5.6.3 On floors above the ground level, the storage or display of Class I and Class II liquids shall be limited to 60 gal (227 L) in unprotected occupancies and 120 gal (454 L) in protected occupancies.

4.5.6.4 Class I and Class II liquids shall not be permitted to be stored or displayed in basements.

Table 4.5.6.2 Allowable Storage and Display Amounts for Mercantile Occupancies¹

Level of Protection		Liquid Classification		
		IA ²	IB, IC, II, and IIIA (Any Combination)	IIIB
Unprotected	Maximum quantity allowed ³	60 gal	3750 gal per building area; a maximum of two areas permitted per occupancy when separation is provided by a minimum 1-hour-rated fire separation wall	15,000 gal
	Maximum storage density	2 gal/ft ² in storage or display areas and adjacent aisles		
NFPA 13, Ordinary Hazard (Group 2) Sprinkler System ⁴	Maximum quantity allowed ³	120 gal	7500 gal per building area; a maximum of two areas permitted per occupancy when separation is provided by a minimum 1-hour-rated fire separation wall	Unlimited
	Maximum storage density	4 gal/ft ² in storage or display areas and adjacent aisles		
NFPA 30, Section 4.8	Maximum quantity allowed ³	120 gal	30,000 gal per occupancy	Unlimited

For SI units, 1 gal = 3.8 L; 1 ft² = 0.09 m².

¹Existing unprotected mercantile occupancies in operation prior to January 1, 1997, are permitted to store or display up to 7500 gal of Class IB, IC, II, and IIIA liquids (any combination) in each area.

²Ground level floor only.

³Does not include liquids exempted by 4.1.1.

⁴For storage heights that do not exceed 12 ft (3.6 m).

4.5.6.5 Liquids in containers of greater than 5 gal (19 L) capacity shall not be stored or displayed in areas that are accessible to the public.

Exception: This shall not apply to any liquid that is exempt from the requirements of this chapter, as set forth in 4.1.1.2.

4.5.6.6 Class II liquids that are not water-miscible and are packaged in plastic containers of 1 gal (3.8 L) capacity or greater shall be limited to a maximum total quantity of 30 gal (114 L) per pile. Adjacent piles shall be separated by a minimum distance of 50 ft (15 m). This maximum total quantity shall be permitted to be doubled to 60 gal (227 L), if the liquids are stored in listed flammable liquids storage cabinets or are in areas protected by an automatic sprinkler system having a design density of 0.60 gpm per ft² over 2500 ft² (24 L/min/m² over 230 m²) and using high temperature, extra-large orifice quick-response sprinklers.

4.5.6.7 Protection systems for storage and display of liquids that are designed and developed based on full-scale fire tests performed at an approved test facility shall be considered an acceptable alternative to the protection criteria set forth in Section 4.8. Such alternative protection systems shall be approved by the authority having jurisdiction.

4.5.6.8 Means of egress from mercantile occupancies shall meet applicable requirements of NFPA 101, *Life Safety Code*.

4.5.6.9 Power-operated industrial trucks used to move Class I liquids shall be selected, operated, and maintained in accordance with NFPA 505, *Fire Safety Standard for Powered Industrial Trucks Including Type Designations, Areas of Use, Conversions, Maintenance, and Operation*.

4.6* Hazardous Materials Storage Lockers.

4.6.1 Hazardous materials storage lockers that are used as inside rooms shall be considered inside liquid storage rooms and shall meet the requirements for inside rooms as set forth in Section 4.4, as applicable.

4.6.2 Subsections 4.6.3 and 4.6.4 shall apply to storage of flammable and combustible liquids in containers, in hazardous materials storage lockers (hereinafter referred to as lockers) that are located outside.

4.6.3 The design and construction of a locker shall meet all applicable local, state, and federal regulations and requirements and shall be subject to the approval of the authority having jurisdiction. Movable prefabricated structures that have been examined, listed, or labeled by an organization acceptable to the authority having jurisdiction for use as a hazardous materials storage facility shall be acceptable.

4.6.3.1 Lockers governed by this standard shall not exceed 1500 ft² (139 m²) gross floor area. Vertical stacking of lockers shall not be permitted.

4.6.3.2 Where electrical wiring and equipment is required, it shall comply with 4.4.2.6.

4.6.3.3 Where dispensing or filling is permitted inside a locker, operations shall comply with the provisions of Chapter 5.

4.6.3.4 Ventilation shall be provided in accordance with 4.4.2.7.

4.6.3.5 Lockers shall include a spill containment system to prevent the flow of liquids from the structure under emergency conditions. The containment system shall have sufficient capacity to contain 10 percent of the volume of containers allowed or the volume of the largest container, whichever is greater.

4.6.4 Designated sites shall be provided for the location and use of lockers and shall be subject to the approval of the authority having jurisdiction. The designated sites shall be arranged to provide at least the minimum separation distance between individual lockers, distance from locker to property line that is or can be built upon, and distance from locker to nearest side of public ways or to important buildings on the same property, as given in Table 4.6.4 and explanatory notes 1, 2, 3, 4, and 5, as applicable.

Table 4.6.4 Designated Sites¹

Area of Designated Site ² (ft ²)	Distance between Individual Lockers (ft)	Distance from Locker to Property Line that Is or Can Be Built Upon ³ (ft)	Distance from Locker to Nearest Side of Public Ways or to Important Buildings on Same Property ^{3,4} (ft)
≤100	5	10	5
>100 and ≤ 500	5	20	10
>500 and ≤ 1500 ⁵	5	30	20

For SI units, 1 ft = 0.3 m; 1 ft² = 0.09 m².

¹If the locker is provided with a fire resistance rating of not less than 4 hours and deflagration venting is not required in accordance with 4.4.2.4, all distances required by Table 4.6.4 shall be permitted to be waived.

²Site area limits are intended to differentiate the relative size and thus the number of lockers that are permitted in one designated site.

³Distances apply to properties that have protection for exposures, as defined. If there are exposures and such protection for exposures does not exist, the distances shall be doubled.

⁴When the exposed building has an exterior wall, facing the designated site, that has a fire resistance rating of at least 2 hours and has no openings to abovegrade areas within 10 ft (3 m) horizontally and no openings to belowgrade areas within 50 ft (15 m) horizontally of the designated area, the distances can be reduced to half of those shown in the table, except they shall never be less than 5 ft (1.5 m).

⁵When a single locker has a gross single story floor area that will require a site area limit of greater than 1500 ft² (139 m²) or when multiple units exceed the area limit of 1500 ft² (139 m²), the authority having jurisdiction shall be consulted for approval of distances.

Table 4.7.1 Outdoor Liquid Storage in Containers and Portable Tanks

Class	Containers Maximum per Pile		Rigid Plastic and Composite IBCs Maximum per Pile ^a		Portable Tanks and Metal IBCs Maximum per Pile ^b (gal)		Distance between Piles or Racks	Distance to Property Line that Is or Can Be Built Upon	Distance to Street, Alley, or a Public Way
	(gal) ^{b,c,d}	Height (ft)	(gal)	Height (ft)	(gal) ^{b,d}	Height (ft)	(ft)	(ft) ^{c,e}	(ft) ^c
IA	1,100	10	—	—	2,200	7	5	50	10
IB	2,200	12	—	—	4,400	14	5	50	10
IC	4,400	12	—	—	8,800	14	5	50	10
II	8,800	12	8,800	12	17,600	14	5	25	5
III	22,000	18	22,000	18	44,000	14	5	10	5

For SI units, 1 ft = 0.3 m; 1 gal = 3.8 L.

^aStorage of Class I liquids in rigid plastic and composite IBCs not permitted.

^bSee 4.7.1.1 regarding mixed-class storage.

^cSee 4.7.1.4 for smaller pile sizes.

^dFor storage in racks, the quantity limits per pile do not apply, but the rack arrangements shall be limited to a maximum of 50 ft (15 m) in length and two rows or 9 ft (2.7 m) in depth.

^eSee 4.7.1.3 regarding protection for exposures.

4.6.4.1 Once the designated site is approved, it shall not be changed without the approval of the authority having jurisdiction.

4.6.4.2 More than one locker shall be permitted on a designated site, provided that separation distance between individual lockers is maintained in accordance with Table 4.6.4.

4.6.4.3 The approved designated storage site shall be protected from tampering or trespassing where the area is accessible to the general public.

4.6.4.4 Storage Practices.

4.6.4.4.1 Containers of liquid in their original shipping packages shall be permitted to be stored either palletized or solid piled. Unpackaged containers shall be permitted to be stored on shelves or directly on the floor of the locker. Containers over 30 gal (113.5 L) capacity storing Class I or Class II liquids shall not be stored more than two containers high. In all cases, the storage arrangement shall provide unrestricted access to and egress from the locker.

4.6.4.4.2 No other flammable or combustible materials storage shall be permitted within the designated site approved for lockers.

4.6.4.4.3 Placarding or warning signs for lockers shall be in accordance with applicable local, state, and federal regulations or with NFPA 704, *Standard System for the Identification of the Hazards of Materials for Emergency Response*.

4.7 Outdoor Storage.

4.7.1 Outdoor storage of liquids in containers, intermediate bulk containers, and portable tanks shall be in accordance with Table 4.7.1, 4.7.1.1 through 4.7.1.4, and 4.7.2 through 4.7.4.

4.7.1.1 Where two or more classes of materials are stored in a single pile, the maximum gallonage in that pile shall be the smallest of the two or more separate gallonages.

4.7.1.2 No container, intermediate bulk container, or portable tank in a pile shall be more than 200 ft (60 m) from a minimum 20 ft (3.6 m) wide accessway to permit approach of fire control apparatus under all weather conditions.

4.7.1.3 The distances listed in Table 4.7.1 shall apply to properties that have protection for exposures as defined. If there are exposures, and such protection for exposures does not exist, the distance to property line that is or can be built upon shall be doubled.

4.7.1.4 Where total quantity stored does not exceed 50 percent of maximum per pile, the distances to property line that is or can be built upon and to streets, alleys, or public ways shall be permitted to be reduced 50 percent but not to less than 3 ft (0.9 m).

4.7.2 A maximum of 1100 gal (4163 L) of liquids in closed containers, intermediate bulk containers, and portable tanks shall be permitted to be stored adjacent to a building under the same management provided the following conditions apply:

- (1) The adjacent building wall has an exterior fire resistance rating of 2 hours.
- (2) There are no openings to areas at grade or above grade that are within 10 ft (3 m) horizontally of the storage.
- (3) There are no openings directly above the storage.
- (4) There are no openings to areas below grade within 50 ft (15 m) horizontally of the storage.

Exception: The provisions in 4.7.2(1) through 4.7.2(4) are not necessary if the building in question is limited to one story, is of fire-resistive or noncombustible construction, is devoted principally to the storage of liquids, and is acceptable to the authority having jurisdiction.

4.7.2.1 The quantity of liquids stored adjacent to a building protected in accordance with 4.7.2 shall be permitted to exceed that permitted in 4.7.2, provided the maximum quantity per pile does not exceed 1100 gal (4163 L) and each pile is separated by a 10-ft (3-m) minimum clear space along the common wall.

4.7.2.2 Where the quantity stored exceeds the 1100 gal (4163 L) permitted adjacent to the building given in 4.7.2, or the provisions of 4.7.2 cannot otherwise be met, a minimum distance equal to that shown in Table 4.7.1 for distance to property line shall be maintained between buildings and the nearest container or portable tank.

4.7.3 The storage area shall be graded in a manner to divert possible spills away from buildings or other exposures or shall be surrounded by a curb at least 6 in. (150 mm) high. Where curbs are used, provisions shall be made for draining of accumulations of groundwater or rainwater or spills of liquids. Drains shall terminate at a safe location and shall be accessible to operation under fire conditions.

4.7.4 The storage area shall be protected against tampering or trespassers where necessary and shall be kept free of weeds, debris, and other combustible materials not necessary to the storage.

4.7.5 Outdoor storage of containers that are protected from the weather by a canopy or roof that does not limit the dissipation of heat or dispersion of flammable vapors and does not restrict fire-fighting access and control shall be treated as outside storage in accordance with this section and shall not be considered an inside storage area subject to the requirements of Section 4.4.

4.8 Automatic Fire Protection for Inside Storage.

4.8.1 Scope. Section 4.8 shall apply to all storage of liquids in containers and portable tanks as specified in Sections 4.2 through 4.5.

4.8.1.1 Where different classes of liquids and container types are stored in the same protected area, protection shall meet the requirements of this section for the most severe hazard class present.

4.8.1.2 Where storage is on racks as permitted by this code, racks storing Class I, Class II, or Class IIIA liquids shall be either single row or double row, as described in NFPA 230, *Standard for the Fire Protection of Storage*. Unless otherwise specified by Section 4.8, single-row racks shall be not more than 4.5 ft (1.4 m) wide and double-row racks shall not be more than 9 ft (2.8 m) wide.

4.8.1.3* For the purpose of Section 4.8, a relieving-style container shall mean a metal container, a metal intermediate bulk container, or a metal portable tank that is equipped with at least one pressure-relieving mechanism at its top that is designed, sized, and arranged to relieve the internal pressure generated due to exposure to fire so that violent rupture is prevented.

For metal containers greater than 6 gal (23 L) capacity, the pressure-relieving mechanism shall be unobstructed or an additional pressure-relieving mechanism shall be provided. The pressure-relieving mechanism shall be listed and labeled.

4.8.1.4 For new fire protection systems installed after January 1, 1997, fire protection systems shall meet the requirements of Section 4.8.

4.8.1.5 When applying the fire protection criteria of Section 4.8, a minimum aisle space of 6 ft (1.8 m) shall be provided

between adjacent piles or adjacent rack stations, unless otherwise specified in Tables 4.8.2(a) through (j).


4.8.1.6* For the purposes of Section 4.8, any liquid

(a) That gels, thickens, or solidifies when heated; or

(b) Whose viscosity at room temperature versus weight percent content of Class I, Class II, or Class III liquids is in the shaded portion of Figure 4.8.1.6

shall be permitted to be protected using either the criteria for a Class IIIB liquid in accordance with Figures 4.8.2(a) or (c) or the criteria for Group A plastics in accordance with Figure 4.8.2(b), whichever is applicable.

FIGURE 4.8.1.6 Viscosity versus weight percent flammable or combustible component.



4.8.2* Automatic Sprinkler and Foam-Water Fire Protection Systems. Where automatic sprinklers or low-expansion foam-water sprinkler systems are used, the protection criteria of Tables 4.8.2(a) through 4.8.2(j) shall be followed for the applicable liquid class, container type, and storage arrangement. Figures 4.8.2(a), (b), (c), and (d) shall be used to specify protection criteria for liquid classes, container types, and storage arrangements not specifically covered in Tables 4.8.2(a) through 4.8.2(j). All automatic sprinkler and foam-water fire protection systems shall be wet pipe, deluge, or preaction systems. If preaction systems are used, they shall be designed so that water or foam solution will immediately discharge from the sprinkler upon sprinkler actuation.

When foam or foam-water fire protection systems are provided, discharge densities shall be determined based on the listing criteria of the foam discharge devices selected, the foam concentrate, the specific liquids to be protected, and the criteria in Tables 4.8.2(c) and (d). Where the discharge densities given in Tables 4.8.2(c) and (d) differ from those in the listing criteria for the discharge devices, the greater of the two shall be used.

Exception No. 1: Except as otherwise permitted in Sections 4.2 through 4.7.

Exception No. 2: Tables 4.8.2(a) through (j) shall not apply to unstable liquids.

FIGURE 4.8.2(a) Fire protection criteria decision tree for flammable and combustible liquids in metal containers.




FIGURE 4.8.2(b) Fire protection criteria decision tree for flammable and combustible liquids in plastic or fiberboard containers.






FIGURE 4.8.2(c) Fire protection criteria decision tree for water-miscible flammable and combustible liquids in plastic containers.



For SI units, 1 gal = 3.8 L.

FIGURE 4.8.2(d) Fire protection criteria decision tree for flammable and combustible liquids in glass containers.



For SI units, 1 gal = 3.8 L.

4.8.2.1 In-rack sprinklers shall be installed in accordance with the provisions of NFPA 230, *Standard for the Fire Protection of Storage*.

Exception: As modified as follows:

(a) Alternate lines of in-rack sprinklers shall be staggered vertically in the longitudinal flue space.

(b) Sprinkler heads of multiple-level sprinkler systems shall be provided with water shields unless they are separated by horizontal barriers or are specifically listed for installation without water shields.

(c) A vertical clear space of at least 6 in. shall be maintained between the sprinkler deflector and the top of the tier of storage.

(d) Sprinkler discharge shall not be obstructed by horizontal rack structural members.

(e) Longitudinal and transverse flue spaces of at least 6 in. (150 mm) shall be maintained between each rack load.

Table 4.8.2(a) Water Sprinkler Protection of Single- or Double-Row Rack Metal Containers (for Nonmiscible Liquids or Miscible Liquids with Flammable Liquid Concentration >50%)

Liquid Class	Container Size and Arrangement (gal)	Maximum Storage Height (ft)	Maximum Ceiling Height (ft)	Ceiling				In-Rack Sprinkler Protection	Notes	Fire Test Ref. ^c
				Sprinkler Type		Density (gpm/ft ²)	Design Area (ft ²) ^b			
				Nominal K-Factor ^a	Response ^a					
Nonrelieving-Style Container										
IB, IC, II, or III	≤1	16	30	11.2	QR	0.60	2000	One line 8 ft above floor	2, 5	1
	≤1	20	30	8.0 or 11.2	SR or QR	0.60	2000	One line 6 ft above floor; one line 12 ft above floor	2, 5	2
IB, IC, II, or IIIA	≤5	25	30	5.6 or 8.0	SR or QR	0.30	3000	Every level	2	3
IIIB	≤5	40	50	5.6 or 8.0	SR or QR	0.30	2000	One line every other level, beginning above first storage level	2, 6	4
IB, IC, II, or IIIA	>5 and ≤60	25	30	8.0 or 11.2	SR	0.40	3000	Every level	4	5
IIIB	>5 and ≤60	40	50	5.6 or 8.0	SR	0.30	3000	One line every other level, beginning above first storage level	2, 6	6
Relieving-Style Containers ^d										
IB, IC, II, or IIIA	≤5	14	18	11.2	QR	0.65	2000	None	1, 3	7
	≤5	25	30	5.6 or 8.0	SR or QR	0.30	3000	One line every other level, beginning above first storage level	2, 7	8
IIIB	≤5	40	50	5.6 or 8.0	SR or QR	0.30	2000	One line every other level, beginning above first storage level	2, 6	9

Table 4.8.2(a) Water Sprinkler Protection of Single- or Double-Row Rack Metal Containers (for Nonmiscible Liquids or Miscible Liquids with Flammable Liquid Concentration >50%) (Continued)

Liquid Class	Container Size and Arrangement (gal)	Maximum Storage Height (ft)	Maximum Ceiling Height (ft)	Ceiling				In-Rack Sprinkler Protection	Notes	Fire Test Ref. ^c
				Sprinkler Type		Density (gpm/ft ²)	Design Area (ft ²) ^b			
				Nominal K-Factor ^a	Response ^a					
IB, IC, II, or IIIA	>5 and ≤60	25	30	8.0 or 11.2	SR	0.60	3000	One line every other level, beginning above first storage level	2	10
IIIB	>5 and ≤60	40	50	5.6 or 8.0	SR	0.30	3000	One line every other level, beginning above first storage level	2, 6	11
IB, IC, II, or IIIA	Portable tanks	25	30	8.0 or 11.2	SR	0.60	3000	Every level	4	12
IIIB	Portable tanks	40	50	8.0	SR	0.30	3000	One line every other level, beginning above first storage level	4	13

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 ft² = 0.09 m²; 1 gpm/ft² = 40.7 L/min/m².

Notes:

1. Double-row racks 6 ft wide maximum.
2. Space in-rack sprinklers on maximum 9-ft centers, staggered vertically. Base design on 30 gpm per sprinkler, with six hydraulically most remote sprinklers operating in each of upper three levels, or eight hydraulically most remote sprinklers if only one level. In-rack sprinklers are K=5.6 or K=8.0, QR, ordinary temperature, with shields.
3. Use pendent-style K=11.2 ceiling sprinklers.
4. Space in-rack sprinklers on maximum 9-ft centers staggered vertically, 30 gpm per sprinkler, K=5.6 or 8.0, QR or SR, with shield, ordinary temperature, six hydraulically most remote sprinklers each level (upper three levels) operating. Eight sprinklers operating, if only one level.
5. Protection for uncartoned or case-cut nonsolid shelf display up to 6¹/₂ ft and storage above in pallets on racking, shelf material, open wire mesh, or 2 in. × 6 in. wooden slats, spaced a minimum of 2 in. apart.
6. A 0.60 density shall be used if more than one level of storage exists above the top level of in-rack sprinklers (K=8.0 or 11.2 for ceiling sprinklers).
7. A 0.60 density/2000 ft² shall be used if more than one level of storage exists above the top level of in-rack sprinklers (K=8.0 or 11.2 for ceiling sprinklers).

^aSR = standard response and QR = quick response, where both are listed.

^bCeiling sprinklers high temperature.

^cSee Table D.2(a) for references to fire tests on which the protection criteria given in this table are based.

^dBoth ³/₄ in. (20 mm) and 2 in. (50 mm) listed and labeled pressure-relieving mechanisms are required on containers greater than 6 gal capacity.

Table 4.8.2(b) Water Sprinkler Protection of Bulk or Palletized Storage Metal Containers (for Nonmiscible Liquids or Miscible Liquids with Flammable Liquid Concentration >50%)

Liquid Class	Container Size and Arrangement (gal)	Maximum Storage Height (ft)	Maximum Ceiling Height (ft)	Ceiling		Density (gpm/ft ²)	Design Area (ft ²) ^b	Notes	Fire Test Ref. ^c
				Sprinkler Type					
				Nominal K-factor	Response ^a				
Nonrelieving-Style Container									
IB, IC, II, or IIIA	≤5	4	18	5.6 or 8.0	SR or QR	0.21	1500	1	1
	≤5	5	18	5.6 or 8.0	SR or QR	0.30	3000	—	2
	≤5	6½	30	8.0 or 11.2	QR	0.45	3000	—	3
	>5 and ≤60	5	18	8.0 or 11.2	SR	0.40	3000	—	4
IIIB	≤5	18	30	5.6 or 8.0	SR or QR	0.25	3000	—	5
	>5 and ≤60	10	20	5.6 or 8.0	SR	0.25	3000	—	6
		18	30	5.6 or 8.0	SR	0.35	3000	—	7
Relieving-Style Containers ^d									
IB, IC,	≤5	12	30	11.2	QR	0.60	3000	2, 3	8
II, or IIIA	>5 and ≤60	5	30	8.0 or 11.2	SR	0.40	3000	—	9
	>5 and ≤60	6½	30	8.0 or 11.2	SR	0.60	3000	4	10
IIIB	≤5	18	30	5.6 or 8.0	SR or QR	0.25	3000	—	11
	>5 and ≤60	10	20	5.6 or 8.0	SR	0.25	3000	—	12
		18	30	5.6 or 8.0	SR	0.35	3000	—	13
IB, IC,	Portable tanks	1 high	30	5.6 or 8.0	SR	0.30	3000	—	14
II, or IIIA		2 high	30	8.0 or 11.2	SR	0.60	5000	—	15
IIIB	Portable tanks	1 high	30	5.6 or 8.0	SR	0.25	3000	—	16
		2 high	30	8.0 or 11.2	SR	0.50	3000	—	17

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 ft² = 0.09 m²; 1 gpm/ft² = 40.7 L/min/m².

Notes:

1. Minimum hose stream demand: 250 gpm for 2 hrs.

2. Sprinklers shall also be hydraulically calculated to provide a density of 0.80 gpm/ft² over 1000 ft².

3. Use pendent-style K=11.2 ceiling sprinklers.

4. Drums placed on open slotted pallet, not nested, to allow pressure relief from drums on lower levels.

^aSR = standard response and QR = quick response, where both are listed.

^bCeiling sprinklers high temperature.

^cSee Table D.2(b) for references to fire tests on which the protection criteria given in this table are based.

^dBoth ³/₄ in. (20 mm) and 2 in. (50 mm) listed and labeled pressure-relieving mechanisms are required on containers greater than 6 gal capacity.

Table 4.8.2(c) Foam-Water Sprinkler Protection of Single- or Double-Row Racks Metal Containers (for Nonmiscible Liquids or Miscible Liquids with Flammable Liquid Concentration >50%)

Liquid Class	Container Size and Arrangement (gal)	Maximum Storage Height (ft)	Maximum Ceiling Height (ft)	Ceiling				In-Rack Sprinkler Protection	Notes	Fire Test Ref. ^c
				Sprinkler Type		Density (gpm/ft ²)	Design Area (ft ²) ^b			
				Nominal K-Factor	Response ^a					
Nonrelieving-Style Container										
IB, IC, II, or IIIA	≤5	25	30	5.6 or 8.0	SR or QR	0.30	2000	Every level	1, 2	1
	>5 and ≤60	25	30	5.6 or 8.0	SR	0.30	3000	Every level	1, 3	2
IIIB	≤60	40	50	5.6 or 8.0	SR	0.30	2000	One line every other level, beginning above first storage level	1	3
Relieving-Style Containers ^d										
IB, IC, II, IIIA	≤5	25	30	5.6 or 8.0	SR or QR	0.30	2000	One line every other level, beginning above first storage level	1, 2	4
	>5 and ≤60 and portable tanks	25	30	5.6 or 8.0	SR	0.30	3000	One line every other level, beginning above first storage level	1, 3	5
IIIB	≤60	40	50	5.6 or 8.0	SR	0.30	2000	One line every other level, beginning above first storage level	1	6

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 ft² = 0.09 m²; 1 gpm/ft² = 40.7 L/min/m².

Notes:

1. Space in-rack sprinklers on maximum 9-ft centers, staggered vertically. Base design in 30 gpm per sprinkler, with six hydraulically most remote sprinklers operating in each of upper three levels. Sprinklers are K=5.6 or 8.0, SR or QR, ordinary temperature, with shields. Hydraulic design can be reduced to three sprinklers operating per level — three levels operating simultaneously when using a pre-primed foam-water system installed in accordance with NFPA 16, *Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems*, and maintained according to NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*.

2. Design area can be reduced to 1500 ft² when using a pre-primed foam-water system installed in accordance with NFPA 16 and maintained according to NFPA 25.

3. Design area can be reduced to 2000 ft² when using a pre-primed foam-water system installed in accordance with NFPA 16 and maintained according to NFPA 25.

^aSR = standard response and QR = quick response, where both are listed.

^bCeiling sprinklers high temperature.

^cSee Table D.2(c) for references to fire tests on which the protection criteria given in this table are based.

^dBoth 3/4 in. (20 mm) and 2 in. (50 mm) listed and labeled pressure-relieving mechanisms are required on containers greater than 6 gal capacity.

Table 4.8.2(d) Foam-Water Sprinkler Protection of Bulk or Palletized Storage Metal Containers (for Nonmiscible Liquids or Miscible Liquids with Flammable Liquid Concentration > 50%)

Liquid Class	Container Size and Arrangement (gal)	Maximum Storage Height (ft)	Maximum Ceiling Height (ft)	Ceiling				Notes	Fire Test Ref. ^c
				Sprinkler Type		Density (gpm/ft ²)	Design Area (ft ²) ^b		
				Nominal K-Factor	Response ^a				
Nonrelieving-Style Container									
IB, IC, II, or IIIA	≤5 cartoned	11	30	8.0 or 11.2	SR or QR	0.40	3000	2	1
	≤5 uncartoned	12	30	5.6 or 8.0	SR or QR	0.30	3000	2	2
	>5 and ≤60	5 ^d	30	5.6 or 8.0	SR	0.30	3000	2	3
Relieving-Style Containers ^g									
IB, IC, II, or IIIA	>5 and ≤60	6 ^{1/2}	30	5.6 or 8.0	SR	0.30	3000	1	4
	>5 and ≤60	10 ^e	33	11.2	SR	0.45	3000	1, 3	6
	>5 and ≤60	13 ft 9 in. ^f	33	11.2	SR	0.60	3000	1, 3	7
	Portable tanks	2-high maximum	30	5.6 or 8.0	SR	0.30	3000	1	5

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 ft² = 0.09 m²; 1 gpm/ft² = 40.7 L/min/m².

Notes:

1. Drums placed on open slotted pallet, not nested, to allow pressure relief from drums on lower levels.

2. Design area can be reduced to 2000 ft² when using a pre-primed foam-water system installed in accordance with NFPA 16, *Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems*, and maintained according to NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*.

^aSR = standard response and QR = quick response, where both are listed.

^bCeiling sprinklers high temperature.

^cSee Table D.2(d) for references to fire tests on which the protection criteria given in this table are based.

^{d, e, f}1 high; 3 high; 4 high

^gBoth ³/₄ in. (20 mm) and 2 in. (50 mm) listed pressure-relieving mechanisms are required on containers greater than 6 gal capacity.

Table 4.8.2(e) Water Sprinkler Protection of Single-, Double-, and Multi-Row Open Frame Rack Storage Containing Class IIIB Liquids in Plastic Containers (for Nonmiscible Flammable and Combustible Liquids or Miscible Flammable and Combustible Liquids with Concentration >50%)

Liquid Type or Closed-Cup Flash Point (°F)	Container Size (gal)	Maximum Building or Ceiling Height	Packaging Type	Maximum Storage Height	Minimum Aisle Width (ft)	Rack Width	Sprinkler Protection Criteria		
							Ceiling Sprinkler Type	Fire Protection Scheme	Fire Test Ref.*
≥200	≤5	Unlimited	Cartoned or uncartoned	Unlimited	4	Any	Any	Scheme A (see 4.8.6.1)	1

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 32°F = 0°C.

*See Table D.2(e) for reference to the fire test on which the protection criteria given in this table are based.

Table 4.8.2(f) Water Sprinkler Protection of Shelf Storage Metal Containers (for Nonmiscible Liquids or Miscible Liquids with Flammable Liquid Concentration >50%)

Nonrelieving-Style Container									
Liquid Class	Container Size and Arrangement (gal)	Maximum Storage Height (ft)	Maximum Ceiling Height (ft)	Ceiling					
				Sprinkler Type		Density (gpm/ft ²)	Design Area (ft ²) ^b	Notes	Fire Test Ref. ^c
				Nominal K-Factor	Response ^a				
IB, IC, II, or III	≤1	6	18	5.6 or 8.0	SR or QR	0.19	1500	1, 2	1

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 ft² = 0.09 m²; 1 gpm/ft² = 40.7 L/min/m².

Notes:

1. Protection for mercantile shelving that is 2 ft or less in depth per side, with backing between each side.

2. Minimum hose stream demand 250 gpm for 2 hours.

^aSR = standard response and QR = quick response, where both are listed.

^bCeiling sprinklers high temperature.

^cSee Table D.2(f) for references to fire tests on which the protection criteria given in this table are based.

Table 4.8.2(g) Water Sprinkler Protection of Single- and Double-Row Open Frame Rack Storage Containing Water-Miscible Liquids in Plastic Containers (Flammable Liquid Concentration >50%)

Liquid Class	Container Size (gal)	Maximum Building or Ceiling Height (ft)	Packaging Type	Maximum Storage Height (ft)	Minimum Aisle Width (ft)	Rack Width (ft)	Sprinkler Protection Criteria		
							Ceiling Sprinkler Type	Fire Protection Scheme	Fire Test Ref. ^a
IB, IC, II, III	≤1	Unlimited	Cartoned	Unlimited	8	≤9	Any	Scheme B (see 4.8.6.2)	1
	≤60	30	Uncartoned or cartoned	25	8	≤9	Standard spray sprinklers	Scheme B (see 4.8.6.2)	2

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m.

^aSee Table D.2(g) for reference to the fire test on which the protection criteria given in this table are based.

Table 4.8.2(h) Water Sprinkler Protection of Rack and Palletized Storage of Class IB, IC, II, IIIA, and IIIB Liquids in Relieving-Style Metal Containers with Aisles a Minimum of 7.5 ft Wide (for Nonmiscible Flammable or Combustible Liquids or Miscible Flammable or Combustible Liquids with Concentrations >50%)

Table 1. Rack Protection Criteria														
Storage Arrangement	Rack Width (ft)	Shelf Type	Building Height (ft)	Maximum Storage Height (ft)	Container Size (gal)	Packaging Type	Ceiling Sprinkler Protection Criteria		In-Rack Sprinkler Protection Criteria					
							Sprinkler Type/ K-Factor/ Temperature Rating ^a	Design (No. of Sprinklers @ Pressure)	In-Rack Layout ^b	Sprinkler Type		In-Rack End Sprinkler Design Pressure (see Notes 1 and 2)	Notes	Fire Test Ref. ^d
										Nominal K-factor	Response Temperature Rating ^c			
Rack with 7.5-ft aisle	≤6	Open wire mesh and/or none	24	14	≤5 (see Note 3)	Uncartoned or cartoned	ESFR, K = 14.0, Ordinary	12 @ 50 psig	Figure 4.8.6.3(a)	11.2	QR, Ordinary	10 psig	1–5	1
Rack with 8-ft aisle	≤9	None	30	20	≤1	Cartoned only	ESFR, K = 14.0, Ordinary	12 @ 25 psig	None	None	None	None	3, 4, 5	2
				25	≤1	Cartoned only	ESFR, K = 14.0, Ordinary	12 @ 75 psig	None	None	None	None	5	3
				25	≤1	Cartoned only	ESFR, K = 14.0, Ordinary	12 @ 50 psig	Figures 4.8.6.3(d) or (e)	8.0	QR, Ordinary	15 psig	1, 2, 5	4
				25	≤5	Uncartoned or cartoned	ESFR, K = 14.0, Ordinary	12 @ 75 psig	Figures 4.8.6.3(b) or (c)	8.0	QR, Ordinary	30 psig	1, 2, 5	5
Palletized	DNA ^e	DNA	30	8	≤1	Cartoned only	ESFR, K = 14.0, Ordinary	12 @ 50 psig	DNA	DNA	DNA	DNA	5	6
				12	≤5	Uncartoned or cartoned	ESFR, K = 14.0, Ordinary	12 @ 75 psig	DNA	DNA	DNA	DNA	5	7

For SI units, 1 gal = 3.8 L; 1 in. = 25 mm; 1 ft = 0.3 m; 1 psig = 6.9 kPa.

^aESFR = early suppression fast response.

^bFigures 4.8.6.3(a) through 4.8.6.3(e) can be found in 4.8.6.3.

^cQR = quick response, ordinary temperature range.

^dSee Table D.2(h) for references to fire tests on which the protection criteria given in this table are based.

^eDNA = does not apply.

Notes:

- The in-rack sprinkler water demand shall be based on the simultaneous operation of the most hydraulically remote sprinklers as follows:
 - Seven sprinklers where only one level of in-rack sprinklers is installed.
 - Fourteen sprinklers (seven on each two top levels) where more than one level of in-rack sprinklers is installed.
 - The in-rack end sprinkler design pressure as provided in the table.
- The in-rack sprinkler water demand shall be balanced with the ceiling sprinkler water demand at their point of connection.
- One-gal and 1-qt containers do not need to be relieving style.
- Provide minimum 3-in. transverse flue at rack uprights.
- A hose stream allowance of 500 gpm shall be used.

Table 4.8.2(i) Water Sprinkler Protection^a Bulk or Palletized Storage Container Construction — Rigid Nonmetallic IBC^b (for Nonmiscible Combustible Liquids or Miscible Combustible Liquids with Liquid Concentrations >50%)

Ceiling								
Liquid Class	Container Size ^c (gal)	Maximum Storage Height	Maximum Ceiling Height (ft)	Sprinkler Type		Density (gpm/ft ²)	Design Area (ft ²)	Fire Test Ref. ^d
				Nominal K-Factor	Response			
II, III	≤793	1 high	30	11.2	High temp., SR ^c	0.45	3000	1
	≤793	2 high	30	11.2	High temp., SR	0.60 ^f	3000	2

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 ft² = 0.09 m²; 1 gpm /ft² = 40.7 L/min/m².

^aFoam-water sprinkler protection shall be permitted to be substituted for water sprinkler protection, provided the same design criteria are used.

^bRigid nonmetallic IBC — Rigid nonmetallic IBC that has been subjected to a standardized fire test that demonstrates the fire performance when the IBC is stacked one or two high and that is listed and labeled as such.

^cSee Appendix E, Section II.

^dSee Table D.2(i) for reference to fire test on which the protection criteria given in this table are based.

^eSR = Standard Response.

^fSprinkler-operating pressure shall be a minimum of 30 psi (207 kPa).

Table 4.8.2(j) Water Sprinkler Protection of Single- and Double-Row, Open-Frame Rack Storage in Rigid Nonmetallic Intermediate Bulk Containers^a (for Nonmiscible Class II and Class III Liquids and for Miscible Class II and Class III Liquids with >50% Class II and Class III Concentration)

Liquid Class	Container Capacity ^b (gal)	Maximum Building or Ceiling Height (ft)	Maximum Storage Height ^c (ft)	Minimum Aisle Width (ft)	Rack Width (ft)	Sprinkler Protection Criteria		
						Ceiling Sprinkler Type	Fire Protection Scheme	Fire Test Ref.
II, III	≤793	30	25	8	9	Standard spray	Scheme B (see 4.8.6.2)	1 ^d

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m.

^aRigid nonmetallic intermediate bulk containers (IBC) that have been subjected to a standardized fire test that demonstrates the fire performance when the IBCs are stacked one or two high and that are listed and labeled as such.

^bSee Appendix E, Section II.

^cTier height shall not exceed 6 ft. (See 4.8.6.2.)

^dSee Table D.2(j) for references to fire tests on which protection criteria are based.

4.8.2.2 Ceiling sprinklers shall be installed in accordance with NFPA 13, *Standard for the Installation of Sprinkler Systems*, and shall be permitted to have the following maximum head spacing:

- (1) Classes I, II, and IIIA liquids: 100 ft² (9 m²) per sprinkler head
- (2) Class IIIB liquids: 120 ft² (10.8 m²) per sprinkler head

4.8.2.3 Protection systems that are designed and developed based on full-scale fire tests performed at an approved test facility or on other engineered protection schemes shall be considered an acceptable alternative to the protection criteria set forth in Section 4.8. Such alternative protection systems shall be approved by the authority having jurisdiction.

4.8.2.4 Water-based fire protection systems shall be inspected, tested, and maintained in accordance with NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*.

4.8.2.5 The ceiling heights given in Tables 4.8.2(a) through 4.8.2(j) shall be permitted to be increased by a maximum of 10 percent if an equivalent percent increase in ceiling sprinkler design density is provided.

4.8.2.6 Low-expansion foam-water sprinkler systems shall be designed and installed in accordance with NFPA 16, *Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems*. The system shall have at least 15 minutes of foam concentrate, based on the required design flow rate.

4.8.2.7 Water supplies for automatic sprinklers, other water-based extinguishing systems, and hydrants shall be capable of supplying the anticipated demand and shall be capable of supplying that demand for at least 2 hours.


4.8.2.8* Foam-water sprinkler systems shall provide foam solution to operating sprinklers with four sprinklers flowing.

4.8.3 Other Automatic Fire Protection Systems. Alternate fire protection systems, such as automatic water spray systems, automatic water mist systems, high-expansion foam systems, dry chemical extinguishing systems, alternate sprinkler system configurations, or combinations of systems shall be permitted if approved by the authority having jurisdiction. Such alternate systems shall be designed and installed in accordance with the appropriate NFPA standard and with manufacturer's recommendations for the system(s) selected.

4.8.4 Water supplies for automatic sprinklers, other water-based protection systems, and hydrants shall be capable of supplying the anticipated water flow demand for a minimum of 2 hours.

4.8.5 Containment and Drainage. Containment and drainage shall be provided in accordance with Figure 4.8.5, when protection systems are installed in accordance with the provisions of Tables 4.8.2(a) through (j).

4.8.5.1* Where control of liquid spread is required, means to limit the spread of liquid to an area not greater than the design discharge area of the ceiling sprinkler system shall be provided.

FIGURE 4.8.5 Spill containment and liquid spread control for protected storage.

For SI units, 1 gal = 3.8 L.

4.8.6 Fire Protection Schemes.

4.8.6.1 Fire Protection Scheme A.


4.8.6.1.1 Plywood [minimum $\frac{3}{8}$ in. (10 mm)] or sheet metal (minimum 22 ga.) barriers and in-rack sprinklers shall be installed in accordance with Figures 4.8.6.1.1(a), 4.8.6.1.1(b), or 4.8.6.1.1(c). Vertical baffles shall not be provided between in-rack sprinklers.

4.8.6.1.2 Listed or approved K=8.0, ordinary temperature-rated quick-response in-rack sprinklers shall be installed below each barrier level. The in-rack sprinklers shall be designed to provide a minimum end head pressure of 50 psig (gauge pressure of 345 kPa) out of the hydraulically most remote six sprinklers (three on two lines) if one barrier level or the most remote eight sprinklers (four on two lines) if two or more barrier levels are provided.

4.8.6.1.3 If there are adjacent bays of in-rack arrays not dedicated to Class IIIB liquid storage, the barrier and in-rack sprinkler protection shall be extended at least 8 ft (2.4 m) beyond the Class IIIB liquid storage.

4.8.6.1.4 Ceiling sprinkler demand shall not be included in the hydraulic calculations for in-rack sprinklers. Water demand at point of supply shall be calculated separately for in-rack and ceiling sprinklers and based on the greater demand.

FIGURE 4.8.6.1.1(a) Single-row rack sprinkler layout.



For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

X In-rack sprinkler, $\frac{1}{2}$ in., ordinary, QR


4.8.6.1.5 Ceiling sprinklers shall be designed to protect the surrounding occupancy. Any ceiling sprinkler type shall be acceptable. If standard spray ceiling sprinklers are provided, they shall not provide less than 0.20 gpm/ft² over 3000 ft² (8.1 Lpm/m² over 270 m²). If the Class IIIB liquid storage does not extend to the full height of the rack, protection for other commodities stored above the barrier shall be in accordance with appropriate standards based on full height of the rack.

4.8.6.1.6 Barriers shall not be required for storage of liquids with a closed-cup flash point $\geq 450^\circ\text{F}$ (232°C). If barriers are omitted, the following modifications to the protection scheme shall be provided:

- (1) Ceiling sprinkler protection shall be provided with ordinary temperature-rated standard spray sprinklers designed to provide 0.3 gpm/ft² over 2000 ft² (12.2 Lpm/m² over 180 m²).
- (2) The ceiling sprinkler water demand and the in-rack water demand shall be balanced at their point of connection.

4.8.6.1.7 A 500-gpm (1900 Lpm) hose stream allowance shall be provided.


FIGURE 4.8.6.1.1(b) Double-row rack sprinkler layout.



For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

● Longitudinal flue sprinkler, $\frac{1}{2}$ in., ordinary, QR

X Face sprinkler, $\frac{1}{2}$ in., ordinary, QR

FIGURE 4.8.6.1.1(c) Multiple-row rack sprinkler layout.

For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.


X In-rack sprinkler, $1\frac{7}{32}$ in., ordinary, QR

4.8.6.2 Fire Protection Scheme B.

4.8.6.2.1 Horizontal barriers of plywood [minimum $\frac{3}{8}$ in. (10 mm) thickness] or sheet metal (minimum 22 ga.) and in-rack sprinklers shall be installed in accordance with Figures 4.8.6.2.1(a), 4.8.6.2.1(b), or 4.8.6.2.1(c). Vertical baffles shall not be provided between in-rack sprinklers.

4.8.6.2.2 In-rack sprinklers shall be nominal K-factor of 8.0, ordinary temperature-rated, quick-response sprinklers and shall be installed below each horizontal barrier. The design criteria of the in-rack sprinkler system shall meet the following:

- (1) For containers that do not exceed 60 gal (227 L) capacity and where there is only one horizontal barrier, the in-rack sprinkler system shall provide a minimum head pressure of 50 psig (gauge pressure of 345 kPa) from the hydraulically most remote six sprinklers, three each on two lines. Where there are two or more horizontal barriers, the in-rack sprinkler system shall provide a minimum head pressure of 50 psig (gauge pressure of 345 kPa) from the hydraulically most remote eight sprinklers, four each on two lines.
- (2) For containers that exceed 60 gal (227 L) capacity, but do not exceed 793 gal (3000 L), the in-rack sprinkler system shall provide a minimum head pressure of 50 psig (gauge pressure of 345 kPa) from the hydraulically most remote 12 sprinklers, six each on two lines.

FIGURE 4.8.6.2.1(a) Single-row rack sprinkler layout.

For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

X In-rack sprinkler, $1\frac{7}{32}$ in., ordinary, QR

4.8.6.2.3 If there are adjacent bays or racks that are not dedicated to storage of liquids, the barrier and in-rack sprinkler system shall be extended beyond the area devoted to liquid storage as follows:

- (1) For containers that do not exceed 1 gal (3.8 L) capacity, the protection shall be extended at least 8 ft (2.4 m) beyond the area devoted to liquid storage. In addition, adjacent racks across the aisles on each side of the liquid storage shall be protected in accordance with NFPA 13, *Standard for the Installation of Sprinkler Systems*, for the commodity stored.
- (2) For containers that exceed 1 gal (3.8 L) capacity, but do not exceed 793 gal (3000 L), the protection shall be extended at least 8 ft (2.4 m) beyond the area devoted to liquid storage. In addition, the protection shall be extended to protect adjacent racks across the aisles on each side of the liquid storage.

4.8.6.2.4 Ceiling sprinkler protection for containers that do not exceed 1 gal (3.8 L) capacity shall meet the following:

- (1) The ceiling sprinkler protection shall be designed to protect the surrounding occupancy.
- (2) The ceiling sprinkler water demand shall not be included in the hydraulic calculations for the in-rack sprinkler protection. Water demand at the point of supply shall be calculated separately for the in-rack and ceiling protection and shall be based on the greater of the two.
- (3) Any sprinkler type shall be acceptable for the ceiling sprinkler protection. If standard spray sprinklers are

used, they shall be capable of providing not less than 0.20 gpm/ft² over 3000 ft² (8.1 Lpm/m² over 270 m²).

- (4) If the liquid storage does not extend to the full height of the rack, protection for commodities stored above the top horizontal barrier shall meet the requirements of NFPA 13, *Standard for the Installation of Sprinkler Systems*, for the commodities stored, based on the full height of the rack.

4.8.6.2.5 Ceiling sprinkler protection for containers that exceed 1 gal (3.8 L) capacity, but do not exceed 60 gal (227 L), shall meet the following:

- (1) The ceiling sprinkler protection shall be designed to provide a minimum density of 0.45 gpm/ft² over the most remote 3000 ft² (18.3 Lpm/m² over 270 m²), using K=11.2 or K=8.0 high-temperature-rated standard-response sprinklers of nominal K-factor of 8.0 or 11.2. Other types of sprinklers shall not be used.
- (2) The ceiling sprinkler water demand and the in-rack sprinkler demand shall be balanced at the point of connection.

FIGURE 4.8.6.2.1(b) Single-row rack sprinkler layout.





FIGURE 4.8.6.2.1(c) Double-row rack sprinkler layout.




4.8.6.2.6 Ceiling sprinkler protection for containers that exceed 60 gal (3.8 L) capacity, but do not exceed 793 gal (3000 L), shall meet the following:

- (1) The ceiling sprinkler protection shall be designed to provide a minimum density of 0.60 gpm/ft² over the most remote 3000 ft² (24.4 Lpm/m² over 270 m²), using K=11.2 or K=8.0 high-temperature-rated standard-response sprinklers of nominal K-factor of 8.0 or 11.2. Other types of sprinklers shall not be accepted.
- (2) The ceiling sprinkler water demand and the in-rack sprinkler demand shall be balanced at the point of connection.


4.8.6.2.7 A 500-gpm (1900 L) water supply capacity shall be provided for hose streams.

4.8.6.3 In-Rack Sprinkler Layouts for Table 4.8.2(h). Figures 4.8.6.3(a) through 4.8.6.3(e) shall be used to determine layout of in-rack sprinklers for Table 4.8.2(h).

FIGURE 4.8.6.3(a) Modified double-row rack sprinkler layout.


For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

X In-rack sprinkler, $\frac{3}{8}$ in., ordinary, QR

FIGURE 4.8.6.3(b) Double-row rack sprinkler layout.


For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

●, X In-rack sprinkler, $\frac{17}{32}$ in., QR

FIGURE 4.8.6.3(c) Double-row rack sprinkler layout.


For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

X In-rack sprinkler, $\frac{17}{32}$ in., QR

FIGURE 4.8.6.3(d) Double-row rack sprinkler layout.

For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

●, X In-rack sprinkler, $\frac{17}{32}$ in., QR

FIGURE 4.8.6.3(e) Double-row rack sprinkler layout.

For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

X In-rack sprinkler, $1\frac{7}{32}$ in., QR

4.9 Manual Fire Protection. Portable fire extinguishers or pre-connected hoselines, either $1\frac{1}{2}$ -in. (40 mm) lined fire hose or 1-in. (25 mm) hard rubber hose, shall be provided where liquids are stored. If $1\frac{1}{2}$ -in. (40 mm) lined fire hose is used, it shall be installed in accordance with NFPA 14, *Standard for the Installation of Standpipe, Private Hydrants, and Hose Systems*.

4.9.1 Portable fire extinguishers shall meet the following requirements:

- (1) At least one portable fire extinguisher having a capability of not less than 40:B shall be located outside of, but not more than 10 ft (3 m) from, the door opening into an inside liquid storage area.
- (2) At least one portable fire extinguisher having a capability of not less than 40:B shall be located within 30 ft (9 m) of any Class I or Class II liquid storage area that is located outside of an inside liquid storage area or liquid warehouse.

Exception: An acceptable alternative is at least one portable fire extinguisher having a capacity of 80:B located within 50 ft (15 m) of such a storage area.

4.9.2 Hoseline connections shall meet the following requirements:

- (1) In protected general-purpose warehouses and in protected liquid storage areas, hoseline connections shall be provided as appropriate.
- (2) The water supply for hoseline connections shall be sufficient to meet the fixed fire protection demand plus a total of at least 500 gpm (1900 L/min) for inside and outside hoseline connections.

Exception: As otherwise specified in Tables 4.8.2(a) through 4.8.2(j).

4.10 Control of Ignition Sources. Precautions shall be taken to prevent the ignition of flammable vapors. Sources of ignition include, but are not limited to, the following:

- (1) Open flames
- (2) Lightning
- (3) Smoking
- (4) Cutting or welding
- (5) Hot surfaces
- (6) Frictional heat
- (7) Static electricity
- (8) Electrical or mechanical sparks
- (9) Spontaneous heating, including heat-producing chemical reactions
- (10) Radiant heat

4.10.1* Materials that are water-reactive, as described in NFPA 704, *Standard System for the Identification of the Hazards of Materials for Emergency Response*, shall not be stored in the same area with other liquids.

4.10.2* Power-operated industrial trucks used to move Class I liquids shall be selected, operated, and maintained in accordance with NFPA 505, *Fire Safety Standard for Powered Industrial Trucks Including Type Designations, Areas of Use, Conversions, Maintenance, and Operation*.

Chapter 5 Operations

5.1 Scope.

5.1.1 This chapter shall apply to operations involving the use or handling of liquids either as a principal or incidental activity, except as covered elsewhere in this code or in other NFPA standards.

5.1.2* The provisions of this chapter shall relate to the control of hazards of fire involving liquids.

5.1.3 Provisions of this chapter shall not prohibit the use of movable tanks in conjunction with the dispensing of flammable or combustible liquids into fuel tanks of motorized equipment outside on premises not accessible to the public. Such uses shall only be made with the approval of the authority having jurisdiction.

5.2 General.

5.2.1 Liquid processing operations shall be located and operated so that they do not constitute a significant fire or explosion hazard to life, to property of others, or to important buildings or facilities within the same plant. Specific requirements shall be dependent on the inherent risk in the operations themselves, including the liquids being processed, operating temperatures and pressures, and the capability to control any liquid or vapor releases or fire incidents that could occur. The interrelationship of the many factors involved shall be based on good engineering and management practices to establish suitable physical and operating requirements.

5.2.2 Requirements for specific operations shall be covered in Sections 5.5 through 5.8 and Sections 5.10 and 5.11. Requirements for procedures and practices for fire prevention, fire protection, and fire control in these operations shall be covered in Sections 5.9 through 5.12 and shall be applied as appropriate.

5.3 Facility Design.

5.3.1 Scope. This section shall apply to operations where the handling and use of liquids is a principal activity. This section shall not apply to operations where the handling and use of liquids is incidental to the principal activity. (See Section 5.5.)

5.3.2 Location. Liquid processing vessels and equipment shall be located in accordance with the requirements of this subsection.

5.3.2.1 Processing vessels and buildings containing such processing vessels shall be located so that a fire involving the vessels does not constitute an exposure hazard to other occupancies. The minimum distance of a processing vessel to a property line that is or can be built upon, including the opposite side of a public way, to the nearest side of a public way, or to the nearest important building on the same property shall be as follows:

- (1) In accordance with Table 5.3.2.1
- (2) Determined by an engineering evaluation of the process, followed by application of sound fire protection and process engineering principles

Exception: Where process vessels are located in a building and the exterior wall facing the exposure (line of adjoining property that is or can be built upon or nearest important building on the same property) is greater than 25 ft (7.6 m) from the exposure and is a blank wall having a fire resistance rating of not less than 2 hours, any greater distances required by Table 5.3.2.1 shall be permitted to be waived.

If the exterior wall is a blank wall having a fire resistance rating of not less than 4 hours, all distances required by Table 5.3.2.1 shall be permitted to be waived.

5.3.2.2 Where Class IA liquids or unstable liquids, regardless of class, are handled or processed, the exposing walls shall have explosion resistance in accordance with good engineering practice. (See 5.3.3.7 for information on explosion relief of other building walls.)

5.3.2.3* Other liquid-processing equipment, such as pumps, heaters, filters, and exchangers, shall not be located closer than 25 ft (7.6 m) to property lines where the adjoining property is or can be built upon or to the nearest important building on the same property that is not an integral part of the process. This spacing requirement shall be permitted to be waived where exposures are protected as outlined in 5.3.2.1.

5.3.2.4 Processing equipment in which unstable liquids are handled shall be separated from unrelated plant facilities that use or handle liquids by either 25-ft (7.6-m) clear spacing or a wall having a fire resistance rating of not less than 2 hours. The wall shall also have explosion resistance in accordance with good engineering practice.

5.3.2.5 Each process unit or building containing liquid-processing equipment shall be accessible from at least one side for fire fighting and fire control.

Table 5.3.2.1 Location of Processing Vessels from Property Lines and Nearest Important Building on the Same Property Where Protection for Exposures Is Provided

Vessel Maximum Operating Liquid Capacity (gal)	Minimum Distance from Property Line that Is or Can Be Built Upon, Including Opposite Side of Public Way (ft)				Minimum Distance from Nearest Side of Any Public Way or from Nearest Important Building on Same Property that Is Not an Integral Part of the Process (ft)			
	Stable Liquid Emergency Relief		Unstable Liquid Emergency Relief		Stable Liquid Emergency Relief		Unstable Liquid Emergency Relief	
	Not Over 2.5 psig	Over 2.5 psig	Not Over 2.5 psig	Over 2.5 psig	Not Over 2.5 psig	Over 2.5 psig	Not Over 2.5 psig	Over 2.5 psig
275 or less	5	10	15	20	5	10	15	20
276 to 750	10	15	25	40	5	10	15	20
751 to 12,000	15	25	40	60	5	10	15	20
12,001 to 30,000	20	30	50	80	5	10	15	20
30,001 to 50,000	30	45	75	120	10	15	25	40
50,001 to 100,000	50	75	125	200	15	25	40	60
Over 100,000	80	120	200	300	25	40	65	100

For SI units, 1 gal = 3.8 L; 1 ft = 0.3 m; 1 psig = a gauge pressure of 6.9 kPa.

Note: Double all of above distances where protection for exposures is not provided.

5.3.3 Construction.

5.3.3.1* Process buildings or structures used for liquid operations shall be constructed consistent with the operations being conducted and with the classes of liquids handled. The construction of process buildings or structures and of buildings in which liquids are handled shall meet the requirements of Table 5.3.3.1.

Exception No. 1: Buildings or structures used solely for the blending, mixing, or dispensing of Class IIIB liquids at temperatures below their flash points shall be permitted to be constructed of combustible construction, subject to the approval of the authority having jurisdiction.

Exception No. 2: Buildings or structures used for processing or handling of liquids that are protected with either automatic sprinklers or equivalent fire protection systems shall be permitted to be constructed of combustible construction, subject to the approval of the authority having jurisdiction.

Exception No. 3: Buildings or structures used for processing or handling of liquids that are not protected with either automatic sprinklers or equivalent fire protection systems, but where the quantities of liquids do not exceed 360 gal (1360 L) of Class I and Class II liquids and 720 gal (2725 L) of Class III liquids, shall be permitted to be constructed of combustible construction, subject to the approval of the authority having jurisdiction.

Table 5.3.3.1 Construction of Buildings or Structures Used for Liquid Handling and Operations¹

Liquid Class	Distance to Adjacent Property Line that Is or Can Be Built Upon (ft)	Distance to Street, Alley, or Public Way (ft)	Minimum Type Construction ²
Class I liquids, unstable liquid of any class, and liquids of any class heated above their flash points	50	10	II (000)
	25	5	II (111)
	10	5	II (222)
Class II	25	5	II (000)
	10	5	II (111)
Class III	10	5	II (000)

For SI units, 1 ft = 0.3 m.

¹Distances apply to properties that have protection for exposures, as defined in this code. If there are exposures for which protection does not exist, the distances shall be doubled.

²Construction types are defined in NFPA 220, *Standard on Types of Building Construction*.

5.3.3.2* Load-bearing building supports and load-bearing supports of vessels and equipment capable of releasing appreciable quantities of liquids so as to result in a fire of sufficient intensity and duration to cause substantial property damage shall be protected by one or more of the following:

- (1) Drainage to a safe location to prevent liquids from accumulating under vessels or equipment

- (2) Fire-resistive construction
- (3) Fire-resistant protective coatings or systems
- (4) Water spray systems designed and installed in accordance with NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*
- (5) Other alternate means acceptable to the authority having jurisdiction

5.3.3.3 Class I liquids shall not be handled or used in basements. Where Class I liquids are handled or used above grade within buildings with basements or closed pits into which flammable vapors can travel, such belowgrade areas shall be provided with mechanical ventilation designed to prevent the accumulation of flammable vapors. Means shall be provided to prevent liquid spills from running into basements.

5.3.3.4* Provision for smoke and heat venting shall be permitted to assist access for fire fighting.

5.3.3.5* Areas shall have exit facilities arranged to prevent occupants from being trapped in the event of fire. Exits shall not be exposed by the drainage facilities described in 5.3.5.

5.3.3.6 Adequate aisles shall be maintained for unobstructed movement of personnel and fire protection equipment.

5.3.3.7* Areas where Class IA or unstable liquids are processed shall have explosion venting through one or more of the following methods:

- (1) Open air construction
- (2) Lightweight walls and/or roof
- (3) Lightweight wall panels and roof hatches
- (4) Windows of explosion-venting type

5.3.4 Ventilation.

5.3.4.1 Enclosed processing areas handling or using Class I liquids or Class II or Class III liquids, heated to temperatures at or above their flash points, shall be ventilated at a rate sufficient to maintain the concentration of vapors within the area at or below 25 percent of the lower flammable limit. Compliance with 5.3.4.2 through 5.3.4.5 shall be deemed as meeting the requirements of 5.3.4.1.

5.3.4.2* Ventilation requirements shall be confirmed by one of the following:

(a) Calculations based on the anticipated fugitive emissions (*see Appendix F for calculation method*).

(b) Sampling of the actual vapor concentration under normal operating conditions. The sampling shall be conducted at a 5-ft (1.5-m) radius from each potential vapor source extending to or toward the bottom and the top of the enclosed processing area. The vapor concentration used to determine the required ventilation rate shall be the highest measured concentration during the sampling procedure.

Exception: Where a ventilation rate of not less than 1 ft³/min/ft² (0.3 m³/min/m²) of solid floor area is provided, the above ventilation confirmation requirement shall not apply.

5.3.4.3 Ventilation shall be accomplished by mechanical or natural exhaust ventilation. Exhaust ventilation discharge shall be to a safe location outside the building, without recirculation of the exhaust air.

Exception: Recirculation is permitted where it is monitored continuously using a fail-safe system that is designed to automatically sound an alarm, stop recirculation, and provide full exhaust to the outside

in the event that vapor-air mixtures in concentrations over one-fourth of the lower flammable limit are detected.

5.3.4.4* Provision shall be made for introduction of make-up air in such a manner as to avoid short-circuiting the ventilation. Ventilation shall be arranged to include all floor areas or pits where flammable vapors can collect. Local or spot ventilation to control special fire or health hazards, if provided, shall be permitted to be utilized for up to 75 percent of the required ventilation.

5.3.4.5 Equipment such as dispensing stations, open centrifuges, plate and frame filters, and open vacuum filters used in a building and the ventilation of the building shall be designed to limit flammable vapor-air mixtures under normal operating conditions to the interior of equipment and to not more than 5 ft (1.5 m) from equipment that exposes Class I liquids to the air.

5.3.5 Drainage.

5.3.5.1* Emergency drainage systems shall be provided to direct liquid leakage and fire protection water to a safe location.

5.3.5.2 Emergency drainage systems, if connected to public sewers or discharged into public waterways, shall be equipped with traps or separators.

5.3.5.3 A facility shall be designed and operated to prevent the discharge of liquids to public waterways, public sewers, or adjoining property.

5.3.6 Electrical Equipment. Electrical wiring and utilization equipment shall meet the requirements of Section 5.9.

5.3.7 Liquid Handling, Transfer, and Use.

5.3.7.1 Class I liquids shall be kept in closed tanks or containers when not actually in use. Class II and Class III liquids shall be kept in closed tanks or containers when ambient or process temperature is at or above their flash point.

5.3.7.2 Where liquids are used or handled, provisions shall be made to promptly and safely dispose of leakage or spills.

5.3.7.3 Class I liquids shall not be used outside closed systems where there are open flames or other ignition sources within the classified areas set forth in Chapter 6.

5.3.7.4 Transfer of liquids among vessels, containers, tanks, and piping systems by means of air or inert gas pressure shall be permitted only under all of the following conditions:

- (1) The vessels, containers, tanks, and piping systems shall be designed for such pressurized transfer and shall be capable of withstanding the anticipated operating pressure.
- (2) Safety and operating controls, including pressure relief devices, shall be provided to prevent overpressure of any part of the system.
- (3) Only inert gas shall be used to transfer Class I liquids. Inert gas shall be used to transfer Class II and Class III liquids that are heated above their flash points.

5.3.7.5 Positive displacement pumps shall be provided with pressure relief discharging back to the tank, pump suction, or other suitable location or shall be provided with interlocks to prevent overpressure.

5.3.7.6 Piping, valves, and fittings shall be in accordance with Chapter 3.

5.3.7.7 Listed flexible connectors shall be permitted to be used where vibration exists. Approved hose shall be permitted to be used at transfer stations.

5.3.7.8* The staging of liquids in containers, intermediate bulk containers, and portable tanks shall be limited to the following:

- (1) Containers, intermediate bulk containers, and portable tanks that are in use
- (2) Containers, intermediate bulk containers, and portable tanks that were filled during a single shift
- (3) Containers, intermediate bulk containers, and portable tanks needed to supply the process for one continuous 24-hour period
- (4) Containers, intermediate bulk containers, and portable tanks that are stored in accordance with Chapter 4.

5.3.7.9 Intermediate bulk containers and portable tanks that contain Class I, Class II, or Class IIIA liquids used in a process and staged in the process area shall not be filled in the process area.

Exception No. 1: Intermediate bulk containers and portable tanks that meet the requirements of Chapter 2.

Exception No. 2: Intermediate products that are manufactured in the process area.

5.3.8* Equipment. Equipment shall be designed and arranged to prevent the unintentional escape of liquids and vapors and to minimize the quantity escaping in the event of accidental release.

5.4 Recirculating Heat Transfer Systems.

5.4.1 Scope. This section shall apply only to recirculating heat transfer systems that use a heat transfer fluid (HTF) that is heated up to or above its flash point under normal operation.

Exception: This section shall not apply to process streams or to any system of 60 gal (227 L) capacity or less.

5.4.2* General Requirements. A heater or vaporizer for heat transfer fluid that is located inside a building shall meet all applicable requirements of 5.3.2 through 5.3.8.

5.4.3* System Design.

5.4.3.1* Drainage shall be provided at strategic low points in the heat transfer system. Drains shall be piped to a safe location that is capable of accommodating the total capacity of the system or the capacity of that part of the system that is isolated.

5.4.3.2* Where the heat transfer system expansion tank is located above floor level and has a capacity of more than 250 gal (950 L), it shall be provided with a low-point drain line that can allow the expansion tank to drain to a drain tank on a lower level. The drain line valve shall be operable from a safe location.

5.4.3.3 A heat transfer fluid system shall not be used to provide direct building heat.

5.4.3.4 All pressure relief device outlets shall be piped to a safe location.

5.4.4* Fuel Burner Controls and Interlocks. Oil- or gas-fired heaters or vaporizers shall be designed and installed in accordance with the applicable requirements of NFPA 31, *Standard for the Installation of Oil-Burning Equipment*, or NFPA 8501, *Standard for Single Burner Boiler Operation*, whichever is applicable. Wood dust suspension-fired heaters or vaporizers shall be designed and installed in accordance with the applicable requirements of NFPA 8503, *Standard for Pulverized Fuel Systems*.

5.4.5 Piping.

5.4.5.1* Piping shall meet all applicable requirements of Chapter 3.

5.4.5.2 All pipe connections shall be welded. Welded threaded connections shall be permitted to be used for piping 2 in. and smaller.

Exception: Mechanical joints shall be permitted to be used at pump, valve, and equipment connections.

5.4.5.3 Existing and new piping that is insulated shall use closed-cell, nonabsorbent insulation.

Exception: Where all pipe joints are welded and where there are no other points in the system subject to leakage, such as at valves or pumps, other types of insulation shall be permitted.

5.4.6 Fire Protection.

5.4.6.1* Automatic sprinkler protection meeting the requirements of NFPA 13, *Standard for the Installation of Sprinkler Systems*, for Extra Hazard (Group I) Occupancies shall be provided for building areas containing a heat transfer system heater or vaporizer.

5.4.6.2 An alternate fire protection system shall be permitted to be used, if approved by the authority having jurisdiction. Such alternate system shall be designed and installed in accordance with the appropriate NFPA standard and with manufacturer's recommendations for the system selected.

5.4.7 Operation.

5.4.7.1* Operations involving heat transfer fluid systems and equipment shall be reviewed to ensure that the fire and explosion hazards resulting from loss of containment of the fluid or failure of the system are provided with corresponding fire prevention and emergency action plans.

5.4.7.2 Operators of heat transfer systems shall be trained in the hazards of system misoperation and leakage and shall be trained to recognize upset conditions that can lead to dangerous situations.

5.4.7.3 Safety interlocks shall be inspected, calibrated, and tested annually or at other intervals established in accordance with other appropriate standards to determine that they are in proper operating condition.

5.5 Incidental Operations.

5.5.1* This section shall apply to areas where the use, handling, and storage of liquids is only a limited activity to the established occupancy classification.

5.5.2 Class I liquids or Class II or Class III liquids that are heated up to or above their flash points shall be drawn from or transferred into vessels, containers, or portable tanks as follows:

- (1) From original shipping containers with a capacity of 5 gal (19 L) or less
- (2) From safety cans
- (3) Through a closed piping system
- (4) From portable tanks or containers by means of a device that has antisiphoning protection and that draws through an opening in the top of the tank or container
- (5) By gravity through a listed self-closing valve or self-closing faucet

5.5.2.1 If hose is used in the transfer operation, it shall be equipped with a self-closing valve without a hold-open latch

in addition to the outlet valve. Only listed or approved hose shall be used.

5.5.2.2 Means shall be provided to minimize generation of static electricity. Such means shall meet the requirements of 5.9.4.

5.5.2.3 Where pumps are used for liquid transfer, means shall be provided to deactivate liquid transfer in the event of a liquid spill or fire.

5.5.3 All storage of liquids shall comply with Chapter 4.

Exception: As provided in 5.5.4 and 5.5.5.

5.5.4 The quantity of liquid located outside of identified storage areas, such as storage cabinets, other inside liquid storage areas, general-purpose warehouses, or other specific processing areas that are cut off from the general plant area by at least a 2-hour fire separation, shall meet the requirements of 5.5.4.1.

5.5.4.1 The aggregate of the sum of all incidental operations in each single fire area shall not exceed the sum of the following:

- (1) 25 gal (95 L) of Class IA liquids in containers
- (2) 120 gal (454 L) of Class IB, Class IC, Class II, or Class III liquids in containers
- (3) Two portable tanks each not exceeding 660 gal (2498 L) of Class IB, Class IC, Class II, or Class IIIA liquids
- (4) 20 portable tanks each not exceeding 660 gal (2498 L) of Class IIIB liquids

Exception: Where quantities of liquid in excess of the above limits are needed to supply an incidental operation for one continuous 24-hour period, that greater quantity shall be allowed.

5.5.4.2 Where quantities of liquids in excess of the limits in 5.5.4.1 are necessary, storage shall be in tanks that meet all applicable requirements of Chapter 2 and Section 5.3.

5.5.5 Areas in which liquids are transferred from one tank or container to another container shall be provided with the following:

- (1) Separation from other operations that can represent an ignition source by distance or by fire-resistant construction
- (2) Drainage or other means to control spills
- (3)* Natural or mechanical ventilation that meets the requirements of 5.3.4

5.6 Loading and Unloading Operations and Facilities.

5.6.1 This section shall apply to operations involving the loading or unloading of tank cars and tank vehicles and the areas in facilities where these operations are conducted.

5.6.2 Bonding requirements, as specified as follows, shall not be required:

- (1) Where tank cars and tank vehicles are loaded exclusively with products that do not have static-accumulating properties, such as asphalts (including cutback asphalts), most crude oils, residual oils, and water-soluble liquids
- (2) Where no Class I liquids are handled at the loading facility and where the tank cars and tank vehicles loaded are used exclusively for Class II and Class III liquids
- (3) Where tank cars and tank vehicles are loaded or unloaded through closed connections

5.6.3* Tank vehicle and tank car loading and unloading facilities shall be separated from aboveground tanks, warehouses, other plant buildings, or the nearest line of adjoining property that can be built upon by a distance of at least 25 ft (7.6 m) for

Class I liquids and at least 15 ft (4.6 m) for Class II and Class III liquids, measured from the nearest fill spout or transfer connection. These distances shall be permitted to be reduced if there is suitable protection for exposures. Buildings for pumps or shelters for personnel shall be permitted to be a part of the facility.

5.6.4* Loading and unloading facilities shall be provided with drainage systems or other means to contain spills.

5.6.5 A loading or unloading facility that has a canopy or roof that does not limit the dissipation of heat or dispersion of flammable vapors and does not restrict fire-fighting access and control shall be treated as an outdoor facility.

5.6.6* Loading and unloading facilities that are used to load liquids into tank vehicles through open domes shall be provided with a means for electrically bonding to protect against static electricity hazards. Such means shall consist of a metallic bond wire that is permanently electrically connected to the fill pipe assembly or to some part of the rack structure that is in electrical contact with the fill pipe assembly. The free end of this wire shall be provided with a clamp or an equivalent device for convenient attachment to some metallic part that is in electrical contact with the cargo tank of the tank vehicle. All parts of the fill pipe assembly, including the drop tube, shall form a continuous electrically conductive path.

5.6.7 Tank car facilities where flammable and combustible liquids are loaded or unloaded through open domes shall be protected against stray currents by permanently bonding the fill pipe to at least one rail and to the facility structure, if of metal. Multiple pipelines that enter the area shall be permanently bonded together. In addition, in areas where excessive stray currents are known to exist, all pipelines entering the area shall be provided with insulating sections to electrically isolate them from the facility piping.

Exception: These precautions shall not be required where only Class II or Class III liquids are handled and where there is no probability that tank cars will contain vapors from previous cargoes of Class I liquids.

5.6.8 Equipment such as piping, pumps, and meters used for the transfer of Class I liquids between storage tanks and the fill stem of the loading facility shall not be used for the transfer of Class II or Class III liquids.

Exception No. 1: This provision shall not apply to water-miscible liquid mixtures where the class of the mixture is determined by the concentration of liquid in water.

Exception No. 2: This provision shall not apply where the equipment is cleaned between transfers.

5.6.9 Remote pumps located in underground tanks shall have a listed leak detection device installed on the pump discharge side that will indicate if the piping system is not essentially liquidtight. This device shall be checked and tested at least annually according to the manufacturer's specifications to ensure proper installation and operation.

5.6.10 Loading and Unloading of Tank Vehicles.

5.6.10.1 Liquids shall be loaded only into cargo tanks whose material of construction is compatible with the chemical characteristics of the liquid. The liquid being loaded shall also be chemically compatible with the liquid hauled on the previous load unless the cargo tank has been cleaned.

5.6.10.2 Before loading tank vehicles through open domes, a bonding connection shall be made to the vehicle or tank

before dome covers are raised and shall remain in place until filling is completed and all dome covers have been closed and secured.

Exception: As modified by 5.6.2.

5.6.10.3 When transferring Class I liquids, engines of tank vehicles or motors of auxiliary or portable pumps shall be shut down during making and breaking hose connections. If loading or unloading is done without requiring the use of the motor of the tank vehicle, the motor shall be shut down throughout any transfer operations involving Class I liquids.

5.6.10.4* Filling through open domes into the tank cars that contain vapor-air mixtures within the flammable range or where the liquid being filled can form such a mixture shall be by means of a downspout that extends to within 6 in. (150 mm) of the bottom of the tank. This precaution shall not be required when loading liquids that are not accumulators of static electric charges.

5.6.10.5 When top loading a tank vehicle with Class I or Class II liquids without a vapor control system, valves used for the final control of flow shall be of the self-closing type and shall be manually held open except where automatic means are provided for shutting off the flow when the vehicle is full. Automatic shutoff systems shall be provided with a manual shutoff valve located at a safe distance from the loading nozzle to stop the flow if the automatic system fails. When top loading a tank vehicle with vapor control, flow control shall be in accordance with 5.6.10.7 and 5.6.10.8.

5.6.10.6 When bottom loading a tank vehicle, a positive means shall be provided for loading a predetermined quantity of liquid, together with a secondary automatic shutoff control to prevent overfill. The connecting components between the loading rack and the tank vehicle that are required to operate the secondary control shall be functionally compatible. The connection between the liquid loading hose or pipe and the truck piping shall be by means of a dry disconnect coupling.

5.6.10.7 When bottom loading a tank vehicle that is equipped for vapor control, but when vapor control is not used, the tank shall be vented to the atmosphere, at a height not lower than the top of the cargo tank of the vehicle, to prevent pressurization of the tank. Connections to the facility's vapor control system shall be designed to prevent the escape of vapor to the atmosphere when not connected to a tank vehicle.

5.6.10.8 When bottom loading is used, reduced flow rates (until the fill opening is submerged), splash deflectors, or other devices shall be used to prevent splashing and to minimize turbulence.

5.6.10.9 Metal or conductive objects, such as gauge tapes, sample containers, and thermometers, shall not be lowered into or suspended in a compartment while the compartment is being filled or immediately after cessation of pumping to permit the relaxation of charge.

5.6.11 Loading and Unloading of Tank Cars.

5.6.11.1 Liquids shall be loaded only into tank cars whose material of construction is compatible with the chemical characteristics of the liquid. The liquid being loaded shall also be chemically compatible with the liquid hauled on the previous load unless the tank car has been cleaned.

5.6.11.2* Filling through open domes into the tanks of tank vehicles that contain vapor-air mixtures within the flammable

range, or where the liquid being filled can form such a mixture, shall be by means of a downspout that extends to within 6 in. (150 mm) of the bottom of the tank. This precaution shall not be required when loading liquids that are not accumulators of static electric charges.

5.6.11.3 When bottom loading is used, reduced flow rates (until the fill opening is submerged), splash deflectors, or other devices shall be used to prevent splashing and to minimize turbulence.

5.6.11.4 Metal or conductive objects, such as gauge tapes, sample containers, and thermometers, shall not be lowered into or suspended in a compartment while the compartment is being filled or immediately after cessation of pumping to permit the relaxation of charge.

5.6.12* Switch Loading. To prevent hazards due to a change in flash point of liquids, no tank car or tank vehicle that has previously contained a Class I liquid shall be loaded with a Class II or Class III liquid unless proper precautions are taken.

5.7 Wharves.

5.7.1 This section shall apply to all wharves as defined in Section 1.6 whose primary purpose is the bulk transfer of liquids. General-purpose wharves that handle bulk transfer of liquids and other commodities shall meet the requirements of NFPA 307, *Standard for the Construction and Fire Protection of Marine Terminals, Piers, and Wharves*.

5.7.2 This section shall not apply to the following:

- (1) Marine service stations, as covered in NFPA 30A, *Code for Motor Fuel Dispensing Facilities and Repair Garages*
- (2) Marinas and boatyards, as covered in NFPA 303, *Fire Protection Standard for Marinas and Boatyards*
- (3) Wharves that handle liquefied petroleum gases, as covered in NFPA 59A, *Standard for the Production, Storage, and Handling of Liquefied Natural Gas (LNG)*, and NFPA 58, *Liquefied Petroleum Gas Code*

5.7.3 Incidental handling of packaged cargo of liquids and loading/unloading of general cargo, such as ships' stores, during transfer of liquids shall be conducted only when approved by the wharf supervisor and the senior officer of the vessel.

5.7.4 Wharves at which liquid cargoes are to be transferred in bulk to or from tank vessels shall be at least 100 ft (30 m) from any bridge over a navigable waterway or from any entrance to or superstructure of a vehicular or railroad tunnel under a waterway. The termination of the loading or unloading fixed piping shall be at least 200 ft (60 m) from any bridge or from any entrance to or superstructure of a tunnel.

5.7.5 The substructure and deck of the wharf shall be substantially designed for the use intended. The deck shall be permitted to be of any material that will afford the desired combination of flexibility, resistance to shock, durability, strength, and fire resistance. Heavy timber construction shall be permitted.

5.7.6 Tanks used exclusively for ballast water or Class II or Class III liquids shall be permitted to be installed on a suitably designed wharf.

5.7.7 Loading pumps capable of building up pressures that exceed the safe working pressure of cargo hose or loading arms shall be provided with bypasses, relief valves, or other arrangements to protect the loading facilities against excessive pressure.

Relief devices shall be tested at least annually to determine that they function satisfactorily at their set pressure.

5.7.8 All pressure hoses and couplings shall be inspected at intervals appropriate to their service. With the hose extended, the hose and couplings shall be tested using the in-service maximum operating pressure. Any hose showing material deterioration, signs of leakage, or weakness in its carcass or at the couplings shall be withdrawn from service and repaired or discarded.

5.7.9 Piping, valves, and fittings shall meet applicable requirements of Chapter 3 and shall also meet the following requirements:

(a) Flexibility of piping shall be assured by appropriate layout and arrangement of piping supports so that motion of the wharf structure resulting from wave action, currents, tides, or the mooring of vessels will not subject the piping to excessive strain.

(b) Pipe joints that depend on the friction characteristics of combustible materials or on the grooving of pipe ends for mechanical continuity of piping shall not be permitted.

(c) Swivel joints shall be permitted to be used in piping to which hoses are connected and for articulated swivel-joint transfer systems, provided the design is such that the mechanical strength of the joint will not be impaired if the packing materials should fail, for example, by exposure to fire.

(d) Each line conveying Class I or Class II liquids leading to a wharf shall be provided with a readily accessible block valve located on shore near the approach to the wharf and outside of any diked area. Where more than one line is involved, the valves shall be grouped in one location.

(e) Means shall be provided for easy access to any cargo line valves that are located below the wharf deck.

5.7.10 Pipelines on wharves that handle Class I or Class II liquids shall be adequately bonded and grounded. If excessive stray currents are encountered, insulating flanges or joints shall be installed. Bonding and grounding connections on all pipelines shall be located on the wharf side of insulating flanges, if used, and shall be accessible for inspection. Bonding between the wharf and the vessel shall not be required.

5.7.11 Hose or articulated swivel-joint pipe connections used for cargo transfer shall be capable of accommodating the combined effects of change in draft and change in tide. Mooring lines shall be kept adjusted to prevent surge of the vessel from placing stress on the cargo transfer system. Hose shall be supported to avoid kinking and damage from chafing.

5.7.12 Material shall not be placed on wharves in such a manner as to obstruct access to fire-fighting equipment or important pipeline control valves. Where the wharf is accessible to vehicle traffic, an unobstructed roadway to the shore end of the wharf shall be maintained for access of fire-fighting apparatus.

5.7.13 Loading or unloading shall not commence until the wharf supervisor and the person in charge of the tank vessel agree that the tank vessel is properly moored and all connections are properly made.

5.7.14 Mechanical work shall not be performed on the wharf during cargo transfer, except under special authorization based on a review of the area involved, methods to be employed, and precautions necessary.

5.7.15 Sources of ignition shall be controlled during transfer of liquids. Mechanical work, including but not limited to

vehicular traffic, welding, grinding, and other hot work, shall not be performed during cargo transfer except as authorized by the wharf supervisor and the senior officer on the vessel. Smoking shall be prohibited at all times on the wharf during cargo transfer operations.

5.7.16 For marine terminals handling flammable liquids, Figure 5.7.16 shall be used to determine the extent of classified areas for the purpose of installation of electrical equipment.

5.7.17 Where a flammable atmosphere can exist in the vessel cargo compartment, cargo transfer systems shall be designed to limit the velocity of the incoming liquid stream to 3 ft (0.9 m) per second until the compartment inlet opening is sufficiently submerged to prevent splashing.

5.7.18 Filters, pumps, wire screens, and other devices that can produce static electric charges through turbulence shall be so located to allow a minimum of 30 seconds relaxation time prior to discharging cargo into the compartment.

5.7.19* Spill collection shall be provided around manifold areas to prevent spread of liquids to other areas of the wharf or under the wharf. Vapor seals shall be provided on all drain lines leaving the wharf.

5.7.20 Where required, wharves shall have a system to isolate and shut down the loading operation in the event of failure of a hose, loading arm, or manifold valve. This system shall meet all of the following requirements:

(a) If the protective system closes a valve on a gravity-fed or pipeline-fed loading system, care shall be taken to ensure the line is protected from any resulting pressure surges.


(b) Emergency shutdown systems shall be permitted to be automatically or manually activated. Manually activated device(s) shall be well marked and accessible during an emergency.

5.7.21* Fire protection for wharves shall be related to the products being handled, emergency response capability, size, location, frequency of use, and adjacent exposures.

5.7.21.1 Where a fire water main is provided, the main shall be permitted to be wet or dry. In all cases, isolation valves and fire department connections shall be provided at the wharf-to-shore connection.

5.7.21.2 Where a fire water main is provided, hydrants and monitors shall be provided so that effective fire water streams can be applied to any berth or loading manifold from two directions.

FIGURE 5.7.16 Marine terminal handling flammable liquids.



For SI units, 1 in. = 25 mm; 1 ft = 0.3 m.

Division 1 Division 2 Nonclassified

Notes:

- The "source of vapor" is the operating envelope and stored position of the outboard flange connection of the loading arm (or hose).
- The berth area adjacent to tanker and barge cargo tanks is to be Division 2 to the following extent:
 - 25 ft (7.6 m) horizontally in all directions on the pier side from the portion of the hull containing cargo tanks.
 - From the water level to 25 ft (7.6 m) above the cargo tanks at their highest position.
- Additional locations can be classified as required by the presence of other sources of flammable liquids on the berth, or by Coast Guard or other regulations.

5.7.21.3 Fire water pumps, fire hoses, fire water mains, foam systems, and other fire suppression equipment shall be maintained and tested in accordance with NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*.

5.7.21.4 Where no fire water main is provided, at least two 150-lb (68-kg) dry chemical extinguishers shall be provided. The extinguishers shall be located within 50 ft (15 m) of pump or manifold areas and shall be easily reached along emergency access paths.

5.8 Reserved.

5.9 Control of Ignition Sources.

5.9.1 General. Precautions shall be taken to prevent the ignition of flammable vapors by sources such as the following:

- (1) Open flames
- (2) Lightning
- (3) Hot surfaces
- (4) Radiant heat
- (5) Smoking
- (6) Cutting and welding
- (7) Spontaneous ignition
- (8) Frictional heat or sparks
- (9) Static electricity
- (10) Electrical sparks
- (11) Stray currents
- (12) Ovens, furnaces, and heating equipment

5.9.2 Smoking. Smoking shall be permitted only in designated and properly identified areas.

5.9.3* Hot Work. Welding, cutting, and similar spark-producing operations shall not be permitted in areas containing flammable liquids until a written permit authorizing such work has been issued. The permit shall be issued by a person in authority following his/her inspection of the area to assure that proper precautions have been taken and will be followed until the job is completed.

5.9.4* Static Electricity. All equipment such as tanks, machinery, and piping shall be designed and operated to prevent electrostatic ignitions.

All metallic equipment such as tanks, machinery, and piping where an ignitable mixture could be present shall be bonded or grounded. The bond or ground or both shall be physically applied or shall be inherently present by the nature of the installation. Any electrically isolated section of metallic piping or equipment shall be bonded or grounded to prevent hazardous accumulation of static electricity.

Nonmetallic equipment and piping shall be designed to provide equivalent safeguards against static electricity.

5.9.5 Electrical Installations. Electrical equipment and wiring installations shall be in accordance with Chapter 6.

5.10 Vapor Recovery and Vapor Processing Systems.

5.10.1 Scope.

5.10.1.1 This section shall apply to vapor recovery and vapor processing systems where the vapor source operates at pressures from vacuum up to and including 1 psig (gauge pressure of 6.9 kPa), or where there is a potential for vapor mixtures in the flammable range.

5.10.1.2 This section shall not apply to the following:

- (1) Marine systems that comply with U.S. DOT Regulations, 33 *CFR* 154, 155, and 156, and U.S. Coast Guard Regulations, 46 *CFR* 30, 32, 35, and 39
- (2) Marine and automotive service station systems that comply with NFPA 30A, *Code for Motor Fuel Dispensing Facilities and Repair Garages*

5.10.2 Overpressure/Vacuum Protection. Tanks and equipment shall have independent venting for overpressure or vacuum conditions that could occur from malfunction of the vapor recovery or vapor processing system.

Exception: For tanks, venting shall comply with 2.2.5.

5.10.3 Vent Location.

5.10.3.1 Vents on vapor processing systems shall be not less than 12 ft (3.6 m) from adjacent ground level, with outlets located and directed so that ignitable vapors will disperse to a concentration below the lower flammable limit before reaching any location that could contain an ignition source.

5.10.3.2 Vapor processing equipment and vents shall be located in accordance with 5.3.2.

5.10.4 Vapor Collection Systems.

5.10.4.1 Vapor collection piping shall be designed to prevent trapping liquid.

5.10.4.2 Vapor recovery and vapor processing systems that are not designed to handle liquid shall be provided with a means to eliminate any liquid that carries over to or condenses in the vapor collection system.

5.10.5* Liquid Level Monitoring.

5.10.5.1 A liquid knock-out vessel used in the vapor collection system shall have means to verify the liquid level and a high liquid level sensor that activates an alarm.

5.10.5.2 For unmanned facilities, the high liquid level sensor shall initiate shutdown of liquid transfer into the vessel and shutdown of vapor recovery or vapor processing systems.

5.10.6 Overfill Protection.

5.10.6.1 Storage tanks served by vapor processing or vapor recovery systems shall be equipped with overfill protection in accordance with Section 2.6.1.

5.10.6.2 Overfill protection of tank vehicles shall be in accordance with 5.6.10.5 through 5.6.10.7.

5.10.7 Sources of Ignition.

5.10.7.1 Vapor Release. Tank or equipment openings provided for purposes of vapor recovery shall be protected against possible vapor release in accordance with 2.3.3.4.6, 5.6.10.6, and 5.6.10.7.

5.10.7.2* Electric. Electrical area classification shall be in accordance with Chapter 6.

5.10.7.3* Static Electricity. Vapor collection and vapor processing equipment shall be protected against static electricity in accordance with 5.9.4.

5.10.7.4* Spontaneous Ignition. Where there is the potential for spontaneous ignition, precautions shall be taken either by design or written procedures to prevent ignition.

5.10.7.5* Friction Heat or Sparks from Mechanical Equipment. Mechanical equipment used to move vapors that are in the flammable range shall be designed to prevent sparks or other ignition sources under both normal and equipment malfunction conditions.

5.10.7.6* Flame Propagation. Where there is reasonable potential for ignition of a vapor mix in the flammable range, means shall be provided to stop the propagation of flame through the vapor collection system. The means chosen shall be appropriate for the conditions under which they will be used.

5.10.7.7 Explosion Protection. Where used, explosion protection systems shall comply with NFPA 69, *Standard on Explosion Prevention Systems*.

5.10.8 Emergency System Shutdown. Emergency shutdown systems shall be designed to fail to a safe position in the event of loss of normal system power (i.e., air or electric) or equipment malfunction.

5.11 Solvent Distillation Units.

5.11.1 Scope. This section shall apply to solvent distillation units having distillation chambers or still pots that do not exceed 60 gal (227 L) capacity and are used to recycle Class I, Class II, and Class IIIA liquids. This section shall not apply to research, testing, or experimental processes; to distillation processes carried out in petroleum refineries, chemical plants, or distilleries; or to distillation equipment used in dry cleaning operations.

5.11.2 Equipment. Solvent distillation units shall be approved or shall be listed in accordance with UL 2208, *Standard for Solvent Distillation Units*.

5.11.3 Solvents. Solvent distillation units shall only be used to distill liquids for which they have been investigated and are indicated on the unit's marking or instruction manual. Unstable or reactive liquids or materials shall not be processed unless they have been specifically indicated on the system's markings or in the instruction manual.

5.11.4 Location. Solvent distillation units shall only be used in locations in accordance with their approval or listing. They shall not be used in basements. They shall be located away from potential sources of ignition, as indicated on the unit's marking.

5.11.5 Liquid Storage. Distilled liquids and liquids awaiting distillation shall be stored in accordance with Chapters 1 through 4.

5.12 Management of Fire Hazards.

5.12.1 This section shall apply to the management methodology used to identify, evaluate, and control the hazards involved in processing and handling of flammable and combustible liquids. These hazards include, but are not limited to, preparation, separation, purification, and change of state, energy content, or composition.

5.12.2 Operations involving flammable and combustible liquids shall be reviewed to ensure that fire and explosion hazards resulting from loss of containment of liquids are provided with corresponding fire prevention and emergency action plans.

Exception No. 1: Operations where liquids are used solely for on-site consumption as fuels.

Exception No. 2: Operations where Class II or Class III liquids are stored in atmospheric tanks or transferred at temperatures below their flash points.

Exception No. 3: Mercantile occupancies, crude petroleum exploration, drillings, and well servicing operations, and normally unoccupied facilities in remote locations.

5.12.3 The extent of fire prevention and control that is provided shall be determined by means of an engineering evaluation of the operation and application of sound fire protection and process engineering principles. This evaluation shall include, but not be limited to, the following:

- (1) Analysis of the fire and explosion hazards of the operation
- (2) Analysis of emergency relief from process vessels, taking into consideration the properties of the materials used and the fire protection and control measures taken
- (3) Analysis of applicable facility design requirements in Sections 5.3 through 5.7
- (4) Analysis of applicable requirements for liquid handling, transfer, and use, as covered in Sections 5.3 through 5.7
- (5) Analysis of local conditions, such as exposure to and from adjacent properties and exposure to floods, earthquakes, and windstorms
- (6) Analysis of the emergency response capabilities of the local emergency services

5.12.4 A written emergency action plan that is consistent with available equipment and personnel shall be established to respond to fires and related emergencies. This plan shall include the following:

- (a) Procedures to be followed in case of fire, such as sounding the alarm, notifying the fire department, evacuating personnel, and controlling and extinguishing the fire.
- (b) Procedures and schedules for conducting drills of these procedures.
- (c) Appointment and training of personnel to carry out assigned duties. These duties shall be reviewed at the time of initial assignment, as responsibilities or response actions change, and whenever anticipated duties change.
- (d) Maintenance of fire protection equipment.
- (e) Procedures for shutting down or isolating equipment to reduce the release of liquid. This shall include assigning personnel responsible for maintaining critical plant functions or shutdown of plant processes.
- (f) Alternate measures for the safety of occupants.

5.12.5 The fire hazards management review conducted in accordance with 5.12.2 shall be repeated whenever the hazards leading to a fire or explosion change significantly. Conditions that might require repeating a review shall include, but are not limited to, the following:

- (1) When changes occur in the materials in process
- (2) When changes occur in process equipment
- (3) When changes occur in process control
- (4) When changes occur in operating procedures or assignments

5.13 Fire Protection and Fire Suppression.

5.13.1 General.

5.13.1.1* This section shall cover the commonly recognized management control systems and methods used to prevent or

minimize the loss from fire or explosion in liquid-processing facilities.

5.13.1.2* The authority having jurisdiction shall be consulted on specific cases or qualified engineering judgment shall be exercised.

5.13.2 Portable Fire Control Equipment.

5.13.2.1* Listed portable fire extinguishers shall be provided for facilities in such quantities, sizes, and types as could be needed for the special hazards of operation and storage.

5.13.2.2 When the need is indicated in accordance with 5.12.3, standpipe and hose systems, installed in accordance with NFPA 14, *Standard for the Installation of Standpipe, Private Hydrants, and Hose Systems*, or hose connections from sprinkler systems using combination spray and straight stream nozzles, installed in accordance with NFPA 13, *Standard for the Installation of Sprinkler Systems*, shall be used.

5.13.2.3 When the need is indicated in accordance with 5.12.3, mobile foam apparatus shall be provided.

5.13.2.4 Automotive and trailer-mounted fire apparatus, where determined necessary, shall not be used for any purpose other than fire fighting.

5.13.3 Fixed Fire Control Equipment.

5.13.3.1 A reliable water supply or other suitable fire control agent shall be available in pressure and quantity to meet the fire demands indicated by the special hazards of operation, storage, or exposure.

5.13.3.2* Hydrants, with or without fixed monitor nozzles, shall be provided in accordance with accepted practice. The number and placement shall depend on the hazard of the liquid-processing facility.

5.13.3.3* Where the need is indicated by the hazards of liquid processing, storage, or exposure as determined by 5.12.3, fixed protection shall be provided by means of approved sprinkler systems, water spray systems, deluge systems, fire-resistant materials, or a combination of these.

5.13.3.4 Where provided, fire control systems shall be designed, installed, and maintained in accordance with the following NFPA standards:

- (1) NFPA 11, *Standard for Low-Expansion Foam*
- (2) NFPA 11A, *Standard for Medium- and High-Expansion Foam Systems*
- (3) NFPA 12, *Standard on Carbon Dioxide Extinguishing Systems*
- (4) NFPA 12A, *Standard on Halon 1301 Fire Extinguishing Systems*
- (5) NFPA 16, *Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems*
- (6) NFPA 17, *Standard for Dry Chemical Extinguishing Systems*

5.13.4 Detection and Alarm.

5.13.4.1 An approved means for prompt notification of fire or emergency to those within the plant and to the available public or mutual aid fire department shall be provided.

5.13.4.2 Those areas, including buildings, where a potential exists for a flammable liquid spill shall be monitored as appropriate. Some methods shall include the following:

- (1) Personnel observation or patrol
- (2) Process-monitoring equipment that would indicate a spill or leak could have occurred

- (3) Provision of gas detectors to continuously monitor the area where facilities are unattended

5.13.5 Emergency Planning and Training.

5.13.5.1 Personnel responsible for the use and operation of fire protection equipment shall be trained in the use of that equipment. Refresher training shall be conducted at least annually.

5.13.5.2 Planning of effective fire control measures shall be coordinated with local emergency response agencies.

5.13.5.3 Procedures shall be established to provide for safe shutdown of operations under emergency conditions. Provisions shall be made for periodic training, inspection, and testing of associated alarms, interlocks, and controls.

5.13.5.4 The emergency procedure shall be kept readily available in an operating area and updated regularly.

5.13.5.5 Where premises are likely to be unattended for considerable periods of time, a summary of the emergency plan shall be posted or located in a strategic and accessible location.

5.13.6 Inspection and Maintenance.

5.13.6.1 All fire protection equipment shall be properly maintained, and periodic inspections and tests shall be done in accordance with both standard practice and the equipment manufacturer's recommendations. Water-based fire protection systems shall be inspected, tested, and maintained in accordance with NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*.

5.13.6.2 Maintenance and operating practices shall control leakage and prevent spillage of flammable liquids.

5.13.6.3 Combustible waste material and residues in operating areas shall be kept to a minimum, stored in covered metal containers, and disposed of daily.

5.13.6.4 Ground areas around facilities where liquids are stored, handled, or used shall be kept free of weeds, trash, or other unnecessary combustible materials.

5.13.6.5 Aisles established for movement of personnel shall be maintained clear of obstructions to permit orderly evacuation and ready access for manual fire-fighting activities.

Chapter 6 Electrical Equipment and Installations

6.1 Scope. This chapter shall apply to areas where Class I liquids are stored or handled and to areas where Class II or Class III liquids are stored or handled at or above their flash points.

6.2 General. Any electrical equipment provided shall not constitute a source of ignition for the flammable vapor that might be present under normal operation or during a spill. Compliance with 6.2.1 through 6.2.4 shall be deemed as meeting the requirements of Section 6.2.

6.2.1 All electrical equipment and wiring shall be of a type specified by and installed in accordance with NFPA 70, *National Electrical Code (NEC)*.

6.2.2* So far as it applies, Table 6.2.2 shall be used to delineate and classify areas for the purpose of installation of electrical equipment under normal conditions. In the application of classified areas, a classified area shall not extend beyond a floor, wall, roof, or other solid partition that has no openings within the classified area. The designation of classes, divisions, and zones shall be as defined in NFPA 70, *National Electrical Code*, Chapter 5, Article 500.

Table 6.2.2 Electrical Area Classifications

Location	NEC Class I		Extent of Classified Area
	Division	Zone	
Indoor equipment installed in accordance with Section 5.3 where flammable vapor-air mixtures can exist under normal operation	1	0	The entire area associated with such equipment where flammable gases or vapors are present continuously or for long periods of time
	1	1	Area within 5 ft of any edge of such equipment, extending in all directions
	2	2	Area between 5 ft and 8 ft of any edge of such equipment, extending in all directions; also, space up to 3 ft above floor or grade level within 5 ft to 25 ft horizontally from any edge of such equipment ¹
Outdoor equipment of the type covered in Section 5.3 where flammable vapor-air mixtures can exist under normal operation	1	0	The entire area associated with such equipment where flammable gases or vapors are present continuously or for long periods of time
	1	1	Area within 3 ft of any edge of such equipment, extending in all directions
	2	2	Area between 3 ft and 8 ft of any edge of such equipment, extending in all directions; also, space up to 3 ft above floor or grade level within 3 ft to 10 ft horizontally from any edge of such equipment
Tank storage installations inside buildings	1	1	All equipment located below grade level
Tank — aboveground	2	2	Any equipment located at or above grade level
	1	0	Inside fixed-roof tank
	1	1	Area inside dike where dike height is greater than the distance from the tank to the dike for more than 50 percent of the tank circumference
Shell, ends, or roof and dike area	2	2	Within 10 ft from shell, ends, or roof of tank; also, area inside dikes to level of top of tank
Vent	1	0	Area inside of vent piping or opening
	1	1	Within 5 ft of open end of vent, extending in all directions
	2	2	Area between 5 ft and 10 ft from open end of vent, extending in all directions
Floating roof			
With fixed outer roof	1	0	Area between the floating and fixed-roof sections and within the shell
With no fixed outer roof	1	1	Area above the floating roof and within the shell
Underground tank fill opening	1	1	Any pit, box, or space below grade level, if any part is within a Division 1 or 2 or Zone 1 or 2 classified location
	2	2	Up to 18 in. above grade level within a horizontal radius of 10 ft from a loose fill connection and within a horizontal radius of 5 ft from a tight fill connection
Vent — discharging upward	1	0	Area inside of vent piping or opening
	1	1	Within 3 ft of open end of vent, extending in all directions
	2	2	Area between 3 ft and 5 ft of open end of vent, extending in all directions
Drum and container filling – outdoors or indoors	1	0	Area inside the drum or container
	1	1	Within 3 ft of vent and fill openings, extending in all directions
	2	2	Area between 3 ft and 5 ft from vent or fill opening, extending in all directions; also, up to 18 in. above floor or grade level within a horizontal radius of 10 ft from vent or fill opening
Pumps, bleeders, withdrawal fittings			
Indoor	2	2	Within 5 ft of any edge of such devices, extending in all directions; also, up to 3 ft above floor or grade level within 25 ft horizontally from any edge of such devices
Outdoor	2	2	Within 3 ft of any edge of such devices, extending in all directions; also, up to 18 in. above grade level within 10 ft horizontally from any edge of such devices

Table 6.2.2 Electrical Area Classifications (Continued)

Location	NEC Class I		Extent of Classified Area
	Division	Zone	
Pits and sumps			
Without mechanical ventilation	1	1	Entire area within a pit or sump if any part is within a Division 1 or 2 or Zone 1 or 2 classified location
With adequate mechanical ventilation	2	2	Entire area within a pit or sump if any part is within a Division 1 or 2 or Zone 1 or 2 classified location
Containing valves, fittings, or piping, and not within a Division 1 or 2 or Zone 1 or 2 classified location	2	2	Entire pit or sump
Drainage ditches, separators, impounding basins			
Outdoor	2	2	Area up to 18 in. above ditch, separator, or basin; also, area up to 18 in. above grade within 15 ft horizontally from any edge
Indoor			Same classified area as pits
Tank vehicle and tank car ² loading through open dome	1	0	Area inside of the tank
	1	1	Within 3 ft of edge of dome, extending in all directions
	2	2	Area between 3 ft and 15 ft from edge of dome, extending in all directions
Loading through bottom connections with atmospheric venting	1	0	Area inside of the tank
	1	1	Within 3 ft of point of venting to atmosphere, extending in all directions
	2	2	Area between 3 ft and 15 ft from point of venting to atmosphere, extending in all directions; also, up to 18 in. above grade within a horizontal radius of 10 ft from point of loading connection
Office and rest rooms	Ordinary		If there is any opening to these rooms within the extent of an indoor classified location, the room shall be classified the same as if the wall, curb, or partition did not exist
Loading through closed dome with atmospheric venting	1	1	Within 3 ft of open end of vent, extending in all directions
	2	2	Area between 3 ft and 15 ft from open end of vent, extending in all directions; also, within 3 ft of edge of dome, extending in all directions
Loading through closed dome with vapor control	2	2	Within 3 ft of point of connection of both fill and vapor lines, extending in all directions
Bottom loading with vapor control or any bottom unloading	2	2	Within 3 ft of point of connections, extending in all directions; also, up to 18 in. above grade within a horizontal radius of 10 ft from point of connections
Storage and repair garage for tank vehicles	1	1	All pits or spaces below floor level
	2	2	Area up to 18 in. above floor or grade level for entire storage or repair garage
Garages for other than tank vehicles	Ordinary		If there is any opening to these rooms within the extent of an outdoor classified location, the entire room shall be classified the same as the area classification at the point of the opening
Outdoor drum storage	Ordinary		
Inside rooms or storage lockers used for the storage of Class I liquids	2	2	Entire room
Indoor warehousing where there is no flammable liquid transfer	Ordinary		If there is any opening to these rooms within the extent of an indoor classified location, the room shall be classified the same as the wall, curb, or partition did not exist
Piers and wharves			See Figure 5.7.16

For SI units, 1 in. = 25.4 mm; 1 ft = 0.3048 m.

¹The release of Class I liquids can generate vapors to the extent that the entire building, and possibly an area surrounding it, should be considered a Class I, Division 2, or Zone 2 location.

²When classifying extent of area, consideration shall be given to the fact that tank cars or tank vehicles can be spotted at varying points. Therefore, the extremities of the loading or unloading positions shall be used.

6.2.3 The area classifications listed in Table 6.2.2 are based on the premise that the installation shall meet the applicable requirements of this code in all respects. Should this not be the case, the authority having jurisdiction shall have the authority to classify the extent of the area.

6.2.4* Where the provisions of 6.2.1 through 6.2.4 require the installation of electrical equipment suitable for Class I, Division 1 or 2 or Zone 1 or 2 locations, ordinary electrical equipment, including switchgear, shall be permitted to be used if installed in a room or enclosure that is maintained under positive pressure with respect to the classified area. Ventilation make-up air shall not be contaminated.

Chapter 7 Referenced Publications

7.1 The following documents or portions thereof are referenced within this code as mandatory requirements and shall be considered part of the requirements of this code. The edition indicated for each referenced mandatory document is the current edition as of the date of the NFPA issuance of this code. Some of these mandatory documents might also be referenced in this code for specific informational purposes and, therefore, are also listed in Appendix G.

7.1.1 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02269-9101.

NFPA 11, *Standard for Low-Expansion Foam*, 1998 edition.

NFPA 11A, *Standard for Medium- and High-Expansion Foam Systems*, 1999 edition.

NFPA 12, *Standard on Carbon Dioxide Extinguishing Systems*, 2000 edition.

NFPA 12A, *Standard on Halon 1301 Fire Extinguishing Systems*, 1997 edition.

NFPA 13, *Standard for the Installation of Sprinkler Systems*, 1999 edition.

NFPA 14, *Standard for the Installation of Standpipe, Private Hydrants, and Hose Systems*, 2000 edition.

NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*, 1996 edition.

NFPA 16, *Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems*, 1999 edition.

NFPA 17, *Standard for Dry Chemical Extinguishing Systems*, 1998 edition.

NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*, 1998 edition.

NFPA 30A, *Code for Motor Fuel Dispensing Facilities and Repair Garages*, 2000 edition.

NFPA 31, *Standard for the Installation of Oil-Burning Equipment*, 1997 edition.

NFPA 32, *Standard for Drycleaning Plants*, 2000 edition.

NFPA 33, *Standard for Spray Application Using Flammable or Combustible Materials*, 2000 edition.

NFPA 34, *Standard for Dipping and Coating Processes Using Flammable or Combustible Liquids*, 2000 edition.

NFPA 35, *Standard for the Manufacture of Organic Coatings*, 1999 edition.

NFPA 36, *Standard for Solvent Extraction Plants*, 1997 edition.

NFPA 37, *Standard for the Installation and Use of Stationary Combustion Engines and Gas Turbines*, 1998 edition.

NFPA 45, *Standard on Fire Protection for Laboratories Using Chemicals*, 2000 edition.

NFPA 58, *Liquefied Petroleum Gas Code*, 1998 edition.

NFPA 59A, *Standard for the Production, Storage, and Handling of Liquefied Natural Gas (LNG)*, 1996 edition.

NFPA 69, *Standard on Explosion Prevention Systems*, 1997 edition.

NFPA 70, *National Electrical Code®*, 1999 edition.

NFPA 80, *Standard for Fire Doors and Fire Windows*, 1999 edition.

NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*, 1999 edition.

NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Noncombustible Particulate Solids*, 1999 edition.

NFPA 99, *Standard for Health Care Facilities*, 1999 edition.

NFPA 101®, *Life Safety Code®*, 2000 edition.

NFPA 220, *Standard on Types of Building Construction*, 1999 edition.

NFPA 221, *Standard for Fire Walls and Fire Barrier Walls*, 2000 edition.

NFPA 230, *Standard for the Fire Protection of Storage*, 1999 edition.

NFPA 251, *Standard Methods of Tests of Fire Endurance of Building Construction and Materials*, 1999 edition.

NFPA 303, *Fire Protection Standard for Marinas and Boatyards*, 2000 edition.

NFPA 307, *Standard for the Construction and Fire Protection of Marine Terminals, Piers, and Wharves*, 2000 edition.

NFPA 395, *Standard for the Storage of Flammable and Combustible Liquids at Farms and Isolated Sites*, 1993 edition.

NFPA 505, *Fire Safety Standard for Powered Industrial Trucks Including Type Designations, Areas of Use, Conversions, Maintenance, and Operation*, 1999 edition.

NFPA 704, *Standard System for the Identification of the Hazards of Materials for Emergency Response*, 1996 edition.

NFPA 8501, *Standard for Single Burner Boiler Operation*, 1997 edition.

NFPA 8503, *Standard for Pulverized Fuel Systems*, 1997 edition.

7.1.2 Other Publications.

7.1.2.1 API Publications. American Petroleum Institute, 1220 L Street, NW, Washington, DC 20005.

API Specification 12B, *Bolted Tanks for Storage of Production Liquids*, 14th edition, 1995.

API Specification 12D, *Field Welded Tanks for Storage of Production Liquids*, 10th edition, 1994.

API Specification 12F, *Shop Welded Tanks for Storage of Production Liquids*, 11th edition, 1994.

API 620, *Recommended Rules for the Design and Construction of Large, Welded, Low-Pressure Storage Tanks*, 9th edition, 1999.

API Standard 650, *Welded Steel Tanks for Oil Storage*, 10th edition, 1998.

API RP 1632, *Cathodic Protection of Underground Petroleum Storage Tanks and Piping Systems*, 3rd edition, 1996.

API Standard 2000, *Venting Atmospheric and Low-Pressure Storage Tanks*, 5th edition, 1998.

7.1.2.2 ASME Publications. American Society of Mechanical Engineers, Three Park Avenue, New York, NY 10016-5990.

ASME Boiler and Pressure Vessel Code.

ASME B31, *Code for Pressure Piping*, 1998.

ASME Code for Unfired Pressure Vessels, 1998.

7.1.2.3 ASTM Publications. American Society for Testing and Materials, 100 Barr Harbor Drive, West Conshohocken, PA 19428-2959.

ASTM A 395, *Ferritic Ductile Iron Pressure-Retaining Castings for Use at Elevated Temperatures*, 1999.

ASTM D 5, *Standard Test Method for Penetration of Bituminous Materials*, 1997.

ASTM D 56, *Standard Method of Test for Flash Point by the Tag Closed Cup Tester*, 1998.

ASTM D 86, *Standard Method of Test for Distillation of Petroleum Products*, 2000.

ASTM D 92, *Standard Test Method for Flash and Fire Points by Cleveland Open Cup*, 1998.

ASTM D 93, *Standard Test Methods for Flash Point by the Pensky-Martens Closed Tester*, 1999.

ASTM D 323, *Standard Method of Test for Vapor Pressure of Petroleum Products (Reid Method)*, 1999.

ASTM D 3278, *Standard Method of Tests for Flash Point of Liquids by Setaflash Closed Tester*, 1996.

ASTM D 3828, *Standard Test Methods for Flash Point by Small Scale Closed Tester*, 1998.

ASTM F 852, *Standard for Portable Gasoline Containers for Consumer Use*, 1999.

ASTM F 976, *Standard for Portable Kerosene Containers for Consumer Use*, 1999.

7.1.2.4 ATA Publication. American Trucking Association Traffic Department, 2200 Mill Road, Alexandria, VA 22314. *National Motor Freight Classification*.

7.1.2.5 NACE Publications. National Association of Corrosion Engineers, P.O. Box 218340, Houston, TX 77218.

NACE Standard RP-0169, *Recommended Practice, Control of External Corrosion on Underground or Submerged Metallic Piping Systems*, 1996.

NACE Standard RP-0285, *Recommended Practice, Corrosion Control of Underground Storage Tank Systems by Cathodic Protection*, 1995.

7.1.2.6 NRFC Publication. National Railroad Freight Committee, 222 South Riverside Plaza, Chicago, IL 60606-5945. *Uniform Freight Classification*.

7.1.2.7 STI Publications. Steel Tank Institute, 570 Oakwood Road, Lake Zurich, IL 60047.

STI-P₃, *Specification and Manual for External Corrosion Protection of Underground Steel Storage Tanks*, 1997.

STI RP 892, *Recommended Practice for Corrosion of Underground Piping Networks Associated with Liquid Storage and Dispensing Systems*, 1991.

7.1.2.8 UL Publications. Underwriters Laboratories Inc., 333 Pfingsten Road, Northbrook, IL 60062.

UL 58, *Standard for Steel Underground Tanks for Flammable and Combustible Liquids*, 1996.

UL 80, *Standard for Steel Inside Tanks for Oil Burner Fuel*, 1996.

UL 142, *Standard for Steel Aboveground Tanks for Flammable and Combustible Liquids*, 1993.

UL 971, *Standard for Nonmetallic Underground Piping for Flammable Liquids*, 1995.

ANSI/UL 1313, *Nonmetallic Safety Cans for Petroleum Products*, 1993.

UL 1316, *Standard for Glass-Fiber Reinforced Plastic Underground Storage Tanks for Petroleum Products, Alcohols, and Alcohol-Gasoline Mixtures*, 1994.

UL 1746, *Standard for External Corrosion Protection Systems for Steel Underground Storage Tanks, Part I*, 1993.

UL 2080, *Standard for Fire Resistant Tanks for Flammable and Combustible Liquids*, 2000.

UL 2085, *Standard for Protected Aboveground Tanks for Flammable and Combustible Liquids*, 1997.

UL 2208, *Standard for Solvent Distillation Units*, 1996.

UL 2245, *Standard for Below-Grade Vaults for Flammable Liquid Storage Tanks*, 1999.

7.1.2.9 ULC Publication. Underwriters Laboratories of Canada, 7 Crouse Road, Scarborough, Ontario, M1R 3A9, Canada.

ULC-S603.1 M, *Standard for Galvanic Corrosion Protection Systems for Steel Underground Tanks for Flammable and Combustible Liquids*.

7.1.2.10 UN Publication. United Nations, Headquarters, New York, NY 10017.

Recommendations on the Transport of Dangerous Goods, 9th revised edition, 1995.

7.1.2.11 U.S. Government Publications. U.S. Government Printing Office, Washington, DC 20402.

Title 33, *Code of Federal Regulations*, Parts 154, 155 and 156.

Title 46, *Code of Federal Regulations*, Parts 30, 32, 35, and 39.

Title 49, *Code of Federal Regulations*, "Transportation."

Title 49, *Code of Federal Regulations*, Part 173, Appendix H.

Appendix A Explanatory Material

Appendix A is not a part of the requirements of this NFPA document but is included for informational purposes only. This appendix contains explanatory material, numbered to correspond with the applicable text paragraphs.

A.1.1.1 This code is recommended for use as the basis for legal regulations. Its provisions are intended to reduce the hazard to a degree consistent with reasonable public safety, without undue interference with public convenience and necessity, of operations that require the use of flammable and combustible liquids. Compliance with this code does not eliminate all hazards in the use of flammable and combustible liquids. (*See the Flammable and Combustible Liquids Code Handbook for additional explanatory information.*)

A.1.1.2(1) Liquids that are solid at 100°F (37.8°C) or above, but are handled, used, or stored at temperatures above their flash points, should be reviewed against pertinent sections of this code.

A.1.1.2(3) Certain mixtures of flammable or combustible liquids and halogenated hydrocarbons either do not exhibit a flash point using the standard closed-cup test methods or will exhibit elevated flash points. However, if the halogenated hydrocarbon is the more volatile component, preferential evaporation of this component can result in a liquid that does have a flash point or has a flash point that is lower than the original mixture. In order to evaluate the fire hazard of such mixtures, flash point tests should be conducted after fractional evaporation of 10, 20, 40, 60, or even 90 percent of the original sample or other fractions representative of the conditions of use. For systems such as open process tanks or spills in open air, an open-cup test method might be more appropriate for estimating the fire hazard.

A.1.1.2(4) See NFPA 30B, *Code for the Manufacture and Storage of Aerosol Products*.

A.1.1.3(1) Requirements for transportation of flammable and combustible liquids are found in NFPA 385, *Standard for Tank Vehicles for Flammable and Combustible Liquids*, and in 49 CFR 100-199.

A.1.1.3(2) See NFPA 31, *Standard for the Installation of Oil-Burning Equipment*.

A.1.2 Requirements for the safe storage and use of the great variety of flammable and combustible liquids commonly available depend primarily on their fire characteristics, particularly

the flash point, which is the basis for the classification system given in Section 1.7. It should be noted that a liquid's classification can be changed by contamination. For example, placing a Class II liquid into a tank that last contained a Class I liquid can change the flash point of the former so that it falls into the range of a Class I liquid. The same situation can exist where a Class II liquid is exposed to the vapors of a Class I liquid via an interconnecting vapor line. (See 3.7.1.3 and 3.7.2.7.) Care should be exercised in such cases to apply the requirements appropriate to the actual classification. Refer to *Fire Protection Guide to Hazardous Materials* or *NFPA Haz-Mat Quick Guide*, for flash point and other fire hazard data.

The volatility of a liquid is increased by heating. Where Class II or Class III liquids are exposed to storage conditions, use conditions, or process operations where they are naturally or artificially heated up to or above their flash points, additional fire safety features, such as ventilation, separation from ignition sources, diking, or electrical area classification, might be necessary.

Additional fire safety considerations might also be necessary for the safe storage and use of liquids that have unusual burning characteristics, that are subject to self-ignition when exposed to air, that are highly reactive with other substances, that are subject to explosive decomposition, or that have other special properties that dictate safeguards over and above those specified for a normal liquid of similar flash point classification.

A.1.5 An existing situation involving a distinct hazard to life or adjacent property includes conditions that might result in an explosion or sudden escalation of a fire. Examples include but are not limited to inadequate ventilation of confined spaces, lack of adequate emergency venting of a tank, failure to fireproof the supports of elevated tanks, or lack of drainage or dikes to control spills.

A.1.6.2 Approved. The National Fire Protection Association does not approve, inspect, or certify any installations, procedures, equipment, or materials; nor does it approve or evaluate testing laboratories. In determining the acceptability of installations, procedures, equipment, or materials, the authority having jurisdiction may base acceptance on compliance with NFPA or other appropriate standards. In the absence of such standards, said authority may require evidence of proper installation, procedure, or use. The authority having jurisdiction may also refer to the listings or labeling practices of an organization concerned with product evaluations that is in a position to determine compliance with appropriate standards for the current production of listed items.

A.1.6.3 Authority Having Jurisdiction. The phrase "authority having jurisdiction" is used in NFPA documents in a broad manner, since jurisdictions and approval agencies vary, as do their responsibilities. Where public safety is primary, the authority having jurisdiction may be a federal, state, local, or other regional department or individual such as a fire chief; fire marshal; chief of a fire prevention bureau, labor department, or health department; building official; electrical inspector; or others having statutory authority. For insurance purposes, an insurance inspection department, rating bureau, or other insurance company representative may be the authority having jurisdiction. In many circumstances, the property owner or his or her designated agent assumes the role of the authority having jurisdiction; at government installations, the commanding officer or departmental official may be the authority having jurisdiction.

A.1.6.7 Boil-Over. A boil-over is an entirely different phenomenon from a slop-over or froth-over. Slop-over involves a minor frothing that occurs when water is sprayed onto the hot surface of a burning oil. Froth-over is not associated with a fire but results when water is present or enters a tank containing hot viscous oil. Upon mixing, the sudden conversion of water to steam causes a portion of the tank contents to overflow.

A.1.6.8.1 Important Building. Examples of important buildings might include occupied buildings where egress within 2 minutes cannot be reasonably expected, and control buildings that require presence of personnel for orderly shutdown of important or hazardous processes. Important buildings can also include unprotected storage where products from fire can harm the community or the environment, or buildings that contain high-value contents or critical equipment or supplies.

A.1.6.28.4 Water-Miscible Liquid. Liquids that are water-miscible include low molecular weight (3 carbons or less) alcohols, such as methyl alcohol, ethyl alcohol, n-propyl alcohol, isopropyl alcohol, and allyl alcohol. Acetone and tert-butyl alcohol are also water-miscible.

When water-miscible flammable liquids are mixed with water, a homogeneous solution is formed. The flash point, fire point, heat of combustion, and heat release rate for the solution will be different from the pure liquid. The flash point and fire point of the solution will increase as the water concentration increases. At a certain water concentration, which varies for different liquids, the fire point will no longer exist and the solution will no longer present a fire hazard.

A.1.6.29 Listed. The means for identifying listed equipment may vary for each organization concerned with product evaluation, some of which do not recognize equipment as listed unless it is also labeled. The authority having jurisdiction should utilize the system employed by the listing organization to identify a listed product.

A.1.6.34 Pier. The terms *pier* and *wharf* are used interchangeably.

A.1.6.43.2 Atmospheric Tank. Older style flat roof tanks were designed to operate at pressures from atmospheric through 0.5 psig (gauge pressure of 3.45 kPa), measured at the top of the tank. This limitation was established to avoid continuous stress on the roof plates of the tank.

A.1.6.51 Warehouses. Warehousing operations referred to in these definitions are those operations not accessible to the public and include general purpose, merchandise, distribution, and industrial warehouse-type operations.

A.1.6.52 Wharf. The terms *wharf* and *pier* are used interchangeably.

A.1.7.2.1 Boiling Point. At the boiling point, the surrounding atmospheric pressure can no longer hold the liquid in the liquid state and the liquid boils. A low boiling point is indicative of a high vapor pressure and a high rate of evaporation.

A.1.7.2.2 Flash Point. Flash point is a direct measure of a liquid's volatility (i.e., its tendency to vaporize). The lower the flash point, the greater the volatility and the greater the risk of fire. Flash point is determined using one of several different test procedures and apparatus that are specified in 1.7.4.

A liquid that has a flash point at or below ambient temperature is easy to ignite and will burn quickly. On ignition, the spread of flame over the surface of such a liquid will be rapid,

because it is not necessary for the fire to expend energy heating the liquid to generate more vapor. Gasoline is a familiar example. A liquid with a flash point above ambient temperature presents less risk because it must be heated to generate enough vapor to become ignitable; it is more difficult to ignite and presents less potential for the generation and spread of vapor. A common example is home heating oil (Fuel Oil No. 2). Home heating oil must be atomized to a fine mist in order for it to be easily ignited.

Certain solutions of liquids in water exhibit a flash point using the standard closed-cup test procedures but will not burn and could even extinguish a fire. To assist identifying such solutions, the following standards are helpful:

- (1) ASTM D 4207, *Standard Test Method for Sustained Burning of Low Viscosity Liquid Mixtures by the Wick Test*
- (2) ASTM D 4206, *Standard Test Method for Sustained Burning of Liquid Mixtures by the Setaflash Tester (Open Cup)*

Liquid mixtures that do not sustain combustion for a specified time at a specified temperature are considered to be noncombustible. These tests provide additional data for determining proper storage and handling of such mixtures. In a confined space, such mixtures could still create an ignitable vapor-air mixture, depending on the amount of flammable liquid in the mixture and the quantity of the spill.

Related to the flash point is the fire point. The fire point of a liquid is the temperature at which ignition of vapors will result in continued burning. As the term *flash point* suggests, the vapors generated at that temperature will flash but will not necessarily continue to burn. The difference between flash point and fire point has some significance when conducting flash point tests [see 4.1.1.2 references to ASTM D 92, *Standard Test Method for Flash and Fire Points by Cleveland Open Cup*, and 49 CFR (U.S. Department of Transportation Hazardous Materials Regulations), *Method of Testing for Sustained Combustibility*.] However, a closed-cup flash point is used to classify the liquid and characterize its hazard.

For more information, see ASTM E 502, *Standard Test Method for Selection and Use of ASTM Standards for the Determination of Flash Point of Chemicals by Closed Cup Methods* and the *ASTM Manual on Flash Point Standards and Their Use*.

A.1.7.2.4 Vapor Pressure. Vapor pressure is a measure of the pressure that the liquid exerts against the atmosphere above it. Just as the atmosphere exerts pressure on the surface of the liquid, the liquid pushes back. Vapor pressure is normally less than atmospheric pressure and is a measure of the liquid's tendency to evaporate (i.e., to move from the liquid to the gaseous state). This tendency is also referred to as volatility, thus the use of the term *volatile* to describe liquids that evaporate very easily. The higher the vapor pressure, the greater the rate of evaporation and the lower the boiling point. Simply put, this means more vapors and increased fire risk.

A.1.7.3 The classification of liquids is based on flash points that have been corrected to sea level, in accordance with the relevant ASTM test procedures. At high altitudes, the actual flash points will be significantly lower than those either observed at sea level or corrected to atmospheric pressure at sea level. Allowances could be necessary for this difference in order to appropriately assess the risk.

Table A.1.7.3 presents a comparison of the definitions and classification of flammable and combustible liquids, as set

forth in Section 1.7 of this code, with similar definitions and classification systems used by other regulatory bodies.

The Hazardous Materials Regulations of the U.S. Department of Transportation (DOT), as set forth in the 49 CFR 173.120(b)(2) and 173.150(f), provide an exception whereby a flammable liquid that has a flash point between 100°F (37.8°C) and 141°F (60.5°C) and does not also meet the definition of any other DOT hazard class, can be reclassified as a combustible liquid [i.e., one having a flash point above 141°F (60.5°C)] for shipment by road or rail within the United States.

A.2.2.3.3.2 Such pressure vessels are generally referred to as "state special."

A.2.2.4.1 The design of the supporting structure for tanks such as spheres is outside the scope of this code and requires special engineering consideration. See Appendix N of API 620, *Recommended Rules for the Design and Construction of Large, Welded, Low-Pressure Storage Tanks*.

A.2.2.5.1.9 Liquid properties that justify omitting such devices include, but are not limited to, condensation, corrosiveness, crystallization, polymerization, freezing, or plugging. When any of these conditions exist, consideration should be given to heating, use of devices that employ special materials of construction, use of liquid seals, or inerting. See NFPA 69, *Standard on Explosion Prevention Systems*.

A.2.2.5.2.4 Exception The formula is based on $Q = 21,000 (A)^{0.8}$.

A.2.2.5.2.6 Exception No. 1 Ethyl alcohol (ethanol) has a heat of combustion of 11,548 Btu/lb (26.8 mJ/kg) and a rate of burning of 0.000626 lb/ft²/sec (0.015 kg/m²/sec). The burning rate was calculated based on pan pool fires of diameters between 0.7 ft and 16.5 ft (0.2 m to 5.0 m). The pool fires were burning at steady state in a wind-free environment. The ratio of the lip height of the pan (freeboard) to the diameter of the pan was approximately 0.06. Details of these tests can be found in "Fire Tests of Distilled Spirit Storage Tanks," Client Report CR-5727.1, for the Association of Canadian Distillers.

A.2.2.5.2.9.2 A suitable formula for this calculation is

$$CFH = 1667 C_f A \sqrt{P_t - P_a}$$

where:

CFH = venting requirement (ft³ of free air per hour)

C_f = flow coefficient of 0.5

A = orifice area (in.²)

P_t = absolute pressure inside the tank (in. of water)

P_a = absolute atmospheric pressure outside the tank (in. of water)

A.2.2.5.2.10 Vent sizing formulae and prescriptive vent sizes, such as those established by UL 142, *Standard for Steel Above-ground Tanks for Flammable and Combustible Liquids*, are typically based on the direct installation of a venting device on to a tank. When the outlet of a vent must be extended to a remote location, such as for tanks located in buildings, which require vent discharges, to be located outside, a significant reduction in vent flow can occur unless the size of the vent and connecting piping is increased. In such cases, the size of vents and vent pipe extensions should be calculated to ensure that a tank will not be over-pressurized during a fire exposure.

Table A.1.7.3 Comparative Classification of Liquids

Agency	Agency Classification	Agency Flash Point		NFPA Definition	NFPA Classification	NFPA Flash Point	
		°F	°C			°F	°C
ANSI/CMA Z129.1-1994	Flammable	<141	<60.5	Flammable	Class I	< 100	<37.8
	Combustible	≥141 to <200	≥60.5 to <93	Combustible	Class II Class IIIA	≥100 to <140 ≥140 to <200	≥37.8 to <60 ≥60 to <93
DOT	Flammable	<141	<60.5	Flammable	Class I	<100	<37.8
	Combustible	≥141 to <200	≥60.5 to <93	Combustible	Class II Class IIIA	≥100 to <140 ≥140 to <200	≥37.8 to <60 ≥60 to <93
DOT HM-181 Domestic Exemption ¹	Flammable	<100	<37.8	Flammable	Class I	<100	<37.8
	Combustible	≥100 to <200	≥37.8 to <93	Combustible	Class II Class IIIA	≥100 to <140 ≥140 to <200	≥37.8 to <60 ≥60 to <93
UN	Flammable	<141	<60.5	Flammable	Class I	<100	< 37.8
	Combustible	≥141 to <200	≥60.5 to <93	Combustible	Class II Class IIIA	≥100 to <140 ≥140 to <200	≥37.8 to <60 ≥60 to <93
OSHA	Flammable	<100	<37.8	Flammable	Class I	<100	<37.8
	Combustible ²	≥100	≥37.8	Combustible	Class II Class IIIA Class IIIB ²	≥100 to <140 ≥140 to <200 ≥200	≥37.8 to <60 ≥60 to <93 ≥93

¹See A.1.7.3.²See 29 CFR 1910.106 for Class IIIB liquid exemptions.

A.2.2.5.3 The required venting capacity depends upon the filling or withdrawal rate, whichever is greater, and the vent line length. Unrestricted vent piping sized in accordance with Table 2.2.5.3 will prevent back pressure development in tanks from exceeding 2.5 psig (gauge pressure of 17.2 kPa).

A.2.2.6 Other means of internal corrosion protection include protective coatings and linings and cathodic protection.

A.2.2.6.1.1(1) Acceptable design standards for cathodic protection systems include the following:

- (1) API RP 1632, *Cathodic Protection of Underground Petroleum Storage Tanks and Piping Systems*
- (2) ULC-S603.1 M, *Standard for Galvanic Corrosion Protection Systems for Steel Underground Tanks for Flammable and Combustible Liquids*
- (3) STI-P₃, *Specification and Manual for External Corrosion Protection of Underground Steel Storage Tanks*
- (4) NACE RP-0169, *Recommended Practice, Control of External Corrosion on Underground or Submerged Metallic Piping Systems*
- (5) NACE RP-0285, *Recommended Practice, Corrosion Control of Underground Storage Tank Systems by Cathodic Protection*
- (6) UL 1746, *Standard for External Corrosion Protection Systems for Steel Underground Storage Tanks, Part 1*
- (7) STI RP 892, *Recommended Practice for Corrosion of Underground Piping Networks Associated with Liquid Storage and Dispensing Systems*

A.2.2.6.1.1(2) See UL 1316, *Standard for Glass-Fiber-Reinforced Plastic Underground Storage Tanks for Petroleum Products, Alcohols, and Alcohol-Gasoline Mixtures*; UL 1746, *Standard for External Corrosion Protection Systems for Steel Underground Storage Tanks*; and STI ACT-100, *Specification for External Corrosion Protection of FRP Composite Steel Underground Tanks*, F894.

A.2.2.6.1.2 See API RP 1615, *Installation of Underground Petroleum Storage Systems*, for further information.

A.2.3.1.1 Appendix E of API Standard 650, *Welded Steel Tanks for Oil Storage*, and Appendix B of API 620, *Recommended Rules for the Design and Construction of Large, Welded, Low-Pressure Storage Tanks*, provide information on tank foundations.

A.2.3.1.3 For further information, see ASTM E 119, *Standard Test Methods for Fire Tests of Building Construction and Materials*, and UL 1709, *Standard for Rapid Rise Fire Tests of Protection Materials for Structural Steel*.

A.2.3.2 See PEI RP200, *Recommended Practices for Installation of Aboveground Storage Systems for Motor Vehicle Fueling*, for additional information.

A.2.3.2.3.2(b) An aboveground storage tank dike is normally sized to contain the entire contents of the largest single tank within it. Some designs incorporate sufficient freeboard (additional capacity) to accommodate precipitation or fire-fighting

water. The amount of this freeboard is usually governed by local conditions.

A.2.3.2.3.2(d) Diked areas for tanks containing Class I liquids located in extremely porous soils might require special treatment to prevent seepage of hazardous quantities of liquids to low-lying areas or waterways in case of spills.

A.2.3.2.3.2(f)(3) Because unstable liquids will react more rapidly when heated than when at ambient temperatures, subdivision by drainage channels is the preferred method.

A.2.3.2.3.4.1 Engineering designs that can reduce exposure hazards include use of sealed sleeve piping and secondary containment piping to prevent leakage and the use of remotely controlled isolation valves on product lines to stop the flow of liquids when the piping is subjected to fire exposure.

A.2.3.2.3.4.3 Methods of preventing an exposure hazard include intermediate diking, drainage, or fire protection features such as water spray systems, monitors, or fire-resistive coatings. High integrity pumps or equipment also constitute a method of limiting exposure hazards.

A.2.3.2.5.4 Examples of liquids with minimal potential for accumulation of static charge include crude oil, asphalt, and water-miscible liquids. For additional information, see NFPA 77, *Recommended Practice on Static Electricity*.

A.2.3.3.2.1 Dropping or rolling the tank into the hole can break a weld, puncture or damage the tank, or scrape off the protective coating of coated tanks. See PEI RP100, *Recommended Practices for Installation of Underground Liquid Storage Systems*.

A.2.3.4.1 This subsection provides an approach that allows considerable flexibility for compliance without compromising fire safety, while fostering ingenuity in application of fire safety principles to achieve the intended objectives, outlined in the performance criteria set out at the beginning of each subsection. Each subsection has been written with the first sentence outlining the performance criteria that, if implemented, would achieve compliance with that subsection. In order to clarify the intent of each performance criterion, the subsequent paragraphs constitute one method of achieving compliance with the intent envisioned in the performance requirements. It is recognized that other combinations of requirements can also be used to meet the intent of the performance criteria, provided such requirements are acceptable to the authority having jurisdiction.

A.2.3.4.2.2(b) See NFPA 68, *Guide for Venting of Deflagrations*, for information on deflagration venting.

A.2.3.4.3.2 See NFPA 220, *Standard on Types of Building Construction*.

A.2.3.4.3.4 See NFPA 68, *Guide for Venting of Deflagrations*, for information on deflagration venting.

A.2.3.4.3.5 NFPA 101®, *Life Safety Code*®, provides information on the design of exit facilities.

A.2.3.4.4.2 Equipment in enclosed storage areas can deteriorate over time and periodic sampling should be conducted to assure that leakage rates have not increased or that the ventilation rate is adequate for any increase in leakage rates.

A.2.3.4.4.4 Local or spot ventilation might be needed for the control of special fire or health hazards. NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Non-*

combustible Particulate Solids, and NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*, provide information on this subject.

A.2.3.4.5.5 Appendix A of NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*, provides information on this subject.

A.2.3.4.7.5 Substitutes for manual gauging include, but are not limited to, heavy-duty flat gauge glasses, magnetic, hydraulic, or hydrostatic remote reading devices, and sealed float gauges.

A.2.3.4.7.8 Suitable devices include, but are not limited to, a float valve, a pre-set meter on the fill line, a low head pump incapable of producing overflow, or a liquidtight overflow pipe, sized at least one pipe size larger than the fill pipe, that discharges by gravity back to the outside source of liquid or to an approved location.

A.2.3.4.11.1 NFPA 10, *Standard for Portable Fire Extinguishers*, provides information on the suitability of various types of extinguishers.

A.2.3.4.11.2 See NFPA 13, *Standard for the Installation of Sprinkler Systems*, and NFPA 14, *Standard for the Installation of Standpipe, Private Hydrant, and Hose Systems*.

A.2.3.4.12.2 See NFPA 24, *Standard for the Installation of Private Fire Service Mains and Their Appurtenances*, for information on this subject.

A.2.3.4.12.3 See NFPA 13, *Standard for the Installation of Sprinkler Systems*; NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*; and NFPA 16, *Standard for the Installation of Foam-Water Sprinkler and Foam-Water Spray Systems*, for information on these subjects.

For certain fuel types, such as ketones, esters, and alcohols, the minimum required densities established in the listing criteria for foam discharge devices are often higher than the general densities specified for protection of flammable and combustible liquids. When determining the design criteria for extinguishing systems using foam, it is important to ensure that the listing criteria, which are typically based on empirical data from fire tests, are not overlooked. Otherwise, the fire protection system design can be inadequate for proper protection.

A.2.4.2 See PEI RP200, *Recommended Practices for Installation of Aboveground Storage Systems for Motor Vehicle Fueling*, and STI R931, *Double Wall AST Installation and Testing Instructions*, for additional requirements to test secondary containment tanks.

A.2.4.3 For information on testing of underground tanks, see NFPA 329, *Recommended Practice for Handling Releases of Flammable and Combustible Liquids and Gases*. For information on testing aboveground tanks, see API 653, *Tank Inspection, Repair, Alteration, and Reconstruction*.

A.2.5.3.3 See NFPA 51B, *Standard for Fire Prevention During Welding, Cutting, and Other Hot Work*.

A.2.5.3.4 The prevention of electrostatic ignition in equipment is a complex subject. Refer to NFPA 77, *Recommended Practice on Static Electricity*, or manufacturers' recommendations for guidance.

A.2.6.4.1 For further information, see API 2015, *Cleaning Petroleum Storage Tanks*; API 2015A, *A Guide for Controlling the Lead Hazard Associated with Tank Entry and Cleaning*; and API 2015B, *Cleaning Open Top and Covered Floating Roof Tanks*.

A.2.6.5.3(b) Special training might be required.

A.2.6.6 See NFPA 329, *Recommended Practice for Handling Releases of Flammable and Combustible Liquids and Gases*, for information on testing methods.

A.2.6.7.3 For additional information, see API 653, *Tank Inspection, Repair, Alteration, and Reconstruction*.

A.3.5.2 API 2218, *Fireproofing Practices in Petroleum and Petrochemical Processing Plants*, contains guidance on selecting and installing fire-resistant coatings to protect exposed steel supports from a high-challenge fire exposure. It also contains a general discussion on determining need for such protection and estimating the extent of the area exposed.

A.3.5.4 Buried steel piping should be coated with a suitable material and should be cathodically protected. Galvanized steel pipe, by itself and without other corrosion protection methods, is not acceptable for underground piping. Steel swing joints and stainless steel flexible connectors should also be made corrosion resistant when in contact with the soil. Thus, such fittings should also be coated and cathodically protected when installed between nonmetallic, compatible tanks and piping, such as fiberglass reinforced plastic.

A.3.7.1.4 Vent sizing formulae and prescriptive vent sizes, such as those established by UL 142, *Standard for Steel Above-ground Tanks for Flammable and Combustible Liquids*, are typically based on the direct installation of a venting device on to a tank. When the outlet of a vent must be extended to a remote location, such as for tanks located in buildings, which require vent discharges, to be located outside, a significant reduction in vent flow can occur unless the size of the vent and connecting piping is increased. In such cases, the size of vents and vent pipe extensions should be calculated to ensure that a tank will not be over-pressurized during a fire exposure.

A.3.9 Where loading and unloading risers for Class II or Class IIIA liquids are located in the same immediate area as loading and unloading risers for Class I liquids, consideration should be given to providing positive means, such as different pipe sizes, connection devices, special locks, or other methods designed to prevent the erroneous transfer of Class I liquids into or from any container or tank used for Class II or Class IIIA liquids. Note that such consideration might not be necessary for water-miscible liquids, where the class is determined by the concentration of liquid in water, or where the equipment is cleaned between transfers.

A.4.1.1 See Appendix E for limitations of the protection criteria of Tables 4.8.2(a) through (j), particularly for intermediate bulk containers and portable tanks having capacities greater than 60 gal (227 L).

A.4.2.1(e) The term *rigid nonmetallic intermediate bulk container* is used to describe intermediate bulk containers that have a plastic vessel that serves as the primary liquid-holding component. This vessel can be enclosed in or encased by an outer structure consisting of a steel cage, a single-wall metal or plastic enclosure, or a double wall of foamed or solid plastic. These are often called *composite IBCs*, which is the term used by U.S. Department of Transportation (DOT) to describe them. The term *rigid non-metallic intermediate bulk container* also denotes an all-plastic single-wall IBC that could or could not have a separate plastic base and for which the containment vessel also serves as the support structure. IBCs that have an outer liquidtight metal structure are considered to be metal IBCs or metal portable tanks by DOT and are defined in 4.2.1(a).

A.4.3.4 Venting of storage cabinets has not been demonstrated to be necessary for fire protection purposes. Additionally, venting

a cabinet could compromise the ability of the cabinet to adequately protect its contents from involvement in a fire since cabinets are not generally tested with any venting. Therefore, venting of storage cabinets is not recommended.

However, it is recognized that some jurisdictions can require storage cabinets to be vented and that venting can also be desirable for other reasons, such as health and safety. In such cases, the venting system should be installed so as to not affect substantially the desired performance of the cabinet during a fire. Means of accomplishing this can include thermally actuated dampers on the vent openings or sufficiently insulating the vent piping system to prevent the internal temperature of the cabinet from rising above that specified. Any make-up air to the cabinet should also be arranged in a similar manner.

If vented, the cabinet should be vented from the bottom with make-up air supplied to the top. Also, mechanical exhaust ventilation is preferred and should comply with NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Noncombustible Particulate Solids*. Manifolding the vents of multiple storage cabinets should be avoided.

A.4.4 See Section 1.6 for definitions. See Figures A.4.4(a) and (b) for explanatory information on the types of inside liquid storage areas. See Appendixes D and E for information on protection criteria.

A.4.4.2.4 NFPA 68, *Guide for Venting of Deflagrations*, provides information on this subject.

A.4.4.2.5 Spill containment can be accomplished by any of the following:

- (1) Noncombustible, liquidtight raised sills, curbs, or ramps of suitable height at exterior openings
- (2) Noncombustible, liquidtight raised sills, curbs, or ramps of suitable height, or other flow-diverting structures at interior openings
- (3) Sloped floors
- (4) Open-grate trenches or floor drains that are connected to a properly designed drainage system
- (5) Wall scuppers that discharge to a safe location or to a properly designed drainage system
- (6) Other means that are acceptable to the authority having jurisdiction

Where sills, curbs, or ramps are used, the appropriate height will depend on a number of factors, including the maximum expected spill volume, the floor area, and the existence of any drainage systems. Historically, curbs and sills have been 4 in. (100 mm) high.

A variety of curb, sill, and ramp heights can be used to obtain the desired containment volume. As a guide, 1 ft² of water at a depth of 1 in. equals 0.62 gal (1 m² of water at a depth of 25 mm equals 25 L). Once the total quantity of liquid containment has been established, the necessary curb, sill, or ramp height can then be calculated.

Where open-grate trenches are used, the volume of the trench should be able to contain the maximum expected spill volume or otherwise be connected to a properly designed drainage system.

It should be noted that these containment and drainage provisions address only fire protection concerns. Consult the appropriate environmental regulations for other restrictions that could apply. (See 1.4.3.)

A.4.4.4.1 Exception Other arrangements include, but are not limited to, increases in pile height, pile size, or maximum total quantity stored, or use of multiple-row racks or high-rise warehouses.

FIGURE A.4.4(a) Guide to application of Chapter 4, Container and Portable Tank Storage.





FIGURE A.4.4(b) Examples of the various inside liquid storage areas. Shaded areas are the liquid storage areas.



A.4.5.2.3 Exception No. 2 Based on work done by the FM Global, it was determined that flammable liquids in plastic containers could cause uncontrollable fires under certain conditions of storage in general-purpose warehouses. A research project on flammable liquids container storage carried out by Underwriters Laboratories Inc., under the auspices of the National Fire Protection Research Foundation, has suggested a test protocol that can judge the capability of packaging systems to withstand a small ignition source or to minimize the rate at which the lading is released from the containers, so that the fire can be controlled by automatic sprinklers.

There is currently no nationally recognized consensus standard for conducting such tests.

A.4.6 Environmental concerns have dictated special handling of hazardous materials, chemicals, and wastes. Some of these have flammable and combustible liquid characteristics, in addition to their environmental and health problems, thus causing some questions as to how they should be stored and handled.

Several manufacturers have met this problem by designing and manufacturing movable, modular prefabricated storage lockers, working diligently with various building officials and authorities having jurisdiction. This results in a product that is intended to meet government standards and regulations for hazardous materials storage. Several municipalities have passed model ordinances covering the design, construction, and location of hazardous materials storage lockers. Design features can include, but are not limited to, the following:

- (1) Secondary spill containment sumps
- (2) Deflagration venting
- (3) Ventilation requirements, including mechanical ventilation where dispensing operations are expected
- (4) Electrical equipment for hazardous locations in accordance with NFPA 70, *National Electrical Code*®
- (5) Static electricity control
- (6) Fire suppression systems (dry chemical or sprinklers)
- (7) Heavy structural design for the following:
 - a. Security provisions
 - b. Doors that lock and permit pallet loading
 - c. Wind load, snow load, and storage load conditions
 - d. Anchorage provisions
 - e. Skid design, permitting relocation using lift trucks
- (8) Fire-rated exterior walls, if required
- (9) Interior partitions to segregate incompatible materials
- (10) Size limits to limit quantities that can be stored within preassembled or ready-to-assemble designs

- (11) Nonsparking floors
- (12) Shelving, if required
- (13) Heating or cooling units, if needed
- (14) Corrosion protection as required
- (15) Employee safety provisions (eye/face wash)
- (16) NFPA 704, *Standard System for the Identification of the Hazards of Materials for Emergency Response*, hazard symbols

Features provided are determined by specific storage requirements and needs of the owner, keeping in mind applicable regulations and ordinances that apply and the approval requirements of the authority having jurisdiction.

Several testing laboratories have developed internal procedures for the examination, testing, and listing or labeling of hazardous materials storage lockers submitted by manufacturers.

A.4.8.1.3 Table A.4.8.1.3 provides examples of commonly used metal containers that are considered either relieving-style or nonrelieving style for use in developing protected storage arrangements in accordance with Tables 4.8.2(a) through (d) and Table 4.8.2(h).

A.4.8.1.6 Interpolation between 4.8.1.6(a) and (b) is allowed.

A.4.8.2 Protected storage allowed under previous editions of this code can be continued if the class of liquids stored, the quantity of liquids stored, fire protection, and building configuration remain unchanged. Tables A.4.8.2(a) and A.4.8.2(b), reprinted here from the 1993 edition of this code, can be used as a reference for storage arrangements in previously approved protected inside liquids storage areas.

For certain liquids such as ketones, esters, and alcohols, the minimum required densities established in the listing criteria for foam discharge devices are often higher than the general densities specified for protection of flammable and combustible liquids. When determining the design criteria for extinguishing systems using foam, it is important to ensure that the listing criteria, which are typically based on empirical data from fire tests, are not overlooked. Otherwise, the fire protection system design can be inadequate for proper protection.

Where Figures 4.8.2(a) through (d) permit the use of sprinkler systems designed in accordance with NFPA 13, *Standard for the Installation of Sprinkler Systems*, caution should be exercised with regard to the use of early suppression fast response (ESFR) sprinklers to protect containers that exceed 10 gal (38 L) capacity that contain water-miscible Class I, II, or III liquids in concentrations greater than 20 percent up to 50 percent. The use of ESFR protection, particularly without provisions for the control of spread of liquid, presents the possibility of a liquid pool fire that could exceed the limited design operating area of an ESFR system.

The information in Tables 4.8.2(a) through (j) was developed from full-scale fire tests. Where only one orifice size sprinkler is allowed, this was the only size proven to provide fire control. Where a choice of orifice sizes is allowed by the tables, each was able to provide fire control; however, the larger orifice size sprinklers sometimes demonstrated better fire control and further limited fire damage. Where only one response type of sprinkler is allowed, this is the only type of sprinkler proven to provide fire control. Where a choice of response characteristics (SR or QR) is allowed by the tables, each was able to provide fire control; however, the QR sprinklers sometimes demonstrated better fire control and further limited fire damage.

Table A.4.8.1.3 Common Relieving- and Nonrelieving-Style Metal Containers

Container Type	Relieving Style	Nonrelieving Style
≤1 qt ¹	All	N/A
>1 qt and ≤6 gal ¹	Metal containers with plastic cap, or flexible or rigid plastic spout with plastic cap	Metal containers with steel spout and steel screw cap
≤1 gal, friction lid	Metal containers with metal friction-fit covers (e.g., paint can lid)	N/A
1 gal and ≤6 gal (lug cover)	Metal containers with metal covers held in place with a mechanical friction-fit (e.g., lug-type) closure mechanism	N/A
>6 gal and ≤60 gal ^{2,3} (drums)	Metal containers, tight or open-head (drums) having at least one 2 in. plastic plug: (Note: cap seals, if used, need to be plastic and nonmetallic)	Open head metal containers with steel covers having no steel flange openings; or open head and tight head metal containers with steel flange openings where only steel plugs and/or cap seals are used
>60 gal and ≤793 gal	Metal portable tanks or metal intermediate bulk containers with at least one relief device conforming to the design, construction, and capacity of the container's section (<i>see Section 4.2</i>)	N/A

¹All containers ≤ 1 qt are considered relieving style because their failure is inconsequential.

²In full-scale fire tests, where containers were provided with both $\frac{3}{4}$ in. (19 mm) and 2 in. (50 mm) relieving vent openings and, in some cases, both vents were obstructed by pallet slats, rupture of containers did not occur. Because it is not possible to determine if all conceivable obstruction scenarios were represented, where drums are stacked more than one high, provide an additional $\frac{3}{4}$ in. (19 mm) or 2 in. (50 mm) pressure-relieving mechanism.

³The use of plastic plugs instead of steel plugs (bungs) in a steel drum in order to achieve a relieving-style container should contemplate the following issues in order to assure the safe storage of liquids:

- (1) The compatibility of the plastic plug materials and gaskets with the liquids being stored.
- (2) The stability and shelf life of the liquids being stored as the plastic plugs can admit water vapor, oxygen, and light.
- (3) The difference in expansion coefficients for plastic plugs and steel drums for those drums subject to temperature variations and hot or cold conditions.
- (4) The tooling issues involved with the use of plastic plugs as the torque levels are different from those levels used for steel plugs.
- (5) The training of fill line operators in order to avoid cross-threading and/or the stripping of threads.
- (6) The voiding of the United Nations (UN) rating on the steel drum by installing plastic plugs. If the user needs to install a plug other than the one originally provided by the container manufacturer, then the user should contact the manufacturer to ensure that the UN rating will still be valid.

Table A.4.8.2(a) Storage Arrangements for Protected Palletized or Solid Pile Storage of Liquids in Containers and Portable Tanks

Liquid Class	Storage Level	Maximum Storage Height (ft)		Maximum Quantity per Pile (gal)		Maximum Quantity ^a (gal)	
		Containers	Portable Tanks	Containers	Portable Tanks	Containers	Portable Tanks
IA	Ground floor	5	—	3,000	—	12,000	—
	Upper floors	5	—	2,000	—	8,000	—
	Basement	NP	NP	—	—	—	—
IB	Ground floor	6 $\frac{1}{2}$	7	5,000	20,000	15,000	40,000
	Upper floors	6 $\frac{1}{2}$	7	3,000	10,000	12,000	20,000
	Basement	NP	NP	—	—	—	—
IC	Ground floor	6 $\frac{1}{2}$ ^b	7	5,000	20,000	15,000	40,000
	Upper floors	6 $\frac{1}{2}$ ^b	7	3,000	10,000	12,000	20,000
	Basement	NP	NP	—	—	—	—
II	Ground floor	10	14	10,000	40,000	25,000	80,000
	Upper floors	10	14	10,000	40,000	25,000	80,000
	Basement	5	7	7,500	20,000	7,500	20,000
III	Ground floor	20	14	15,000	60,000	55,000	100,000
	Upper floors	20	14	15,000	60,000	55,000	100,000
	Basement	10	7	10,000	20,000	25,000	40,000

For SI units, 1 ft = 0.3 m; 1 gal = 3.8 L.

NP = not permitted.

^aApplies only to cut-off rooms and attached buildings.

^bThese height limitations can be increased to 10 ft for containers of 5 gal capacity or less.

Table A.4.8.2(b) Storage Arrangements for Protected Rack Storage of Liquids in Containers

Liquid Class	Type Rack	Storage Level	Maximum Storage Height of Containers (ft)	Maximum Quantity of Containers (gal) ^{1,2}
IA	Double row or single row	Ground floor	25	7,500
		Upper floors	15	4,500
		Basement	NP	—
IB IC	Double row or single row	Ground floor	25	15,000
		Upper floors	15	9,000
		Basement	NP	—
II	Double row or single row	Ground floor	25	24,000
		Upper floors	25	24,000
		Basement	15	9,000
III	Multirow, double row, or single row	Ground floor	40	55,000
		Upper floors	20	55,000
		Basement	20	25,000

For SI units, 1 ft = 0.3 m; 1 gal = 3.8 L.

NP = not permitted.

¹Maximum quantity allowed on racks in cut-off rooms and attached buildings.

²Maximum quantity allowed per rack section in liquid warehouses.

A.4.8.2.8 Most fire tests using foam-water protection schemes have been conducted with immediate foam solution discharge from the operating sprinklers. If an appreciable delay is encountered before properly proportioned foam is discharged, control of the fire might not be established. One method of accomplishing immediate foam solution discharge is by using an in-line balanced pressure (ILBP) proportioning system.

A.4.8.5.1 Subsection 4.8.5.1 requires that control of liquid spread be provided to prevent a pool fire on the floor from spreading and opening more sprinkler heads than the design of the sprinkler system anticipates. For example, if the sprinkler system is designed to provide 0.45 gpm per ft² over 3000 ft², 4.8.5.1 requires that the spread of liquid also be limited to 3000 ft². Various means are available to achieve this control.

Typical methods use trench or spot drains that divide the floor of the storage area into rectangles having areas equal to or less than the design area of the sprinkler system. Drains are centered under racks, and the floor is sloped toward the drain trenches with a minimum slope of 1 percent. The floor is made highest at the walls. See Figures A.4.8.5.1(a) and (b). Trenches are arranged as described in NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*, and as shown in Figure A.4.8.5.1(c). Note particularly the dimensions of the trenches, and note that the solid covering spans one-third of the width on either side of the open grate and the open grate spans the middle third. Spot drains can be similarly arranged.

Another method, shown in Figure A.4.8.5.1(d), uses spot drains located at building columns, where the area between any four columns does not exceed the design area of the sprinkler system. The floor is sloped to direct water flow to the drains.

Connections to the drains are provided at trapped sumps, arranged as described in NFPA 15 [see Figure A.4.8.5.1(e)]. To provide a safety factor, the drain pipes are sometimes sized to carry 150 percent of anticipated sprinkler discharge. The following equation can be used to calculate the flow of the drain pipe:

$$F = 1.5 \times D \times A$$

where:

F = flow (gpm or L/min)

D = sprinkler design density (gpm per ft² or L/min/m²)

A = sprinkler design area (ft² or m²)

Additional information can be found in *Guidelines for Safe Warehousing of Chemicals*, Center for Chemical Process Safety, American Institute of Chemical Engineers.

A.4.10.1 The indiscriminate mixed storage of materials that have a high toxicity or high reactivity hazard that are also flammable liquids is a practice that could result in either a catastrophic release of toxic materials or an explosion. (See also Section 1.2 and A.1.2.)

A.4.10.2 Subsection 1-6.3.2 of NFPA 505, *Fire Safety Standard for Powered Industrial Trucks Including Type Designations, Areas of Use, Conversions, Maintenance, and Operation*, states “In locations used for the storage of flammable liquids in sealed containers or liquefied or compressed flammable gases in containers, approved power-operated industrial trucks designated as Types CNS, DS, ES, GS, LPS, GS/CNS, or GS/LPS shall be permitted to be used where approved by the authority having jurisdiction.” Compared to the above types, industrial trucks that are designated DY and EE have significantly less potential for igniting flammable vapors (such as might result from a spill of Class I liquid) and should be used in inside liquid storage areas where conditions warrant.

A.5.1.2 These provisions might not provide adequate protection for operations involving hazardous materials or chemical reactions, nor do they consider health hazards resulting from exposure to such materials.






A.5.3.2.3 Equipment operated at pressures over 1000 psig (gauge pressure of 7000 kPa) could require greater spacing.

A.5.3.3.1 See NFPA 220, *Standard on Types of Building Construction*.

A.5.3.3.2 API 2218, *Fireproofing Practices in Petroleum and Petrochemical Processing Plants*, contains guidance on selecting and installing fire-resistant coatings to protect exposed steel supports from a high-challenge fire exposure. It also contains a general discussion on determining need for such protection and estimating the extent of the area exposed.

A.5.3.3.4 NFPA 204, *Guide for Smoke and Heat Venting*, provides information on this subject.

A.5.3.3.5 NFPA 101, *Life Safety Code*, provides information on the design of exit facilities.

FIGURE A.4.8.5.1(a) General scheme for warehouse spill control of liquids.**FIGURE A.4.8.5.1(b) Plan view of warehouse spill control of liquids.****FIGURE A.4.8.5.1(c) Details of drainage trench design.****FIGURE A.4.8.5.1(d) Typical arrangement of floor drains.****FIGURE A.4.8.5.1(e) Details of Liquid-Seal Trap.**

A.5.3.3.7 NFPA 68, *Guide for Venting of Deflagrations*, provides information on this subject.

A.5.3.4.2 Equipment in enclosed processing areas can deteriorate over time, and periodic sampling should be conducted to ensure that leakage rates have not increased or that the ventilation rate is adequate for any increase in leakage rates.

A.5.3.4.4 NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Noncombustible Particulate Solids*, and NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*, provide information on this subject.

A.5.3.5.1 This might require curbs, scuppers, or special drainage systems to control the spread of fire. Appendix A of NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*, provides information on this subject.

A.5.3.7.8 The process area is not intended to be a liquid container storage area. However, it is recognized that containers of liquids are brought into the area to use in the processes and, that as a result of the processes, liquids could be filled into containers in the process area.

The amount of liquid in containers in the process area should be limited as much as possible. Full containers should not be stored in the process area but can be staged there. Only the amount of liquid needed for one continuous 24-hour period should be brought into the process area in full containers. Partial containers can remain in the process area as long as they do not increase the hazard present. Containers that were filled in the process area can remain there during the shift that they were filled but should be relocated to the appropriate storage area before the end of the workday or shift in the case of 24-hour-a-day operations.

A.5.3.8 Where the vapor space of equipment is usually within the flammable range, the probability of explosion damage to the equipment can be limited by inerting, by providing an explosion suppression system, or by designing the equipment to contain the peak explosion pressure that can be modified by explosion relief. Where the special hazards of operation, sources of ignition, or exposures indicate a need, consideration should be given to providing protection by one or more of the above means.

See NFPA 68, *Guide for Venting of Deflagrations*, and NFPA 69, *Standard on Explosion Prevention Systems*, for additional information on various methods of mitigating losses from explosions.

A.5.4.2 Mist explosions have occurred when heat transfer fluid that is above its boiling point has been released in an enclosed area. Consideration should be given to locating heaters or vaporizers either in a detached building or in a room with damage-limiting construction.

A.5.4.3 The system should be interlocked to stop circulation of the heat transfer fluid through the system and to shut off the system heater or vaporizer in the event of a fire, abnormally low pressure in the system, or operation of an approved heat detection system. Where the refractory inside the heater or vaporizer can retain enough heat to cause either breakdown of the heat transfer fluid or tube fouling if fluid circulation through the unit is stopped, circulation could have to be continued. In the event of a confirmed fire, it is desirable to subdivide the piping system by means of interlocked safety shutoff valves. A practical way of accomplishing this is to isolate all secondary-circulating loops from the primary loop that runs into and out of the vaporizer or heater.

A well-marked remote emergency shutoff switch or electrical disconnect should be provided to shut down the entire system in the event of an emergency. This should be located either in a constantly attended location or at a location that would be accessible in the event of a leak or a fire.

If there are any process or utility lines running in or through rooms or areas containing parts of the heat transfer system, consideration should be given to providing emergency shutoff valves. They should be located so they are readily accessible in the event of a fire.

Where the liquid level in the system expansion tank is maintained by an automatically actuated supply pump taking suction from the heat transfer fluid storage tank, an interlock should be provided to shut down the supply pump when a high level indicator is actuated, regardless of whether the pump is in automatic or manual mode.

A.5.4.3.1 Heat transfer fluid (HTF) systems have the potential for releasing large quantities of heated flammable or combustible liquid. Low point drains piped to a safe location provide the ability to remove HTF from a breached piping system in order to minimize the total quantity of fluid released. An engineering analysis should be used to determine the location and design of low point drains. The engineering analysis should consider system inventory, the amount of HTF that can be released in a specific fire area, the exposure created by a release, and the fire protection provided.

A.5.4.3.2 Where possible, the storage tank(s) should be located below the lowest system drain opening to permit gravity flow. Breather vents should be provided based on the maximum emptying or filling rates.

A.5.4.4 If stack gas from a heater or vaporizer is recovered to provide auxiliary heat for other equipment (e.g., rotary dryers), suitable dampers, isolation gates, burner control logic, or other means should be provided to ensure that all equipment is properly purged and will operate in a safe manner. The control logic should anticipate all possible operating modes of the individual pieces of equipment, whether operating singly or together, to ensure safe startup and shutdown under normal or upset conditions.

Instrumentation and interlocks should be provided to sound an alarm and to automatically shut down the fuel source to the heater or vaporizer when any of the following conditions are detected:

- (a) Low flow of heat transfer fluid through the heat exchange tubes of the heater, as measured at the discharge.
- (b) High temperature or pressure of the fluid at the heater or vaporizer outlet. The high temperature interlock should be set at or below the manufacturer's maximum recommended bulk fluid temperature.
- (c) Low pressure at the heater or vaporizer outlet or elsewhere in the system. This interlock could require a bypass to allow for startup.
- (d) Low fluid level in the expansion tank.
- (e) Low liquid level in the vaporizer.
- (f) Sprinkler system flow in any area containing the heat transfer equipment or piping.

Alarm set points should be provided at levels below or above the automatic shutoff setpoints to monitor the above-mentioned variables and provide an opportunity for operators to correct the problem before conditions reach an unsafe level.

A.5.4.5.1 Where possible, piping should be run underground, outside, or in floor trenches. Overhead routing of heat transfer fluid piping should be minimized.

A.5.4.6.1 Historical records show that fires involving heat transfer fluids can be very severe and long lasting. It is recommended that automatic sprinkler or deluge protection be provided throughout all building areas potentially exposed to a heat transfer fluid spill fire.

A.5.4.7.1 Some factors that should be considered as part of such a review include the following:

(a) *Infiltration of material being heated into the heat transfer system.* In this case, the system should be shut down and the internal leak point found and repaired as soon as possible.

(b) *Leaks in the system.* Any leak should be corrected promptly regardless of how small. Corrections should be permanent, such as repacking valve stems and replacing leaky gaskets. Any heat transfer fluid released as a result of a leak or operation of a safety valve should be cleaned up immediately if it is or can come in contact with a hot surface. Other spills can be cleaned up at the first available opportunity.

(c) *Pipe or equipment insulation that is soaked with heat transfer fluid.* In this case, the cause of the leak should be corrected promptly and the insulation replaced with clean, dry insulation.

(d) *High temperature anywhere in the system.* In this case, operating procedures should specify shutdown of the heater or vaporizer fuel supply as soon as the temperature of the heat transfer fluid exceeds the manufacturer's recommended maximum bulk fluid temperature. Any corrective actions taken to correct a high temperature condition should only be done with the heat source shut off.

A.5.5.1 Incidental operations are operations that utilize liquids only as a limited activity to that which establishes the occupancy classification. Examples include automobile assembly, assembly of electronic equipment, furniture manufacturing, and areas within refineries, distilleries, and chemical plants where the use of liquids is incidental, such as in maintenance shops, office equipment, or vehicle repair shops. Some more detailed descriptions are given below:

(a) *Vehicle Assembly.* Vehicle assembly operations usually involve both process and incidental use of liquids. An example of a process operation would be paint storage and mixing utilized for application of the vehicle primer, color coats, and clear coats. For these operations, the requirements of Section 5.3 apply. Examples of incidental use would be sealer deck wipedown operations, windshield washer solvent dispensing, brake fluid filling, and final line paint repair operations. These operations might be continuous. However, the quantities of liquids used and the vapor exposures are significantly reduced from larger volume usage found within vehicle body component paint mixing and storage operations.

(b) *Assembly of Electrical Equipment.* Examples of incidental use of liquids in these types of occupancies could include wet etching operations in clean rooms, "photoresist" coating operations, "softbaking" operations, wave solder operations, and wipedown operations.

(c) *Chemical Plant Maintenance Shop.* Incidental use of liquids is commonplace in maintenance shops located within a chemical plant. Examples are cutting oils used in a machine shop, Class II solvents for degreasing, and Class I and II paint solvents and fuels associated with automotive and industrial truck repair.

(d) *Cleaning and Sanitation.* Under provisions established by the U.S. Food and Drug Administration (FDA) in 21 *CFR*, "GMP for Medical Devices," Class I and Class II liquids can be used for cleaning and sanitation purposes. Limited quantities are used to remove manufacturing materials, mold release compounds, and other contaminants not intended to be on the final product. An example would be the use of isopropyl alcohol (IPA), transferred to a cleaning wipe via a plunger-type liquid-dispensing container. The cleaning wipe is then used to remove manufacturing materials not intended to be on the final product. The key point here is not that the liquid is not part of the final product, but that limited quantities of liquid are used and the use is incidental to the manufacturing operation that produces the product.

A.5.5.5(3) NFPA 91, *Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists, and Noncombustible Particulate Solids*, provides information on the design and installation of mechanical ventilation.

A.5.6.3 Use of fixed fire protection systems, dikes, fire-rated barriers, or a combination of any of these can provide suitable protection from exposures.

A.5.6.4 The intent of this requirement is to prevent the spread of uncontrolled, spilled liquid from traveling beyond the loading or unloading area and exposing surrounding equipment and buildings.

A.5.6.6 The use of nonconductive materials in the fill pipe assembly should be avoided to prevent any electrical discontinuity in the piping of the system. Serious accidents have occurred when nonconductive materials, such as plastic or rubber hose, have been used in the fill pipe assembly.

A.5.6.10.4 NFPA 77, *Recommended Practice on Static Electricity*, provides additional information on protection against static electricity.

A.5.6.11.2 NFPA 77, *Recommended Practice on Static Electricity*, provides additional information on static electricity protection.

A.5.6.12 The term *switch loading* describes a situation that warrants special consideration.

When a tank is emptied of a cargo of Class I liquid, a mixture of vapor and air is left, which can be, and often is, within the flammable range. When such a tank is refilled with a Class I liquid, any charge that reaches the tank shell will be bled off by the required bond wire. Also, there will be no flammable mixture at the surface of the rising oil level because the Class I liquid produces at its surface a mixture too rich to be ignitable. This is the situation commonly existing in tank vehicles in gasoline service. If, as occasionally happens, a static charge does accumulate on the surface sufficient to produce a spark, it occurs in a too-rich, nonignitable atmosphere and thus causes no harm.

A very different situation arises if the liquid is "switch loaded," that is, when a Class II or Class III liquid is loaded into a tank vehicle that previously contained a Class I liquid.

Class II or Class III liquids are not necessarily more potent static generators than the Class I liquid previously loaded, but the atmosphere in contact with the rising oil surface is not enriched to bring it out of the flammable range. If circumstances are such that a spark should occur either across the oil surface or from the oil surface to some other object, the spark occurs in a mixture that can be within the flammable range, and an explosion can result.

It is emphasized that bonding the tank to the fill stem is not sufficient; a majority of the recorded explosions have occurred when it was believed the tank had been adequately bonded. The electrostatic potential that is responsible for the spark exists inside the tank on the surface of the liquid and cannot be removed by bonding. Measures to reduce the change of such internal static ignition can be one or more of the following:

(a) Avoid spark promoters. Conductive objects floating on the oil surface increase the charge of sparking to the tank wall. Metal gauge rods or other objects projecting into the vapor space can create a spark gap as the rising liquid level approaches the projection. A common precaution is to require that fill pipes (downspouts) reach as close to the bottom of the tank as practicable. Any operation such as sampling, taking oil temperature, or gauging that involves lowering a conductive object through an opening into the vapor space on the oil should be deferred until at least 1 minute after flow has ceased. This will permit any surface charge to relax.

(b) Reduce the static generation by one or more of the following:

- (1) Avoid splash filling and upward spraying of oil where bottom filling is used.
- (2) Employ reduced fill rates at the start of filling through downspouts, until the end of the spout is submerged. Some consider 3 ft (0.914 m) per sec to be a suitable precaution.
- (3) Where filters are employed, provide relaxation time in the piping downstream from the filters. A relaxation time of 30 seconds is considered by some to be a suitable precaution.

(c) Eliminate the flammable mixture before switch loadings by gas freeing or inerting.

See NFPA 77, *Recommended Practice on Static Electricity*, and NFPA 385, *Standard for Tank Vehicles for Flammable and Combustible Liquids*, for further information.

A.5.7.19 Where practical, the collection basin should be drained to a remote location.

A.5.7.21 Because of the many variables involved, exact requirements cannot be provided. However, Table A.5.7.21 provides guidance on the level of fire protection typically provided at wharves and marine terminals handling flammable liquids.

A.5.9.3 See NFPA 51B, *Standard for Fire Prevention During Welding, Cutting, and Other Hot Work*.

A.5.9.4 The prevention of electrostatic ignition in equipment is a complex subject. Refer to NFPA 77, *Recommended Practice on Static Electricity*, for guidance.

A.5.10.5 If the liquid knock-out vessel utilizes a pump for automatic liquid removal, consideration should be given to a low-level alarm and shut down to avoid running the pump dry, resulting in a potential source of ignition.

A.5.10.7.2 Electrical enclosures that need to be opened frequently for maintenance (i.e., enclosures housing vapor processing system controls) have a higher potential for mechanical damage that could render the enclosures unable to contain an explosion. Additional inspection could be needed to ensure the integrity of the enclosure.

A.5.10.7.3 The most recent edition of API 2003, *Protection Against Ignition Arising Out of Static, Lightning, and Stray Currents*, can be used as a reference for protections against static ignition.

Table A.5.7.21 Typical Fire Protection for Wharves and Marine Terminals

	Water Demand (gpm)	Hydrant Monitors ^a (gpm)	Hose Reels	Fire Extinguisher Dry Chemical		International Shore Connection	Emergency Equipment Lockers	Monitors and Hose Foam Concentrate Required (gal)	
				30 lb	150 lb Wheeled			Fire Boat Connection	
Barge terminals	500–1000	Two 500	Two 1 ¹ / ₄	2	NR	NR	1	100 ^b	NR
Tanks	1000–2000	Two 500	Two 1 ¹ / ₄	2	1	1	1	300 ^b	2
20,000 DWT and under									
20,001–70,000 DWT	2000	Two 1000	Four 1 ¹ / ₄ ^c	2	2 ^d	2	1	2000	2
70,001 DWT and over	2000 ^e	Two 1000	Four 1 ¹ / ₄ ^c	3	2 ^d	2	1	2000 ^f	2
Sea islands	2000–4000 ^e	Three 1000	Four 1 ¹ / ₄ ^c	4	2	3	2	3000	2

For SI units, 1 gpm = 3.8 L/min; 1 gal = 3.8 L; 1 lb = 0.45 kg.

NR = not required.

^aA minimum of two 1¹/₂-in. hydrant outlets should be provided at each monitor riser.

^bCan be provided by onshore mobile equipment.

^cOne hose reel at each berth should have foam capability.

^dThe proximity of adjacent berths can reduce total required.

^eUnder-dock systems are optional. Add water for under-dock system (0.16 × area).

^fUnder-dock systems are optional. Add foam for under-dock system (0.16 × 0.3 × 30 × area).

A.5.10.7.4 Spontaneous ignition can be a problem in the following:

(a) Facilities where pyrophoric deposits can accumulate from the handling of oxygen-deficient vapors containing sulfur compounds or asphaltic materials. When air is introduced into the system, the pyrophoric materials can react, resulting in potential ignition and fire.

(b) Facilities that handle fluids in such a way that mixing of hypergolic or otherwise incompatible materials can occur. Such mixing could occur with fluids remaining in the vapor recovery system from prior loading activities.

(c) Facilities handling oxygenated hydrocarbons in carbon absorption units. Higher heats of absorption for these types of vapors can potentially lead to overheated carbon beds and increase the chance that an oxidation reaction can be initiated. (For further information, refer to API Report, "An Engineering Analysis of the Effects of Oxygenated Fuels on Marketing Vapor Recovery Equipment.")

A.5.10.7.5 Department of Transportation Coast Guard Regulation of the 33 *CFR* 154, Section 154.826(b), (c), and (d) can be used as a reference for vapor mover designs that minimize the potential for ignition.

A.5.10.7.6 The potential for ignition in the vapor collection system needs to be evaluated on a case-by-case basis.

If ignition occurs, flame propagation in piping systems containing vapor mixtures in the flammable range normally starts with low-speed burning (deflagration). As the flame moves through the piping, it accelerates and, within a short distance, can reach supersonic speeds (detonation). Initial low-speed flame propagation can be stopped by flame arresters, liquid seals, or automatic fast-acting valve systems where designed, operated, and tested within the requirements of NFPA 69, *Standard on Explosion Prevention Systems*. Flame propagation can also be stopped for both deflagrations and detonations by use of detonation arresters tested in accordance with U.S. Department of Transportation Coast Guard Regulations of the 33 *CFR* 154, Appendix A, or other procedures acceptable to the authority having jurisdiction, or automatic fast-acting valve systems tested under the appropriate conditions.

A.5.13.1.1 Other recognized fire prevention and control factors, involving construction, location, and separation, are addressed elsewhere in this chapter.

A.5.13.1.2 The wide range in size, design, and location of liquid-processing facilities precludes the inclusion of detailed fire prevention and control systems and methods applicable to all such facilities.

A.5.13.2.1 NFPA 10, *Standard for Portable Fire Extinguishers*, provides information on the suitability of various types of extinguishers.

A.5.13.3.2 See NFPA 24, *Standard for the Installation of Private Fire Service Mains and Their Appurtenances*, for information on this subject.

A.5.13.3.3 See NFPA 13, *Standard for the Installation of Sprinkler Systems*, and NFPA 15, *Standard for Water Spray Fixed Systems for Fire Protection*, for information on these subjects.

A.6.2.2 For additional information, see NFPA 497, *Recommended Practice for the Classification of Hazardous (Classified) Locations for Electrical Installations in Chemical Process Areas*.

A.6.2.4 NFPA 496, *Standard for Purged and Pressurized Enclosures for Electrical Equipment*, provides details for these types of installations.

Appendix B Emergency Relief Venting for Fire Exposure for Aboveground Tanks

This appendix is not a part of the requirements of this NFPA document but is included for informational purposes only.

B.1 General. The requirements for emergency venting given in Table 2.2.5.2.3 and the modification factors in 2.2.5.2.6 are derived from a consideration of the following:

- (1) Probable maximum rate of heat transfer per unit area
- (2) Size of tank and the percentage of total area likely to be exposed
- (3) Time required to bring tank contents to boil
- (4) Time required to heat unwet portions of the tank shell or roof to a temperature where the metal will lose strength
- (5) Effect of drainage, insulation, and the application of water in reducing fire exposure and heat transfer

B.2 Derivation of Table 2.2.5.2.3. Table 2.2.5.2.3 is based on a composite curve (see Figure B.2) that is composed of three straight lines when plotted on log-log graph paper. The curve can be defined in the following manner:

(a) The first straight line is drawn between the points 400,000 Btu/hr, at 20 ft² (1.858 m²) exposed surface area, and 4,000,000 Btu/hr, at 200 ft² (18.58 m²) exposed surface area. The equation for this portion of the curve is $Q = 20,000A$.


(b) The second straight line is drawn between the points 4,000,000 Btu/hr, at 200 ft² (18.58 m²) exposed surface area, and 9,950,000 Btu/hr, at 1000 ft² (92.9 m²) exposed surface area. The equation for this portion of the curve is $Q = 199,300A^{0.566}$.

(c) The third straight line is drawn between the points 9,950,000 Btu/hr, at 1000 ft² (92.9 m²) exposed surface area, and 14,090,000 Btu/hr, at 2800 ft² (260.12 m²) exposed surface area. The equation for this portion of the curve is $Q = 963,400A^{0.338}$.

The data for plotting the three lines are given in Table B.2.

Table B.2 Data for Figure B.2

$Q = 20,000A$		$Q = 199,300A^{0.566}$		$Q = 963,400A^{0.338}$	
A	Q	A	Q	A	Q
20	400,000	200	4,000,000	1000	10,000,000
30	600,000	250	4,539,000	1200	10,593,000
40	800,000	300	5,032,000	1400	11,122,000
50	1,000,000	350	5,491,000	1600	11,601,000
60	1,200,000	400	5,922,000	1800	12,040,000
70	1,400,000	500	6,719,000	2000	12,449,000
80	1,600,000	600	7,450,000	2400	13,188,000
90	1,800,000	700	8,129,000	2800	14,000,000
100	2,000,000	800	8,768,000	and over	
120	2,400,000	900	9,372,000		
140	2,800,000	1000	10,000,000		
160	3,200,000				
180	3,600,000				
200	4,000,000				

FIGURE B.2 Curve for determining requirements for emergency venting during fire exposure.

For SI units, 1 ft² = 0.09 m².

Note: See Table B.4 for approximate wetted area for horizontal tanks.

B.2.1 For areas exceeding 2800 ft² (260.12 m²) it has been concluded that complete fire involvement is unlikely, and loss of metal strength from overheating will cause failure in the vapor space before development of maximum possible vapor evolution rate. Therefore, additional venting capacity beyond the vapor equivalent of 14,090,000 Btu/hr (4130 kw) will not be effective or required.

B.2.2 For tanks and storage vessels designed for pressures over 1 psig (gauge pressure of 6.89 kPa), additional venting for exposed surfaces beyond 2800 ft² (260.12 m²) is believed to be desirable because, under these storage conditions, liquids are stored close to their boiling points. Therefore, the time to bring the container contents to boiling conditions is not necessarily significant. For these situations, a heat input value should be determined on the basis of

$$Q = 21,000A^{0.82}$$

B.3 Venting Requirements for Specific Liquids. The flow capacities estimated in Section B.2 are based on the assumption that the stored liquid will have the characteristics of hexane, and the vapor liberated has been transposed to equivalent free air at 60°F (15.6°C) and 14.7 psia (101.3 kPa) by using appropriate factors in

$$CFH = \frac{70.5Q}{L\sqrt{M}}$$

where:

CFH = cubic feet of free air per hour

70.5 = factor for converting pounds of gas to ft³ of air

Q = total heat input per hour (Btu)

L = latent heat of vaporization

M = molecular weight

No consideration has been given to possible expansion from the heating of the vapor above the boiling point of the liquid, its specific heat, or the difference in density between the discharge temperature and 60°F (15.6°C), since some of these changes are compensating.

Because tank vent valves are ordinarily rated in CFH standard air, the figures derived from Table 2.2.5.2.3 can be used with the appropriate tank pressure as a basis for valve selection.

Table B.3 gives constants that can be used to compute the vapor generated and equivalent free air for liquids other than hexane, where greater exactness is desired. Inspections of the table will show that the use of hexane in deriving Table 2.2.5.2.3 provides results that are within an acceptable degree of accuracy for the listed liquids.

Table B.3 Values of $L\sqrt{M}$ for Various Flammable Liquids

Chemical	$L\sqrt{M}$	Molecular Weight	Heat of Vaporization Btu/lb at Boiling Point
Acetaldehyde	1673	44.05	252
Acetic acid	1350	60.05	174
Acetic anhydride	1792	102.09	177
Acetone	1708	58.08	224
Acetonitrile	2000	41.05	312
Acrylonitrile	1930	53.06	265
n-Amyl alcohol	2025	88.15	216
iso-Amyl alcohol	1990	88.15	212
Aniline	1795	93.12	186
Benzene	1493	78.11	169
n-Butyl acetate	1432	116.16	133
n-Butyl alcohol	2185	74.12	254
iso-Butyl alcohol	2135	74.12	248
Carbon disulfide	1310	76.14	150
Chlorobenzene	1422	112.56	134
Cyclohexane	1414	84.16	154
Cyclohexanol	1953	100.16	195
Cyclohexanone	1625	98.14	164
o-Dichlorobenzene	1455	147.01	120
cis-Dichloroethylene	1350	96.95	137
Diethylamine	1403	73.14	164
Dimethylacetamide	1997	87.12	214
Dimethylamine	1676	45.08	250
Dimethylformamide	2120	73.09	248
Dioxane (diethylene ether)	1665	88.10	177
Ethyl acetate	1477	88.10	157
Ethyl alcohol	2500	46.07	368
Ethyl chloride	1340	64.52	167
Ethylene dichloride	1363	98.96	137
Ethyl ether	1310	74.12	152
Furan	1362	68.07	165
Furfural	1962	96.08	200
Gasoline	1370-1470	96.0	140-150
n-Heptane	1383	100.20	138
n-Hexane	1337	86.17	144
Hydrogen cyanide	2290	27.03	430
Methyl alcohol	2680	32.04	474
Methyl ethyl ketone	1623	72.10	191
Methyl methacrylate	1432	100.14	143
n-Octane	1412	114.22	132
n-Pentane	1300	72.15	153
n-Propyl acetate	1468	102.13	145
n-Propyl alcohol	2295	60.09	296
iso-Propyl alcohol	2225	60.09	287
Tetrahydrofuran	1428	72.10	168
Toluene	1500	92.13	156
Vinyl acetate	1532	86.09	165
o-Xylene	1538	106.16	149

For SI units, 1 Btu/lb = 2.3 kJ/kg.

Note: For data on other chemicals refer to available handbooks on properties of chemicals.

B.4 Estimation of Wetted Area for Horizontal Tanks. Table B.4 gives the approximate wetted area for various sizes and configurations of horizontal tanks with flat heads, based on 75 percent of total shell area.

Table B.4 Appropriate Wetted Areas for Horizontal Tanks with Flat Heads (Wetted Area Equals 75% Total Area)

Tank Length (ft)	Tank Diameter (ft)										
	3	4	5	6	7	8	9	10	11	12	
3	32										
4	39	55									
5	46	65	88								
6	53	74	100	128							
7	60	84	112	142	173						
8	67	93	124	156	190	226					
9	74	102	136	170	206	245	286				
10	81	112	147	184	223	264	308	353			
11	88	121	159	198	239	283	329	377	428		
12	95	131	171	213	256	301	350	400	454	509	
13	102	140	183	227	272	320	371	424	480	537	
14	109	150	194	241	289	339	393	447	506	565	
15	116	159	206	255	305	358	414	471	532	594	
16	123	169	218	269	322	377	435	495	558	622	
17	130	178	230	283	338	395	456	518	584	650	
18	137	188	242	298	355	414	477	542	610	678	
19		197	253	312	371	433	499	565	636	707	
20		206	265	326	388	452	520	589	662	735	
21		216	277	340	404	471	541	612	688	763	
22		225	289	354	421	490	562	636	714	792	
23		235	300	368	437	508	584	659	740	820	
24		244	312	383	454	527	605	683	765	848	
25			324	397	470	546	626	706	791	876	
26			336	411	487	565	647	730	817	905	
27			347	425	503	584	668	754	843	933	
28			359	440	520	603	690	777	869	961	
29			371	454	536	621	711	801	895	989	
30			383	468	553	640	732	824	921	1018	
31			395	482	569	659	753	848	947	1046	
32				496	586	678	775	871	973	1074	
33				510	602	697	796	895	999	1103	
34				524	619	715	817	918	1025	1131	
35				539	635	734	838	942	1051	1159	
36				553	652	753	860	966	1077	1187	

Table B.4 Appropriate Wetted Areas for Horizontal Tanks with Flat Heads (Wetted Area Equals 75% Total Area) (Continued)

Tank Length (ft)	Tank Diameter (ft)										
	3	4	5	6	7	8	9	10	11	12	
37				567	668	772	881	989	1103	1216	
38					685	791	902	1013	1129	1244	
39					701	810	923	1036	1155	1272	
40					718	828	944	1060	1181	1301	
41					734	847	966	1083	1207	1329	
42					751	866	987	1107	1233	1357	
43					767	885	1008	1130	1259	1385	
44						904	1029	1154	1284	1414	
45						923	1051	1178	1310	1442	
46						941	1072	1201	1336	1470	
47						960	1093	1225	1362	1498	
48						979	1114	1248	1388	1527	
49						998	1135	1272	1414	1555	
50							1157	1295	1440	1583	
51							1178	1319	1466	1612	
52							1199	1342	1492	1640	
53							1220	1366	1518	1668	
54							1246	1389	1544	1696	
55							1263	1413	1570	1725	
56								1437	1593	1753	
57								1460	1622	1781	
58								1484	1648	1809	
59								1507	1674	1839	
60								1531	1700	1866	
61									1726	1894	
62									1752	1923	
63									1778	1951	
64									1803	1979	
65									1829	2007	
66									1855	2036	
67										2064	
68										2092	
69										2120	
70										2149	
71										2177	
72										2205	

For SI units, 1 ft = 0.3 m; 1 ft² = 0.09 m².

Appendix C Temporarily Out of Service, Closure in Place, or Closure by Removal of Underground Tanks

This appendix is not a part of the requirements of this NFPA document but is included for informational purposes only.

C.1 Introduction.

C.1.1 Care is required not only in the handling and use of flammable or combustible liquids but also in the process of rendering temporarily out of service, closing, or removing tanks that have held flammable or combustible liquids. This is particularly true of underground service station tanks that are most frequently used for the storage of motor fuel and occasionally for the storage of other flammable or combustible liquids, such as crankcase drainings, which can contain some gasoline. Through carelessness, explosions have occurred because flammable or combustible liquid tanks have not been properly conditioned before being rendered temporarily out of service, closed, or removed.

C.1.2 In order to prevent accidents caused by improper conditioning, it is recommended that the procedures outlined in this appendix be followed when underground tanks are temporarily taken out of service, closed, or removed.

C.1.3 Underground tanks taken out of service can be safeguarded or disposed of by any one of the following three means:

(a) Placement in a temporarily out-of-service condition. Tanks should be rendered temporarily out of service only when it is planned that they will be returned to active service within a reasonable period or pending closure in place or closure by removal.

(b) Permanent closure in place, with proper safeguarding.

(c) Permanent closure by removal.

C.1.4 In cases where tanks are either rendered temporarily out of service or permanently closed, records should be kept of tank size, location, date of closure, and method used for placing the closed tank in a safe condition.

C.1.5 Procedures for carrying out each of the methods in C.1.3 of disposing of underground tanks are described in the following sections. No cutting torch or other flame- or spark-producing equipment should be used until the tank has been completely purged or otherwise rendered safe. In each case, the steps given should be carried out successively.

C.2 Rendering Tanks Temporarily Out of Service.

C.2.1 When the underground storage tank system (UST) is temporarily out of service for less than 3 months, the owners and operators should comply with the following:

(a) Continue operation and maintenance of corrosion protection. Requirements can be found in U.S. Environmental Protection Agency (EPA), 40 *CFR* 280, "Technical Standards and Requirements for Owners and Operators of Underground Storage Tanks," Paragraph 280.31.

(b) Continue operation and maintenance of any release detection in accordance with U.S. EPA, 40 *CFR* 280, Subpart D, or empty the UST system by removing all materials so that no more than 1 in. (25 mm) of residue, or 0.3 percent by weight of the total capacity of the UST system, remains in the system.

C.2.2 When a UST system is temporarily out of service for 3 months or more, owners and operators should also comply with the following requirements:

- (1) Leave vent lines open and functioning
- (2) Cap or plug all other lines such as fill line, gauge opening, pump suction, and ancillary equipment and secure against tampering

C.3 Permanent Closure. When a UST system is temporarily closed for more than 12 months, owners and operators should permanently close the UST system in accordance with U.S. EPA, 40 *CFR* 280.71–280.74. An extension of this 12-month period can be granted by the implementing agency. However, before such an extension can be applied for, a site assessment should be completed in accordance with U.S. EPA, 40 *CFR* 280.72.

C.4 Closure of Underground Tanks in Place.

C.4.1 At least 30 days before beginning closure procedures, owners and operators should notify the implementing agency of their intent to close unless such action is in response to corrective action proceedings.

C.4.2 Closure of tanks either in place or by removal requires the owners and operators to measure for the presence of a release where contamination is most likely to be present at the UST site. This requirement can be satisfied if one of the external release detection methods allowed in 40 *CFR* 280.43(e) and (f) is operating in accordance with the requirements in Part 280.43 at the time of closure and indicates no release has occurred.

C.4.3 Prepare a safe workplace by following the special safety precautions and cleaning and closure procedures in either of the following documents:

- (1) API 1604, *Removal and Disposal of Used Underground Petroleum Storage Tanks*
- (2) NEIWPCC, *Tank Closure Without Tears: An Inspector's Safety Guide*

C.4.4 Safe work preparation should include the following:

- (a) No smoking in the area.
- (b) Shutting down all open flame and spark-producing equipment not necessary for the removal of the underground tank.
- (c) Using only hand tools to expose tank fittings and preparing for the vapor-freeing procedures.
- (d) Controlling static electricity or providing a conductive path to discharge static electricity by bonding or grounding equipment and vehicles.
- (e) Roping off tank area from pedestrian and vehicular traffic.
- (f) Locating and marking all utility lines on site.
- (g) Determining meteorological conditions. Vapor accumulation can occur on still and high-humidity days. Under these conditions, test the area for vapor accumulation (*refer to C.4.10*) and if present either provide additional forced ventilation or delay the job until there is a breeze and it is less humid. Excavated soil should be tested for vapor release. Artificial ventilation or repeated turning of excavated soil might be necessary to avoid ignitable concentration of vapors.
- (h) Ensuring that personnel are wearing hard hats, safety shoes, and safety glasses and that a combustible gas indicator is available. Providing any other safety measures or methods that might be required to meet local requirements.

C.4.5 Remove all flammable or combustible liquid and residue from the tank and from all connecting lines.